

STORMWATER MANAGEMENT REPORT

Presented to:

Wal-Mart Canada Corp.

Thursday December 9, 2004

Prepared For:

Plaza BNG Inc. 50 Tacoma Drive, Unit 18 Dartmouth, Nova Scotia B2W 3E5

Telephone No.: (902) 468-8688 Facsimile No.: (902) 468-9446

Prepared By:

Stantec Consulting Ltd. 7270 Woodbine Avenue Suite 300 Markham, Ontario L3R 4B9

Telephone No.: (905) 474-0455 Facsimile No.: (905) 474-9889

File No.: 606 20063



STORMWATER MANAGEMENT DESIGN BRIEF

Yarmouth – NS Wal-Mart Development Starrs Road & Highway 101

Yarmouth, Nova Scotia December 3rd, 2004

Prepared For:

Plaza BNG Inc. 50 Tacoma Drive, Unit 18 Dartmouth, Nova Scotia B2W 3E5

Telephone No.: (902) 468-8688 Facsimile No.: (902) 468-9446

Prepared By:

Stantec Consulting Ltd. 7270 Woodbine Avenue Suite 300 Markham, Ontario L3R 4B9

Telephone No.: (905) 474-0455 Facsimile No.: (905) 474-9889

File No.: 60620063

1st Submission Date: February 20, 2004 2nd Submission Date: April 15, 2004

Revised: December 9, 2004

Mr. Bryce Schnare
Plaza BNG Inc.
50 Tacoma Drive, Unit 18
Dartmouth, Nova Scotia
B2W 3E5

Dear Mr. Schnare,

Re: Stormwater Management Design Brief

Proposed Commercial Development

Starrs Road & Highway 101 Yarmouth, Nova Scotia

This third submission is for your review for approval for the development of a Wal-Mart in the Town of Yarmouth, Nova Scotia. The stormwater design brief was prepared to finalize the detailed SWM design.

Included in this submission, for your review and approval, are the following:

- Drawings (SW2, SW3, ESC, D1, Figure 1, Figure 2, and Figure 3);
- **Design brief**; and
- Appendix A (Allowable Release Rate Calculations)
- Appendix B (Control Details)
- Appendix C (Modified Rational Storage Calculations)
- Appendix D (External Drainage)
- Appendix E (SWMHYMO Drainage Analysis)
- Appendix F (Stormceptor Sizing Tool Results)

INTRODUCTION

This design brief summarizes how the proposed design will meet the stormwater management (SWM) quantity and quality control requirements for the proposed Wal-Mart development. The site is located NE of Starrs Road and Highway 101, in the Town of Yarmouth ('the Town'), Nova Scotia (please refer to **Figure 1**). It is currently undeveloped and has a total area of approximately 4.40 hectares (please refer to **Figures 1 and 2**). **Figure 2** illustrates the SWM Plan.

RELEASE RATES

The Town of Yarmouth has requested that no adverse impact occurs as a result of this development. We addressed this request as per the following:

- No increase in peak flows from the site for all storms, up to and including the 100year storm;
- Allow for sufficient capacity of the drainage feature conveying external flows; and
- Implement SWM practices so that no improvements will be required to the existing culverts crossing Starrs Road.

Based on the above, it is proposed to control 5-year post development flow to existing 2-year flow, and to control the 100-year post development flow to 100-year existing flow. The existing flows for the 2-year, 5-year and 100-year design storms from the site are provided in **Table 1** (please refer to **Appendix A**).

Table 1 - Existing Flows
Proposed Commercial Development - Starrs Road & Highway 101

Scenario	Area ¹	Peak Flow Rates (L/s)		
	(ha)	2-year ²	5-year ²	100-year ³
Existing	3.86	166	216	554

Notes:

The actual site area is 4.40 ha, although 3.86 ha of the total site area is being developed at this time.

On-site detention storage will be provided to ensure that post development flows for the 5-year and 100-year design storms will be less than or equal to the existing flows from the site. The proposed post development site flows are provided in **Table 2** (please refer to **Appendices B** and **C**).

Table 2 - Post Development Flows
Proposed Commercial Development - Starrs Road & Highway 101

Scenario	Area 1	Peak Flow F	Rates (L/s)
	(ha)	5-year	100-year ³
Post-Development ²	3.86	166	275

Notes: (continued from Table 1)

Calculated utilizing the modified rational method.

Overland spill conveyed to downstream ditch via a weir located at the SE end of parking lot. This spill control is designed to meet the 100-year allowable release rate.

QUANTITY CONTROL

Pipe storage, parking lot storage and rooftop detention storage will be utilized to attenuate the proposed flow to the existing release rates.

Rooftop Storage

Rooftop control will be provided via installation of roof drain weirs on Building A (Zurn or approved equivalent, see details in **Appendix B**). The roof drains will meet the following requirements:

- The total roof runoff rate will be restricted to a maximum release rate of 42 L/s/ha of rooftop during the 100-year event;
- The maximum ponding depth will be 0.10 m; relief scuppers will be built in the parapet walls to eliminate any ponding above this depth; and,
- The roof drains will discharge to the proposed site sewer system.

Parking Lot Storage

Ponding in parking lot areas will be limited to a maximum depth of 0.3 m above the catchbasins. Ponding elevations for the 100-year storm event are displayed on **Figure 2**. Storage requirements for the 100 and 5-year storms were generated utilizing the Modified Rational Method (refer to **Appendix C**).

Along with surface storage (ponding), pipe storage will be utilized using orifice controls. For minor flows, the orifice plate ensures that the release rate from the site to the downstream ditch meets the existing release rate (please refer to details in **Appendix A**). For major flows, a combination of the orifice plate and weir ensures the release rate from the site into the downstream ditch meets the existing release rate. The proposed locations for the orifice plates and weir controls are illustrated on **Figure 2**. An orifice plate (#1) located in MH22 will control the release rate for minor events into the downstream ditch. Another small area (0.13 ha) at the west end of the proposed parking lot will be controlled for major events only using an orifice plate (#2) at the east invert of CB26, discharging into the culvert conveying external flows.

Tables 3, and **4** outline the storage requirements and release rates for the 100-year and 5-year design storms, respectively. Detailed calculations for these controls can be found in **Appendix B**.

Table 3 **Proposed Release Rates and Storage Requirements** 5-year Storm

Outlet ID	Area ID	Drainage Area (ha)	Release Rate ¹ (m ³ /s)	Storage Required (m³)	Storage Available (m³)	Orifice Location	Orifice Type	Ponding Depth (m)	Orifice Size ² (mm)	Draw Down ³ (min)
1	101	0.88	0.018 4	224	264 ⁵	-	Roof	0.10	-	N/A
	102	2.85	0.122	475	472	MH22	Vertical Plate	0.3	195	0
	103	0.13	0.026	0	1	CB26	Vertical Plate	0.3	100	0
Total (1)	-	3.86	0.166	699	748	-	-	-	-	-

¹As per Model/Modified Rational Calculations (refer to Appendix C)
² See Appendix B for orifice plate details
³ Draw down time calculated based on surface storage only
⁴ Rooftop control = 42/2 = 21 L/s/ha
⁵ Available rooftop storage estimated using 3 cm depth over entire roof area

Table 4 **Proposed Release Rates and Storage Requirements** 100-year Storm

Outlet ID	Area ID	Drainage Area (ha)	Release Rate ^{1,2} (m ³ /s)	Storage Required (m³)	Storage Available (m³)	Orifice Location	Orifice Type	Ponding Depth (m)	Orifice Size ³ (mm)	Draw Down ⁴ (min)
1	101	0.88	0.037 5	333	528 ⁶	-	Roof	0.10	-	N/A
	102 ⁷	2.85	0.203	774	1035	MH22	Vertical Plate	0.3	195	34
	103	0.13	0.034	7	47	CB26	Vertical Plate	0.3	100	3
Total (1)	-	3.86	0.275 ⁷	1136	1818	-	-	-	-	-

Note: ¹As per Model/Modified Rational Calculations (refer to Appendix C)

² Combined orifice and weir controls provided
³ See Appendix B for orifice plate details
⁴ Draw down time calculated based on surface storage only

Rooftop control = 42 L/s/ha
 Available rooftop storage estimated using 6cm depth over entire roof area
 On-site control flow using orifice plates at 100-year W.L. before weir control is activated

Grading

Parking lot grades range from 1.17 % to 3.46 % to promote efficient drainage. Existing elevations at the west border of the site (adjacent Loblaws development) will be maintained. The finished floor elevation for the building is set to promote drainage away from the building.

On-site grading has been designed to provide major overland flow relief to the downstream ditch through a weir incorporated into the curb at the southern parking lot boundary (please refer to **Appendix B**). Overland flow routes are shown on **Figure 2**.

EXTERNAL DRAINAGE

Two 1200 mm storm sewers legs (referred to as the 'proposed culverts') will replace the existing ditch on the proposed site (please refer to **Figure 2**). The proposed culverts will discharge into the existing ditch downstream of the site, which drains to two culverts under Starrs Road.

The proposed culverts were sized to convey existing external 100-year flows (please refer to **Appendix D**) to the existing downstream ditch. The sizing of the culverts assumes that there will be no future development upstream in the Broad Brook watershed area, or that the developed areas will provide on-site controls to match pre development flow rates for all storms.

A drainage analysis has also been performed to address the Town's concerns regarding the impact of the proposed development on the Broad Brook watercourse system (please refer to **Appendix E**). The calculated external drainage flows are in good agreement with the information presented in the Town of Yarmouth Stormwater Management Plan prepared by Beasy Nicoll Engineering Ltd. in August of 1995.

In conclusion, the proposed commercial development will not have any negative impacts on the downstream culverts and will meet the allowable peak flow release rates for the 2-year, 5-year and 100-year storms.

QUALITY CONTROL

Quality control will be provided for the site to reduce the sediment loading into the receiving ditch, and to prevent oil and floating pollutants from leaving the site. A Stormceptor was sized using Stormceptor Sizing Tool Version 4.0.0 to remove a minimum of 70% of TSS (refer to **Appendix F** for results). **Table 5** illustrates the size and location of the proposed oil/grit separator.

Table 5 - Stormceptor® Sizing

Stormceptor	Drainage	Impervious	Controlled 5-year	Type of	% TSS
Manhole	Area ¹	Drainage	Release Rate	Stormceptor [®]	Removal
Location	(ha)	Area (ha)	(L/s)		
D/S MH25	3.08	2.77	186	STC1500	70

Note:

We trust the information provided will assist you in completing your review of the SWM for this site. Should you require any additional information, please contact the undersigned.

Yours very truly,

STANTEC CONSULTING LIMITED


Walter Toth, MBA, P.Eng. Principal

Serge Ristic, P.Eng. (Ontario) Senior Water Resources Engineer

c. Stantec - Steve Auger, Tanya Gibson

Encl.

¹ Drainage Area does not include clean flow from roof.



PROPOSED COMMERCIAL DEVELOPMENT STARRS ROAD AND HIGHWAY 101 YARMOUTH, NOVA SCOTIA



Project No.:

STANTEC CONSULTING LTD.


7270 WOODBINE AVE., SUITE 300 MARKHAM, ONTARIO L3R 4B9 TELEPHONE: (905) 474-0455 FAX: (905) 474-9889


SITE LOCATION PLAN

Date : FEBRUARY 20th, 2004 Scale : NTS

FIGURE

606 20063








STANTEC CONSULTING LTD.


7270 WOODBINE AVE., SUITE 300 MARKHAM, ONTARIO L3R 4B9 TELEPHONE: (905) 474–0455 FAX: (905) 474–9889

COMMERCIAL DEVELOPMENT POST-DEVELOPMENT DRAINAGE BOUNDARIES

APRIL 15th, 2004 Scale :

606 20063





1. ALL WORK SHALL BE CARRIED OUT IN COMPLIANCE WITH THE APPLICABLE HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS. 2. ALL WORK AND MATERIALS TO CONFORM WITH CURRENT MINISTRY OF THE ENVIRONMENT & ENERGY OF NOVA SCOTIA, TOWN OF YARMOUTH, NOVA SCOTIA PROVINCIAL STANDARDS AND SPECIFICATIONS. LOCAL UTILITY STANDARDS AND MINISTRY OF TRANSPORTATION STANDARDS

3. THE CONTRACTOR IS ADVISED THAT WORKS BY OTHERS MAY BE ONGOING DURING THE PERIOD OF THIS CONTRACT. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH ALL OTHER CONTRACTORS AND PREVENT CONSTRUCTION CONFLICTS.

4. THE INFORMATION SHOWN FOR EXISTING UTILITIES WAS PROVIDED BY OTHERS. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING AND PROTECTING ALL UTILITIES DURING CONSTRUCTION. ALL EXISTING UTILITIES MUST BE LOCATED AND VERIFIED BY EACH UTILITY PRIOR TO COMMENCEMENT OF WORK. ANY VARIANCE IS TO BE IMMEDIATELY REPORTED TO THE ENGINEER. LOST TIME DUE TO FAILURE OF THE CONTRACTOR TO CONFIRM UTILITY LOCATIONS AND NOTIFY THE ENGINEER OF CONFLICTS PRIOR TO CONSTRUCTION WILL BE AT THE CONTRACTORS EXPENSE.

1. ALL GRANULAR BASE AND SUB BASE COURSE MATERIALS SHALL BE COMPACTED TO 100% STANDARD PROCTOR MAX. DRY DENSITY. 2. ALL DISTURBED GRASSED AREAS SHALL BE RESTORED TO ORIGINAL CONDITION OR BETTER, WITH SOD ON MIN. 100mm TOPSOIL. THE RELOCATION OF TREES AND SHRUBS SHALL BE SUBJECT TO APPROVAL BY THE PROJECT LANDSCAPE ARCHITECT OR ENGINEER.

3. LIGHT DUTY ASPHALT TO BE CONSTRUCTED AS FOLLOWS: 75mm ASPHALTIC CONCRETE, TYPE C 150mm-20mm GRANULAR BASE COURSE, TYPE 1 150mm-50mm GRANULAR SUB BASE COURSE, TYPE 2

4. HEAVY DUTY ASPHALT TO BE CONSTRUCTED AS FOLLOWS: 40mm ASPHALTIC CONCRETE, TYPE C 50mm ASPHALTIC CONCRETE, TYPE B-HF

150mm-20mm GRANULAR BASE COURSE, TYPE 1 250mm-50mm GRANULAR SUB BASE COURSE, TYPE 2 5. ALL BARRIER CURB WITHIN THE SITE TO BE CONSTRUCTED AS PER DETAIL ON DRAWING D1, UNLESS OTHERWISE SPECIFIED.

6. ALL CURB CUTS TO BE AS PER DETAIL ON DRAWING D1. 7. ALL BARRIER CURBS AND SIDEWALKS AS SHOWN ON THIS DRAWING ARE TO BE PRICED IN THE SITEWORKS PORTION OF THE CONTRACT. CONCRETE PADS, SIDEWALKS, AND CONCRETE APRODS ABUTTING THE BUILDING ARE TO BE PRICED IN THE BUILDING PORTION OF THE

8. INSPECTIONS: ALL WORK ON THE MUNICIPAL RIGHT OF WAY AND EASEMENTS TO BE INSPECTED BY THE MUNICIPALITY PRIOR TO BACKFILLING. ALL WORK RELATING TO WATERMAN, ACREMENT.


9. REFER TO ARCHITECTURAL SITE PLAN FOR DIMENSIONS AND SITE DETAILS. O. STEP JOINTS ARE TO BE USED WHERE PROPOSED ASPHALT MEETS EXISTING ASPHALT AS PER DETAIL ON DRAWING D1. ALL JOINTS MUST BE SEALED AS PER DETAIL.

1. CONTRACTOR TO OBTAIN A ROAD OCCUPANCY PERMIT 48 HOURS PRIOR TO COMMENCING ANY WORK WITHIN THE MUNICIPAL ROAD ALLOWANCE IF REQUIRED BY THE MUNICIPALITY. 2. ALL FUTURE PHASE AREAS TO BE GRADED TO FINAL GRADES SHOWN LESS 100mm. AREAS TO BE FINISHED WITH SOD ON A MINIMUM OF 100mm OF TOPSOIL. 3. ALL FUTURE PHASE AREAS ARE TO BE TOPSOILED AND SEEDED AS PER DRAWING L1. 4. PARKING AREA PONDING DEPTH TO BE 0.3m (MAXIMUM).

5. EMBANKMENTS TO BE SLOPED AT MAX. 3:1, UNLESS OTHERWISE SPECIFIED. 16. FUTURE PHASE SEDIMENT CONTROL TO BE PROVIDED AT FUTURE PHASE CATCH BASINS AND STORM MANHOLES AS PER DETAIL ON DRAWING D1. 17. REFER TO DRAWING ESC FOR EROSION AND SEDIMENT CONTROL.

18. ALL PAVEMENT MARKING, LINE PAINTING, DIRECTIONAL LINES/ARROWS ETC. SHALL BE PLACED IN ACCORDANCE WITH THE ARCHITECTURAL SITE PLAN OR THE OWNER'S TRAFFIC ENGINEERING CONSULTANT'S DRAWINGS. LINE PAINTING AND DIRECTIONAL SYMBOLS SHALL BE APPLIED WITH A MINIMUM OF TWO COATS OF ORGANIC SOLVENT BASED PAINT IN ACCORDANCE WITH DIVISION 2 SPECIFICATIONS. 9. WHERE APPLICABLE THE CONTRACTOR IS TO SUBMIT SHOP DRAWINGS FOR THE RETAINING WALL (INCLUDE RAILINGS IF APPLICABLE) TO THE ENGINEER FOR APPROVAL PRIOR TO CONSTRUCTION. SHOP DRAWINGS MUST BE SITE SPECIFIC, SIGNED AND SEALED BY A LICENSED STRUCTURAL ENGINEER. THE CONTRACTOR WILL ALSO BE REQUIRED TO SUPPLY STRUCTURAL AND GEOTECHNICAL CERTIFICATION OF THE AS—CONSTRUCTED RETAINING WALL

O. THE CONTRACTOR SHALL PROVIDE TO THE ENGINEER 1 (ONE) SET OF AS CONSTRUCTED SITE SERVICING, GRADING, AND SITE ELECTRICAL DWGS.



1.	ISSUED FOR BUILDING PERMIT	12/15/04	TA			
No.	DESCRIPTION	DATE	BY	CITY		
	REVISIONS					
GRADING PLAN						


COMMERCIAL DEVELOPMENT


YARMOUTH, NOVA SCOTIA WAL-MART CANADA CORP.

Stantec Consulting Ltd. 7270 Woodbine Avenue, Suite 300 Markham , Ontario L3R 4B9 Tel: (905) 474-0455 Fax: (905) 474-9889 Email: Markham@stantec.com Corp. Web Page: www.stantec.com **Stantec**

DESIGN BY PROJECT No. CHECKED BY WT 606 20063 DRAWN BY CCR CHECKED BY TG DRAWING No.

File: X:\PSOC\Coast\20\063\Phase\LATEST DRAWINGS\SW2-3.DWG (Grading) <ccreed> Jan 11, 2005-9:59am





1. ALL WORK SHALL BE CARRIED OUT IN COMPLIANCE WITH THE APPLICABLE HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS. 2. ALL WORK AND MATERIALS TO CONFORM WITH CURRENT MINISTRY OF THE ENVIRONMENT & ENERGY OF NOVA SCOTIA, TOWN OF YARMOUTH , NOVA SCOTIA PROVINCIAL STANDARDS AND SPECIFICATIONS. LOCAL UTILITY STANDARDS AND MINISTRY OF TRANSPORTATION STANDARDS 3.THE CONTRACTOR IS ADVISED THAT WORKS BY OTHERS MAY BE ONGOING DURING THE PERIOD

4. THE INFORMATION SHOWN FOR EXISTING UTILITIES WAS PROVIDED BY OTHERS. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING AND PROTECTING ALL UTILITIES DURING CONSTRUCTION. ALL EXISTING UTILITIES MUST BE LOCATED AND VERIFIED BY EACH UTILITY PRIOR TO COMMENCEMENT OF WORK. ANY VARIANCE IS TO BE IMMEDIATELY REPORTED TO THE ENGINEER. LOST TIME DUE TO FAILURE OF THE CONTRACTOR TO CONFIRM UTILITY LOCATIONS AND NOTIFY THE ENGINEER OF POSSIBLE CONFLICTS PRIOR TO CONSTRUCTION WILL BE AT THE CONTRACTORS EXPENSE.

1. WATERMAIN SHALL BE POLYVINYL CHLORIDE (PVC) CLASS 150 DR-18 PIPE MANUFACTURED TO AWWA C900-89 AND CSA CAN3 B137.3-M1986 WITH GASKETED BELL END C/W #14 AWG SOLID COPPER TRACER WIRE. 2. ALL WATERMAIN BEDDING AND TRENCH DETAIL SHALL BE AS PER LOCAL MUNICIPAL, REGIONAL, OR PROVINCIAL STANDARDS, UNLESS SHOWN OTHERWISE. 3. ALL WATERMAINS SHALL HAVE MIN. COVER OF 2.0m. WATERMAINS ARE TO BE INSTALLED TO THE ELEVATIONS SHOWN ON THE APPROVED SITE SERVICING DRAWING. WHERE SPECIFIC WATERMAIN ELEVATIONS ARE NOT SHOWN ON SERVICING DRAWING, A MINIMUM COVER OF 2.0m FROM PROPOSED GRADES, AS SHOWN ON THE GRADING PLAN, MUST BE MAINTAINED AT ALL TIMES. IN PREGRADE AREAS COVER TO BE FROM PREGRADED ELEVATIONS. 4. ALL WATERMAIN HORIZONTAL AND VERTICAL BENDS, JOINTS AND PLUGS TO BE MECHANICALLY RESTRAINED. THRUST BLOCKS/MECHANICAL RESTRAINERS MUST BE INSTALLED ON ALL WATERMAIN BENDS, TEES, AND PLUGS AS PER LOCAL MUNICIPAL STANDARDS. 5. ALL FIRE HYDRANT INSTALLATIONS SHALL BE AS PER TOWN OF YARMOUTH STANDARDS. HYDRANTS SHALL BE PAINTED IN ACCORDANCE WITH LOCAL STANDARDS. S. CONTRACTOR SHALL ORIENT HYDRANT AS DIRECTED BY THE LOCAL FIRE DEPARTMENT. CONTRACTOR TO CONTACT LOCAL FIRE DEPARTMENT AND OBTAIN WRITTEN DIRECTION AS TO THE REQUIRED ORIENTATION AND SPECIFICATIONS FOR FIRE HYDRANTS AND PROVIDE DOCUMENTATION PRIOR TO REQUESTING CERTIFICATION OF SUBSTANTIAL COMPLETION. 7. ALL HYDRANT FLANGE ELEVATIONS TO BE INSTALLED 0.15m ABOVE PROPOSED FINISHED

8. BUILDING SERVICE VALVES TO BE 3.0m OFF THE FACE OF THE BUILDING UNLESS OTHERWISE NOTED AND MUST BE RESTRAINED A MINIMUM OF 12m BACK FROM STUB. WATERMAINS MUST COMPLY WITH MINIMUM HORIZONTAL AND VERTICAL CLEARANCES IN ACCORDANCE WITH LOCAL PROVINCIAL GUIDELINES AND THE APPLICABLE BUILDING AND PLUMBING CODE. WHERE HORIZONTAL SEPARATIONS CANNOT BE ACHIEVED, APPROVAL FROM THE ENGINEER MUST BE OBTAINED AND A MINIMUM 500mm VERTICAL SEPARATION MUST BE


11. ALL WATERMAINS SHALL BE BACTERIALOGICALLY TESTED IN ACCORDANCE WITH LOCAL MUNICIPAL AND PROVINCIAL GUIDELINES. ALL CHLORINATED WATER TO BE DISCHARGED AND PRETREATED TO ACCEPTABLE LEVELS PRIOR TO DISCHARGE. ALL DISCHARGED WATER MUST BE CONTROLLED AND TREATED SO AS NOT TO ADVERSELY EFFECT THE ENVIRONMENT. THE LOCAL MUNICIPALITY MAY HAVE SPECIFIC REQUIREMENTS TO BE COMPLIED WITH. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT ALL MUNICIPAL AND/OR PROVINCIAL REQUIREMENTS ARE FOLLOWED. 2. ALL WATERMAIN STUBS SHALL BE TERMINATED WITH A PLUG AND 50mm BLOW OFF UNLESS OTHERWISE NOTED. 3. ALL DUCTILE IRON FITTINGS SHALL BE CATHODICALLY PROTECTED WITH A 5.4kg ZINC ANODE.

ALL MANHOLES TO BE AS PER STD ON DRAWING D1 WITH FRAME AND COVER AS PER DETAIL ON DRAWING D1, UNLESS OTHERWISE SPECIFIED. SAFETY PLATFORM TO BE INSTALLED IN ALL MANHOLES WHERE DEPTH EXCEEDS 5.0m. 2.ALL CATCH BASINS TO BE PRE—CAST AS PER STD. ON DRAWING D1 WITH FRAME AND GRATE
AS PER DETAIL DRAWING OR OWNER APPROVED EQUIVALENT. CONTRACTOR TO SUPPLY SHOP
DRAWINGS FOR ALL SUPER CATCH BASINS, STAMPED BY A LICENSED PROFESSIONAL STRUCTURAL ENGINEER, TO THE SATISFACTION OF THE ENGINEER AND THE TOWN.

3. CONCRETE PIPE SEWER BEDDING SHALL BE CLASS B AS PER DETAIL ON DRAWING D2, PVC OR RIBBED PIPE SEWER BEDDING SHALL BE CLASS B AS PER DETAIL ON DRAWING TO TOP OF SEWER. NATIVE BACKFILL TO BE COMPACTED TO A MIN. 98% STANDARD PROCTOR DENSITY, WITH A MINIMUM 300mm SAND COVER OVER PIPE. 4. ALL STORM SEWER PIPES UP TO 450mm DIA. SHALL BE PVC SDR-35 OR APPROVED EQUIVALENT. ALL STORM SEWER PIPES 525mm DIA. AND LARGER SHALL BE CONCRETE AND EQUAL TO C.S.A. SPECIFICATIONS A257.2 REINFORCED CLASSES AS SPECIFIED 65-D, OR LATEST AMENDMENT UNLESS OTHERWISE SPECIFIED. 5. ALL SANITARY PVC SEWER PIPES SHALL BE SDR-35 EQUAL CSA SPECIFICATIONS B182.2-M1990 OR LATEST AMENDMENT UNLESS OTHERWISE NOTED. 6. ALL MANHOLE AND CATCH BASIN EXCAVATIONS TO BE BACKFILLED WITH GRANULAR MATERIAL COMPACTED TO 98% STANDARD PROCTOR DENSITY. 7.STORM MANHOLES SHALL BE BENCHED TO SPRING LINE UNLESS OTHERWISE SPECIFIED. SANITARY MANHOLES SHALL BE BENCHED TO OBVERT. MINIMUM WIDTH OF BENCHING TO BE 230mm OR AS SPECIFIED ON DRAWINGS. 8. "MODULOC" OR APPROVED PRE-CAST MANHOLE AND CATCH BASIN ADJUSTERS TO BE USED IN LIEU OF BRICKING. PARGE ADJUSTING UNITS ON THE OUTSIDE ONLY. 9. FOR CONSTRUCTION DETAILS NOT SHOWN ON PLANS, REFERENCE SHALL BE MADE TO THE LOCAL PROVINCIAL STANDARDS DRAWINGS AND MUNICIPAL STANDARDS. D. SERVICES TO BUILDINGS TO BE TERMINATED 1.5m FROM THE OUTSIDE FACE OF BUILDING

UNLESS OTHERWISE NOTED. 1. ALL SINGLE CATCH BASIN LEADS TO BE 300mmø PVC. SDR-35 OR APPROVED EQUIVALENT UNLESS OTHERWISE SPECIFIED. 2. ALL CB LEAD INVERTS TO BE 1.5m BELOW FINISHED GRADE UNLESS OTHERWISE SPECIFIED. 3. ALL IRRIGATION SLEEVES ARE TO BE 100mmø PVC UNLESS OTHERWISE NOTED. SEE DRAWING No. _____ FOR DETAILS.

14. THE CONTRACTOR IS TO PROVIDE CCTV CAMERA INSPECTIONS OF ALL SANITARY AND STORM SEWERS, INCLUDING PICTORIAL REPORT, TWO (2) CD COPIES AND ONE (1) VIDEO TAPE IN A FORMAT SATISFACTORY TO THE ENGINEER. ALL SEWERS ARE TO BE FLUSHED PRIOR TO CAMERA INSPECTION. 5. LASER ALIGNMENT CONTROL TO BE UTILIZED ON ALL SEWER INSTALLATIONS.





Stantec

Email: Markham@stantec.com Corp. Web Page: www.stantec.com

DESIGN BY PROJECT No. CHECKED BY WT 606 20063 DRAWN BY CHECKED BY TG DRAWING No. SW3

File: X:\PSOC\Coast\20\063\Phase\LATEST DRAWNGS\SW2-3.DWG (Servicing) <ccreed> Jan 11, 2005-10:00am





NOTES:

1. ALL EROSION AND SEDIMENT CONTROL MEASURES TO BE INSTALLED PRIOR TO ANY CONSTRUCTION ACTIVITIES.

2. ALL SEEDING TO BE COMPLETED AS PER OPSS SECTION 572, HYDRAULIC MULCH TYPE B, PRIMARY SEED TYPE 1.

3. ALL DISTURBED AREAS TO BE STABILIZED WITH SEED AS SOON AS CONSTRUCTION ACTIVITY IS COMPLETED.

4. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CHECKED AND MAINTAINED ON A REGULAR BASIS. INSPECTION OF SUCH MEASURES SHALL BE COMPLETED AFTER EVERY RAINFALL.

5. ADDITIONAL SILT FENCING SHOULD BE AVAILABLE IN CASE IMMEDIATE REPAIR IS REQUIRED.

6. SWALES WILL BE MAINTAINED BY SITE CONTRACTOR DURING THE EARTHWORKS PROCESS TO ALLOW FOR CONTINUOUS DRAINAGE.

7. SEDIMENTATION CONTROL FENCING WILL BE PLACED AROUND THE PERIMETER OF THE SITE WITH SWALE NETWORKS THROUGHOUT TO PROMOTE CONTINUOUS DRAINAGE.

8. EROSION AND SEDIMENT CONTROL MEASURES WILL BE MAINTAINED IN CONJUCTION WITH CONTRACTOR OPERATIONS. EARTHWORKS WILL REQUIRE A MULTI PHASE ESC PLAN WHICH WILL BE DETERMINED BY THE CONTRACTOR AT THE TIME OF CONSTRUCTION.

9. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CHECKED AND MAINTAINED ON A REGULAR BASIS. INSPECTION OF SUCH MEASURES SHALL BE COMPLETED AFTER EVERY RAINFALL.

10. ALL EROSION AND SEDIMENT CONTROL MEASURES TO BE INSTALLED PRIOR TO ANY CONSTRUCTION ACTIVITIES.

- 11. ALL INSTREAM WORK SHOULD BE COMPLETED BETWEEN 1 JUNE AN SEPTEMBER, 2004.

 12. ALL WORK SHOULD BE CONDUCTED IN ACCORDANCE WITH THE APPLICATION.
- ALL WORK SHOULD BE CONDUCTED IN ACCORDANCE WITH THE APPROPRIATE NOVA SCOTIA WATERCOURSE ALTERATION TECHNICAL GUIDELINES.
 ALL MATERIALS AND EQUIPMENT USED FOR THE PURPOSE OF SITE PREPARATION AND PROJECT COMPLETION SHOULD BE OPERATED AND STORED IN A MANNER THAT PREVENTS ANY DELETERIOUS SUBSTANCE (e.g. PETROLEUM PRODUCTS, SILT, ETC.) FROM ENTERING THE WATER.
- 14. ANY STOCKPILED MATERIALS SHOULD BE STORED AND STABILIZED AWAY FROM THE WATER.
 15. VEHICLE AND EQUIPMENT RE-FUELLING AND MAINTENANCE SHOULD BE CONDUCTED AWAY FROM THE BROOK.
- 16. ANY PART OF EQUIPMENT ENTERING THE WATER SHOULD BE FREE OF FLUID LEAKS AND EXTERNALLY CLEANED TO PREVENT ANY DELETERIOUS SUBSTANCE FROM ENTERING THE WATER.
- 17. ONLY CLEAN MATERIAL FREE OF FINE PARTICULATE MATTER SHOULD BE PLACED IN THE WATER.
 18. SEDIMENT AND EROSION CONTROL MEASURES SHOULD BE IMPLEMENTED PRIOR TO WORK AND MAINTAINED DURING THE WORK PHASE, TO PREVENT ENTRY OF
- TO WORK AND MAINTAINED DURING THE WORK PHASE, TO PREVENT ENTRY OF SEDIMENT INTO THE WATER.

 19. ALL SEDIMENT AND EROSION CONTROL MEASURES SHOULD BE INSPECTED DAILY TO ENSURE THAT THEY ARE FUNCTIONING PROPERLY AND ARE MAINTAINED.
- 20. IF THE SEDIMENT AND EROSION CONTROL MEASURES ARE NOT FUNCTIONING PROPERLY, NO FURTHER WORK SHOULD OCCUR UNTIL THE SEDIMENT AND/OR EROSION PROBLEM IS ADDRESSED.

AND/OR UPGRADED AS REQUIRED.

- 21. ALL CHECK DAMS AND SEDIMENT AND EROSION CONTROL FENCES SHOULD BE INSPECTED DAILY AND ANY SILT OR DEBRIS THAT HAS ACCUMULATED SHOULD BE REMOVED TO ENSURE THAT THEY ARE FUNCTIONING PROPERLY.

 22. ALL DISTURBED AREAS ON THE WORK AREA SHOULD BE STABILIZED AS SOON AS POSSIBLE AFTER THE PROJECT COMPLETION.

 23. SEDIMENT AND EROSION CONTROL MEASURES SHOULD BE LEFT IN PLACE AND MAINTAINED UNITED.
- 23. SEDIMENT AND EROSION CONTROL MEASURES SHOULD BE LEFT IN PLACE AND MAINTAINED UNTIL ALL DISTURBED AREAS ON THE WORK AREA HAVE BEEN STABILIZED.
 24. FISH SHOULD BE REMOVED FROM THE WORK AREA PRIOR TO DE—WATERING AND RELEASED ALIVE IMMEDIATELY DOWNSTREAM.
- 25. SILT OR DEBRIS THAT HAS ACCUMULATED AROUND THE TEMPORARY COFFERDAMS SHOULD BE REMOVED PRIOR TO THEIR WITHDRAWAL.

 26. SEDIMENT LADEN DEWATERING DISCHARGE SHOULD BE PUMPED TO A SETTLING BASIN WELL AWAY FROM THE WATERCOURSE AND ALLOWED TO SETTLE AND/OR FILTER THROUGH THE RIPARIAN VEGETATION BEFORE RE—ENTERING THE WATERCOURSE DOWNSTREAM OF THE CONSTRUCTION AREA. CONTRACTOR TO PROVIDE SEDIMENT CONTROL ACTION PLAN PRIOR TO CONSTRUCTION.
- 27. ANY "SANDBAGS" USED FOR COFFERDAM CONSTRUCTION SHOULD BE FILLED WITH CLEAN PEA GRAVEL FREE OF FINE PARTICULATES.

LEGEND

CONSTRUCTION FENCE AS PER DETAIL ON DRAWING D2

TYPE II SILT CONTROL FENCE AS PER DETAIL ON THIS DRAWING

PROPERTY BOUNDARY

SEDIMENT CONTROL DEVICE AS PER DETAIL ON DWG D1

			·			
1.	ISSUED FOR BUILDING PERMIT	12/15/04	TA			
No.	DESCRIPTION	DATE	BY	CITY		
	REVISIONS					

EROSION & SEDIMENT CONTROL PLAN

SCALE 1: 500

COMMERCIAL DEVELOPMENT

BUILDING A
YARMOUTH, NOVA SCOTIA
WAL-MART CANADA CORP.

Stantec

Stantec Consulting Ltd.
7270 Woodbine Avenue, Suite 300
Markham, Ontario L3R 4B9
Tel: (905) 474-0455
Fax: (905) 474-9889
Email: Markham@stantec.com
Corp. Web Page: www.stantec.com

DESIGN BY TA PROJECT No.


CHECKED BY WT 606 20063

DRAWN BY CCR

CHECKED BY TG DRAWING No.

ESC

File: X:\PSOC\Coast\20\063\Phase\LATEST DRAWINGS\ESC.dwg (ESC-1) <ccreed> Jan 11, 2005-10:01am



APPENDIX A

Allowable Release Rate Calculations

APPENDIX B

Control Details

On-Site Detention Storage - Orifice Outlet

5 Year storm and 100 year storm

Project Description	Yarmouth - NS
Project No.	60620063
Area Id	102

Orifice Equation: Q = C_dA(2gh)^{1/2}

	405	mm
Area:	0.000	m^2
g =	9.81	m/sec ²
$C_d =$	0.62	

Type of Control:
Location:

-	
CBMH18	

Parking Lot Storage - 100

9		
Surface Area =	2349	${\rm m}^{\rm 2}$
Depth =	0.25	m
Volume =	196	m^3
v olalilo –	100	

Parking Lot Storage - 5

	 •
Surface Area =	0 m ²
Depth =	0 m
	_
Volume =	0 m ³

Pipe Storage

Diameter (mm)	Area (m²)	Length (m)	Volume (m³)
250	0.049	0	0.0
300	0.071	0	0.0
375	0.110	0	0.0
450	0.159	0	0.0
525	0.216	0	0.0
600	0.283	0	0.0
750	0.442	0	0.0
825	0.535	0	0.0
900	0.636	0	0.0
1050	0.866	0	0.0
		Total Volume	0.0

	Stage	Head*	Storage (m3)	Discharge (m3/s)
Invert E.L.	26.00	0.00	0	0.00
Ground E.L.	29.15	0.05	11	0.000
5 Year WL	29.15	0.05	11	0.000
100 Year WL	29.40	0.00	207	0.000

^{*}Head calculated from tailwater from 103

MH Storage

Diameter (mm)	Area (m²)	Depth (m)	Volume (m³)
1200	1.131	0	0.0
1200	1.131	0	0.0
1500	1.767	0	0.0
1500	1.767	0	0.0
1800	2.545	0	0.0
1800	2.545	0	0.0
2400	4.524	0	0.0
2400	4.524	0	0.0
2400	4.524	0	0.0
2400	4.524	0	0.0
	To	0.0	

CB Storage

Size	Area	Depth	Volume	No. of CB's	Volume
(m)	(m2)	(m)	(m3)		(m3)
0.6	0.360	2.00	0.72	15	10.80
0.6	0.360	1.50	0.54	0	0.0
				Total Volume	10.8

On-Site Detention Storage - Orifice Outlet

5 Year storm and 100 year storm

Project Description	Yarmouth - NS
Project No.	60620063
Area Id	102

Orifice Equation: $Q = C_dA(2gh)^{1/2}$

Orifice Diameter: 195 mm

Area: 0.030 m² $g = 9.81 \text{ m/sec}^2$ $C_d = 0.62$

Type of Control: Location: Vertical MH22

Parking Lot Storage - 100

anning Lot c	noruge n	,,
Surface Area =	5630	m^2
Depth =	0.3	m
Volume =	563	m ³
	000	

Parking Lot Storage - 5

oloruge e
= 0 m ²
= 0 m
= 0 m ³

Pipe Storage

Diameter (mm)	Area (m²)	Length (m)	Volume (m³)
250	0.049	69	3.4
300	0.071	55	3.9
375	0.110	0	0.0
450	0.159	39	6.2
525	0.216	0	0.0
600	0.283	86	24.2
750	0.442	0	0.0
825	0.535	0	0.0
900	0.636	68	43.3
1050	0.866	450	389.2
		Total Volume	470.1

|--|

WITI Storage			
Diameter (mm)	Area (m²)	Depth (m)	Volume (m³)
1200	1.131	0	0.0
1200	1.131	0	0.0
1500	1.767	0	0.0
1500	1.767	0	0.0
1800	2.545	0	0.0
1800	2.545	0	0.0
2400	4.524	0	0.0
2400	4.524	0	0.0
2400	4.524	0	0.0
2400	4.524	0	0.0
	To	0.0	

Stage Head Storage Disharge (m3/s)(m) (m3)26.07 0.00 0.00 Invert E.L. 0 Ground E.L. 29.10 2.93 472 0.140 pipe storage 5 Year WL 29.10 2.93 472 0.140 100 Year WL 29.40 3.23 1035 0.147 pipe+surface storage

CB Storage

Size	Area	Depth	Volume	No. of CB's	Volume
(m)	(m2)	(m)	(m3)		(m3)
0.6	0.360	1.50	0.54	4	2.16
0.6	0.360	1.50	0.54	0	0.0
				Total Volume	2.2

On-Site Detention Storage - Orifice Outlet

100 year storm

Project Description	Yarmouth - NS
Project No.	60620063
Area Id	Weir flow - 102

 $\mathbf{Q} = \mathbf{C}_{\mathrm{w}} \mathbf{B} \mathbf{H}^{3/2}$ Weir Equation:

Base (Weir Length) =

Type of Control: Location:

Parking Lot Storage - 100

 0 m^2 Surface Area = 0.02 m Depth = $0 \, \mathrm{m}^3$ Volume =

Parking Lot Storage - 5

Surface Area = Depth = 0 m $0 \, \mathrm{m}^3$ Volume =

Pipe Storage

Diameter (mm)	Area (m²)	Length (m)	Volume (m³)
250	0.049	0	0.0
300	0.071	0	0.0
375	0.110	0	0.0
450	0.159	0	0.0
525	0.216	0	0.0
600	0.283	0	0.0
750	0.442	0	0.0
825	0.535	0	0.0
900	0.636	0	0.0
1050	0.866	0	0.0
_		Total Volume	0.0

	Stage	Head (m)	Storage (m3)	Disharge (m3/s)	
Invert E.L.	29.38	0.00	0	0.00	
100 Year WL	29.40	0.00	0	0.093	pipe+surface storage

 $0.09 \text{ m}^3/\text{s}$ Flow over Weir = 0.44 m^2 Cross-sectional area =

Velocity = 0.21 m/s
 Site:
 Yarmouth - NS

 12/9/2004 8:46

Job No.: 60620063

						100 Year							
Catchment ID	Building No.	Runoff Coef.	Area (ha)	Release Rate (I/s)	Storage Required (m3)	Ponding Depth (m)	Storage Available (m3)	Draw Down Time (mins)	Orifice Size (mm) or Weir Length (m)	Orifice Release Rate (I/s) or Weir Discharge Rate (I/s)	Location of Orifice or Weir	Invert	HORIZONTAL/ VERTICAL/TUBE Control
101	Α	0.95	0.88	37	333	0.10	528	n/a	roof	=	0.0	-	-
102		0.95	2.85	203	797	0.30	1035	37	195	147	MH22	26.070	Vertical
103		0.95	0.13	34	7	0.30	47	3	100	34	CB26	27.600	Vertical
Weir flow - 102						0.02			22	93	0.0	-	-
Total		•	3.86	274.6	1136	-	1818	-	-	-	-	-	-

Notes: Area 101 is in series with 102

Allowable Release Rate 553.9 L/s Area 102 is in series with 103

The site area is recognized to be 4.40 ha. However, the downstream uncontrolled area is not considered in this analysis to size orfice plates on-site to meet required storage and allowable release rates.

Weir discharge included in subcatchments 102 and 103 release rates.

 Site:
 Yarmouth - NS

 Job No.:
 60620063

Catchment ID	Building No.	Runoff Coef.	Area (ha)	Release Rate (I/s)	Storage Required (m3)	Ponding Depth (m)	5 Year Storage Available (m3)	Draw Down Time (mins)	Orifice Size (mm)	Orifice Release Rate (I/s)
101	Α	0.95	0.88	18	224	0.10	264	n/a	roof	-
102		0.90	2.85	122	475	0.00	472	0	195	140
103		0.90	0.13	26	0	0.00	1	0	100	26
Total				166.4	699	0.30	748	-		

Total Site Allowable Release Rate 166.0 L/s Notes: Area 101 is in series with 102

Area 102 is in series with 103

The site area is recognized to be 4.40 ha. However, the downstream uncontrolled area is not considered in this analysis to size orfice plates on-site to meet required storage and allowable release rates.

Site: Yarmouth - NS 12/9/2004 8:46


Job No.: 60620063

	100 Year						Pipe Length									
Catchment ID	Surface Ponding (m2)	Ponding Depth (m)	Type of Control	Location of MH	Ground Invert	Invert	Pipe Diameter (mm)									
							250	300	375	450	525	600	750	825	900	1050
102	5630	0.3	Vertical	MH22	29.100	26.070	69	55		39		86			68	450
103	469.3	0.3	Vertical	CB26	29.100	27.600										
Weir flow - 102		0.02	-		29.400	29.400										


APPENDIX C

Modified Rational Storage Calculations


MOD_RTNL 100.xls 12/8/2004 17:04




MOD_RTNL 100.xls 12/8/2004 17:04




MOD_RTNL 100.xls 12/8/2004 17:04




MOD_RTNL 5.xls 12/8/2004 17:04



MOD_RTNL 5.xls 12/8/2004 17:04




MOD_RTNL 5.xls 12/8/2004 17:04



APPENDIX D

External Drainage



PROPOSED COMMERCIAL DEVELOPMENT SITE

EGEND

DRAINAGE BOUNDARY

STANTEC CONSULTING LTD.
7270 WOODBINE AVE., SUITE 300
MARKHAM, ONTARIO L3R 4B9
TELEPHONE: (905) 474-0455
FAX: (905) 474-9889

Date: DECEMBER 3, 2004 Scale: 1:12,500 Project No.: 606 20063 COMMERCIAL DEVELOPMENT EXTERNAL DRAINAGE BOUNDARIES Figure No. : ယ

63\Phase\LATEST DRAWNGS\Figure 3_4 external drainage.dwg (Figure 4 EXTERNAL) <priamo> Dec 09, 2004-10:12am

APPENDIX E

SWMHYMO Drainage Analysis

APPENDIX F

Stormceptor Sizing Tool Results