

**Source Emissions Testing –
Recovery Boiler and Power
Boiler, Winter 2015**



Prepared for:

Northern Pulp Nova Scotia
Corporation
P.O. Box 549, Station Main
New Glasgow, NS B2H 5E8

Prepared by:

Stantec Consulting Ltd.
102-40 Highfield Park Drive
Dartmouth, NS B3A 0A3

Project No. 121413456

April 10, 2015

TABLE OF CONTENTS

EXECUTIVE SUMMARY	ii
1.0 INTRODUCTION	1
2.0 OVERALL APPROACH.....	1
2.1 SUBMISSION OF PRE-TEST PLAN	1
2.2 ON-SITE SOURCE EMISSIONS TESTING.....	2
2.3 INFORMATION REVIEW AND REPORTING	2
3.0 TEST METHODS, EQUIPMENT, AND CALIBRATIONS	3
3.1 SAMPLING PROCEDURES AND EQUIPMENT	3
3.1.1 Total Particulate Matter	3
3.1.2 Combustion Gases	5
3.2 QUALITY ASSURANCE AND QUALITY CONTROL	5
4.0 RESULTS AND DISCUSSION	6
4.1 EXHAUST STACK SAMPLE LOCATION DETAILS	6
4.2 RECOVERY BOILER	7
4.3 POWER BOILER	9
4.4 SUMMARY OF RESULTS	10
5.0 CLOSURE.....	10

LIST OF TABLES

Table E.1	Summary of Scope	ii
Table 2.1	Source Emissions Testing Matrix.....	2
Table 4.1	Sample Location Details	6
Table 4.2	Source Testing Results - Recovery Boiler - Particulate Matter.....	7
Table 4.3	Source Testing Results - Recovery Boiler - Combustion Gases	8
Table 4.4	Source Testing Results - Power Boiler - Particulate Matter	9
Table 4.5	Source Testing Results - Power Boiler - Combustion Gases.....	10

LIST OF FIGURES

Figure 3.1	Source Emissions Testing Method 5 Sampling Train.....	4
------------	---	---

List of Appendices

Appendix A	Pre-test Plan
Appendix B	Calibration Data
Appendix C	Field Data Sheets
Appendix D	Calculations

EXECUTIVE SUMMARY

Northern Pulp Nova Scotia Corporation, referred to herein as Northern Pulp, retained Stantec Consulting Ltd. to conduct source emissions testing at the Kraft pulp mill in New Glasgow, Nova Scotia. Source emissions testing were conducted on the Recovery Boiler and the Power Boiler to fulfill the conditions specified in the current Certificate of Approval to Operate (CoA) 2011-076657-R03. The source emissions testing campaign was performed according to the pre-test plan submitted to the Nova Scotia Department of Environment. The testing was conducted during the week of March 9th, 2015.

In this report, source emissions testing data are presented for measurements which include combustion gases and total particulate matter (PM) as well as exhaust gas temperature, exhaust flow rate, moisture content, velocity, and volumetric flow rate. The scope of work for the testing campaign is summarized in Table E.1.

Table E.1 Summary of Scope

Source	Number of Samples per Source	Parameter	Sampling Method
Recovery Boiler	3	Total Particulate Matter (PM)	EPS 1/RM/8
	3	Combustion Gases	EPS 1/RM/15
Power Boiler	3	Total Particulate Matter (PM)	EPS 1/RM/8
	3	Combustion Gases	EPS 1/RM/15

The average measured concentration of PM from the Power Boiler was 155 mg/Rm³ (corrected to 11% O₂), which is above the respective regulatory stack limit of 150 mg/Rm³ presented in Table 1 of the facility's Approval. The measured concentration of PM from the Recovery Boiler was 833 mg/Rm³ (corrected to 11% O₂), which is above the regulatory limit of 375 mg/Rm³ presented in Table 1 of the facility's Approval.

1.0 INTRODUCTION

Northern Pulp Nova Scotia Corporation, referred to herein as Northern Pulp, retained Stantec Consulting Ltd. (Stantec) to conduct source emissions testing at the Kraft pulp mill in New Glasgow, Nova Scotia. Source emissions testing were conducted on the Recovery Boiler and the Power Boiler. The source emissions testing campaign was performed according the pre-test plan submitted on February 23rd, 2015 to the Nova Scotia Department of Environment, following methods published by the United States Environmental Protection Agency and Environment Canada. The testing was conducted during the week of March 9th, 2015.

In this report, source emissions testing data are presented for combustion gases (oxygen, carbon dioxide, nitrogen oxides, sulphur dioxide, and carbon monoxide), total particulate matter (PM), exhaust gas temperature, exhaust flow rate, moisture content, velocity, and volumetric flow rate.

This report is in five sections. Section 1 contains the introduction and the scope of work for the project. The study approach and a brief description of the various parts of the project are in Section 2. Section 3 contains a brief description of the testing methodologies, equipment, and calibration techniques used during the source emissions testing program. In Section 4, the results of the source emissions testing are presented and discussed, and concluding remarks are presented in Section 5. Appendices A through D contain supporting information for the report.

2.0 OVERALL APPROACH

The project consisted of five parts:

1. Submission of the Pre-test Plan;
2. Site Preparation and Preliminary Survey;
3. On-site Source Emissions Testing;
4. Laboratory Analysis; and
5. Information Review and Reporting.

Each of these parts is described below.

2.1 SUBMISSION OF PRE-TEST PLAN

The on-site testing was conducted in accordance with the Pre-Test Plan submitted on February 23rd, 2015 to Nova Scotia Environment (NSE). The Pre-Test Plan outlined the contaminants to be tested, as well as the methodologies proposed for conducting the source testing on the exhaust stacks. Appendix A provides a copy of the plan.

2.2 ON-SITE SOURCE EMISSIONS TESTING

Stantec set up the source emissions testing equipment and conducted a preliminary survey to measure the exhaust gas temperature, velocity, and flue gas composition for those sources requiring particulate testing. The data from this survey was used to determine the appropriate nozzle size to conduct isokinetic sampling (where the velocity of the gas entering the nozzle is equal to the gas velocity in the stack) for particulate matter sampling.

Three (3) tests for total particulate matter were conducted at defined sampling locations within the cross-section of the exhaust stacks of the Recovery Boiler and the Power Boiler. Three tests for combustion gases were also conducted, near the centre of the exhaust stacks of the Recovery Boiler and the Power Boiler. All testing was completed in compliance with the sampling methods presented in Table 2.1, in accordance with the *Air Quality Regulation*, under the *Environment Act*, Section 112 issued by Nova Scotia Environment (NSE) and the requirements of the facility's approval (2011-076657-R03) issued by the NSE.

The methodologies used for testing the emissions from each exhaust stack are summarized in Table 2.1.

Table 2.1 Source Emissions Testing Matrix

Source	Number of Samples per Source	Approval Condition	Parameter	Sampling Method
Recovery Boiler	3	6. a)	Total Particulate Matter (PM)	EPS 1/RM/8
	3	-	Combustion Gases	EPS 1/RM/15
Power Boiler	3	6. a)	Total Particulate Matter (PM)	EPS 1/RM/8
	3	-	Combustion Gases	EPS 1/RM/15

2.3 INFORMATION REVIEW AND REPORTING

The data collected in the field, along with data from the laboratory analyses, were entered into the Stantec's source emissions testing spreadsheets for analysis. Emissions calculations were then performed to produce the detailed source emissions testing information. Spreadsheet calculations were verified by hand, and numerous spot checks of spreadsheet formulas were conducted to ensure the accuracy of data. Summary tables were prepared and incorporated into this report for submission to Northern Pulp.

3.0 TEST METHODS, EQUIPMENT, AND CALIBRATIONS

This section contains a description of the methods and equipment used to conduct the source emissions testing campaign. The calibration procedures used to ensure the quality of the source emissions testing data are also summarized in this section.

3.1 SAMPLING PROCEDURES AND EQUIPMENT

The following sub-sections contain brief descriptions of the sampling equipment and methodologies used during the source emissions testing campaign.

3.1.1 Total Particulate Matter

Particulate matter emissions from the exhaust stacks were measured in accordance with the Environment Canada Reference Method EPS 1/RM/8, entitled *Reference Methods for Source Testing: Measurement of Releases of Particulate from Stationary Sources*.


The sampling train, used specifically for isokinetic sampling of particulate matter, is described in detail in EPS 1/RM/8, and is generally referred to as the 'Method 5' sampling train for particulate matter, named after the United States Environmental Protection Agency (US EPA) protocol. The sampling train consists of several different components which include: a heated sampling probe (a nozzle, stainless steel liner, thermocouple, and pitot tube assembly), a heated sample case containing a filter, an ice box containing impinger glassware, and an umbilical cord leading to the pump and control console. A schematic of the sampling system is shown in Figure 3.1. The operation of the Method 5 sampling train can be generally described as follows.

Exhaust gases are drawn through the probe nozzle at or near isokinetic conditions (*i.e.*, where the gas velocity in the nozzle is at the same velocity as the gas in the stack). The gases are then drawn through the inner stainless steel liner of the electrically heated sampling probe to the other components of the sampling train.

A pitot tube assembly is attached to the probe next to the nozzle to measure the exhaust gas velocity in the area of the probe nozzle. Using the differential pressure reading on the control console, the desired nozzle flow rate is determined from the differential pressure across a calibrated orifice.

The exhaust gases are drawn from the probe liner through a pre-weighed glass fiber filter, in the hot side of the sampling unit, and then through pre-weighed impingers in an ice bath to cool the gases and condense the moisture in the gas, before the gas enters the umbilical cord.

The umbilical cord carries the filtered, cooled exhaust gases from the sampling site to the control console. The control console contains a fiber vane vacuum pump, which is used to draw the exhaust gases through the sampling train. A calibrated dry gas meter records the volume of gas sampled.



SOURCE EMISSIONS TESTING
METHOD 5 SAMPLING TRAIN

After completion of testing, the impingers are re-weighed, with the difference in mass corresponding to the mass of water collected. This measurement is used to calculate the moisture content of the exhaust gas.

Prior to the particulate matter testing, filters were conditioned and pre-weighed. Following the testing, particulate matter was recovered from the nozzle, the sampling probe and the in-line filter. Following testing, the filter containing the particulate sample, was conditioned and weighed, and the net weight of the collected particulate matter was determined. After each test, the probe and nozzle were rinsed with acetone and this acetone was collected, placed into a pre-weighed container and evaporated until dry. The amount of particulate for each part of the sample was determined gravimetrically, and the mass of particulate matter collected for each test was calculated as the sum of the particulate matter collected in the filter, probe, and nozzle rinse. The contents of the water filled impingers were also recovered gravimetrically for particulate matter and reported separately as requested by the NSE. These recoveries were performed at Stantec's laboratory in Fredericton, New Brunswick. Appendix B contains the equipment calibration data.

3.1.2 Combustion Gases

The combustion gases (O_2 , CO_2 , CO , NO_x , and SO_2) from the boilers were sampled according to the Environment Canada reference method EPS 1/RM/15, entitled *Reference Method for the Monitoring of Gaseous Emissions from Fossil Fuel-fired Burners*. In this method, samples of flue gas are drawn through a probe, non-isokinetically, from a single point near the centre of the stack. An ENERAC Model 500 Micro-Emission Analyzer, manufactured by ENERAC Inc., was used to conduct the sampling. The Model 500 is equipped with a flue gas probe that has an integrated filter trap and condensate trap, and a housing unit that contains the pump and the electrochemical cells which are used to measure concentrations of sulphur dioxide, nitrogen oxides, carbon monoxide, carbon dioxide, and oxygen. The ENERAC Model 500 Micro-Emission Analyzer is manufactured and calibrated to confirm accuracy. Calibration data is included in Appendix B.

3.2 QUALITY ASSURANCE AND QUALITY CONTROL

Throughout the source emissions testing program, quality assurance and quality control procedures were applied to ensure the collection of reliable and accurate emissions data. Quality control checks were performed at several stages during the testing program to ensure the collection of representative samples and the generation of valid results.

The Quality Control (QC) checks included the following:

- use of standardized checklists and field notebooks to ensure completeness, traceability, and comparability of the process information and samples;
- field checking of standardized forms by a second person to ensure accuracy and completeness;

SOURCE EMISSIONS TESTING – RECOVERY BOILER AND POWER BOILER, WINTER 2015

- strict adherence to sample chain-of-custody procedures;
- testing for cyclonic or reverse flow, as well as stratified flow conditions; and
- leak checks of sampling train.

Equipment was calibrated according to the protocols and schedule as prescribed by NSE, Environment Canada, and the US EPA. These calibrations include the following:

Pitots: Calibrated in a wind tunnel with probe and nozzles attached.

Gas meters: Calibrated using a critical orifice calibration set.

Nozzle: Four diameter measurements made using a micrometer across the sharpened edges.

Thermocouples: Calibrated using a potentiometric technique.

Gas Analyzers: Calibrated against reference gases using standard calibration gases within the expected range of concentrations from the source.

Calibration data are in Appendix B of this report.

4.0 RESULTS AND DISCUSSION

The results of the source emissions testing campaign are provided and discussed in this section.

Appendices B through D contain supporting information including calibration information, field data sheets, and calculations.

4.1 EXHAUST STACK SAMPLE LOCATION DETAILS

Table 4.1 provides a summary of the sample location details for each exhaust stack sampled.

Table 4.1 Sample Location Details

Parameter	Recovery Boiler	Power Boiler
Stack Height – Above Grade (m)	69	51
Stack Diameter at Sampling Ports (m)	3.51	1.93*
Stack/Duct Description	Circular	Circular
Stack Orientation	Vertical	Vertical
Number of Sample Ports	4	2
Sample Port Diameter (m)	0.1	0.1
Location Upstream from any Disturbance	>2	>2
Location Downstream from any Disturbance	1.45	>4
Ideal or Non Ideal Flow Characteristics at The Sample Location ¹	Non Ideal	Non Ideal

SOURCE EMISSIONS TESTING – RECOVERY BOILER AND POWER BOILER, WINTER 2015

Table 4.1 Sample Location Details

Parameter	Recovery Boiler	Power Boiler
Total Number of Sample Points for PM	24	24
Number of Sample Points per Traverse for PM	12	12
Sample Time per Point for PM (min)	5	5
Sample time per Test for PM (min)	120	120
Sample time per Test for TRS (min)	NA	NA
Sample time per Test for gases (min)	30	30

*Diameter confirmed while testing during the week of March 9th

4.2 RECOVERY BOILER

The results of the source emissions testing for total particulate matter and combustion gases from the Recovery Boiler exhaust stack are in Tables 4.2 and 4.3, respectively.

Table 4.2 Source Testing Results - Recovery Boiler - Particulate Matter

Parameter	Test #1	Test #2	Test #3	Average	Stack Emission Limit (Table 1 of Approval)
Test Date	Mar. 10, 2015	Mar. 10, 2015	Mar. 11, 2015	-	-
Test Start	9:00 AM	12:15 PM	9:20 AM	-	-
Test Duration (min)	120	120	120	120	-
Volume of Gas Sampled (Rm ³)	1.81	1.87	1.75	1.81	-
Average Isokineticity (%)	105	102	104	103	-
Total Volume of Moisture Collected in Impingers (mL)	540	542	541	541	-
Particulate Matter From Filter and Probe Wash (mg)	2,474	2,779	2,220	2,491	-
Particulate Matter From Impingers (mg)	1.94	4.54	3.27	3.25	-
Exhaust Gas Parameters					
Exhaust Gas Temperature (°C)	67.6	67.8	63.9	66.4	-
Exhaust Gas Moisture Content (%)	28.9	28.3	29.5	28.9	-
Exhaust Gas Velocity (m/s)	13.7	14.5	13.7	14.0	-
Exhaust Gas Volumetric Flow Rate (Rm ³ /s)	83.3	88.6	81.7	84.6	-
Oxygen - O ₂ (%)	4.80	4.50	4.39	4.56	-
Carbon Dioxide - CO ₂ (%)	15.6	15.9	16.1	15.9	-

SOURCE EMISSIONS TESTING – RECOVERY BOILER AND POWER BOILER, WINTER 2015

Table 4.2 Source Testing Results - Recovery Boiler - Particulate Matter

Parameter	Test #1	Test #2	Test #3	Average	Stack Emission Limit (Table 1 of Approval)
<u>Total Particulate Matter - PM</u>					
Concentration at 11% O ₂ (mg/Rm ³)	842	898	759	833	375*
Emission Rate (kg/hr)	411	474	373	419	-
Legend: °C Degrees Celsius. m/s Metres per second. Rm ³ /s Dry cubic metres per second at reference conditions (25°C and 101.3 kPa). mg/Rm ³ Milligrams per dry cubic metre at reference conditions (25°C and 101.3 kPa). kg/hr Kilograms per hour. *For the period between the issuance of Approval No. 2011-076657-R03 and the commissioning of the recovery boiler precipitator system, the particulate emission limit for the Recovery Boiler is 375 mg/Rm ³ .					

The average measured concentration of particulate matter was 833 mg/Rm³ (corrected to 11% O₂), which is above the stack emission limit of 375 mg/Rm³ presented in Table 1 of the facility's Approval.

Table 4.3 Source Testing Results - Recovery Boiler - Combustion Gases

Parameter	Test #1	Test #2	Test #3	Average
Test Date	Mar. 10, 2015	Mar. 10, 2015	Mar. 11, 2015	-
Test Duration (min)	30	30	30	30
Exhaust Gas Volumetric Flow Rate (Rm ³ /s)	83.3	88.6	81.7	84.6
<u>Sulphur Dioxide - SO₂</u>				
Concentration (ppm)	8.14	6.14	27.9	14.0
Concentration (mg/Rm ³)	13.1	9.72	43.8	22.2
Emissions Rate (kg/hr)	6.40	5.14	21.5	11.0
<u>Nitrogen Oxides - NO_x</u>				
Concentration (ppm)	23.7	46.1	52.1	40.7
Concentration (mg/Rm ³)	27.4	52.4	58.8	46.2
Emissions Rate (kg/hr)	13.4	27.7	28.9	23.3
<u>Carbon Monoxide - CO</u>				
Concentration (ppm)	1,772	2,817	3,083	2558
Concentration (mg/Rm ³)	1,248	1,947	2,116	1770
Emissions Rate (kg/hr)	609	1,029	1,039	892
Legend: Rm ³ /s Dry cubic metres per second at reference conditions (25°C and 101.3 kPa). mg/Rm ³ Milligrams per dry cubic metre at reference conditions (25°C and 101.3 kPa). kg/hr Kilograms per hour. NA Not Applicable				

The emission rates for SO₂, NO_x and CO for the Recovery Boiler were 11.0 kg/hr, 23.3 kg/hr and 892 kg/hr, respectively.

SOURCE EMISSIONS TESTING – RECOVERY BOILER AND POWER BOILER, WINTER 2015

4.3 POWER BOILER

The results of the source emissions testing for total particulate matter and combustion gases from the Power Boiler exhaust stack are in Tables 4.4 and 4.5, respectively.

Table 4.4 Source Testing Results - Power Boiler - Particulate Matter

Parameter	Test #1	Test #2	Test #3	Average	Stack Emission Limit (Table 1 of Approval)
Test Date	Mar. 10, 2015	Mar. 11, 2015	Mar. 11, 2015	-	-
Test Start	8:47 AM	12:00 PM	2:52 PM	-	-
Test Duration (min)	120	120	120	120	-
Volume of Gas Sampled (Rm ³)	1.50	1.34	1.48	1.44	-
Average Isokineticity (%)	107	108	105	106	-
Total Volume of Moisture Collected in Impingers (mL)	291	260	285	278	-
Particulate Matter From Filter and Probe Wash (mg)	220	239	229	229	-
Particulate Matter From Impingers (mg)	4.8	3.0	4.2	4.0	-
Exhaust Gas Temperature (°C)	64.7	65.1	63.9	64.6	-
Exhaust Gas Moisture Content (%)	20.8	20.8	20.7	20.8	-
Exhaust Gas Velocity (m/s)	18.9	17.1	19.1	18.4	-
Exhaust Gas Volumetric Flow Rate (Rm ³ /s)	38.2	34.4	38.5	37.0	-
Oxygen - O ₂ (%)	10.8	11.4	9.7	10.6	-
Carbon Dioxide - CO ₂ (%)	9.79	9.26	11.0	10.0	-
<u>Total Particulate Matter - PM</u>					
Concentration at 11% O ₂ (mg/Rm ³)	143	185	137	155	150
Emission Rate (kg/hr)	20.1	22.1	21.5	21.2	-
Legend: °C Degrees Celsius. m/s Metres per second. Rm ³ /s Dry cubic metres per second at reference conditions (25°C and 101.3 kPa). mg/Rm ³ Milligrams per dry cubic metre at reference conditions (25°C and 101.3 kPa). kg/hr Kilograms per hour. ND Non-detectable					

The average measured concentration of particulate matter (corrected to 11% O₂) was 155 mg/Rm³, which is slightly above the stack emission limit of 150 mg/Rm³ presented in Table 1 of the facility's Approval (No. 2011-076657-R02). Only one out of the three tests was above the limit.

SOURCE EMISSIONS TESTING – RECOVERY BOILER AND POWER BOILER, WINTER 2015

Table 4.5 Source Testing Results - Power Boiler - Combustion Gases

Parameter	Test #1	Test #2	Test #3	Average
Test Date	Mar. 10, 2015	Mar. 11, 2015	Mar. 11, 2015	-
Test Duration (min)	30	30	30	30
Exhaust Gas Volumetric Flow Rate (Rm ³ /s)	38.2	34.4	38.5	37.0
<u>Sulphur Dioxide - SO₂</u>				
Concentration (ppm)	ND	ND	ND	ND
Concentration (mg/Rm ³)	ND	ND	ND	ND
Emissions Rate (kg/hr)	ND	ND	ND	ND
<u>Nitrogen Oxides - NO_x</u>				
Concentration (ppm)	16.1	21.0	26.3	21.1
Concentration (mg/Rm ³)	29.7	41.0	43.7	38.1
Emissions Rate (kg/hr)	4.18	4.89	6.86	5.31
<u>Carbon Monoxide - CO</u>				
Concentration (ppm)	1,734	2,079	1,936	1,916
Concentration (mg/Rm ³)	1,940	2,470	1,960	2,123
Emissions Rate (kg/hr)	273	295	307	292
Legend: Rm ³ /s Dry cubic metres per second at reference conditions (25°C and 101.3 kPa). mg/Rm ³ Milligrams per dry cubic metre at reference conditions (25°C and 101.3 kPa). kg/hr Kilograms per hour.				

The average emission rates of NO_x and CO from the Power Boiler were 5.31 kg/hr and 292 kg/hr, respectively. No SO₂ was detected.

4.4 SUMMARY OF RESULTS

Currently there are specified regulatory limits in the facility's approval (2011-076657-R03) for emissions of PM for the Recovery Boiler and the Power Boiler. The measured concentration of PM from the Power Boiler was slightly above the regulatory stack limit. The measured concentration of PM from the Recovery Boiler was above its respective regulatory limit.

5.0 CLOSURE

This report has been prepared for the sole benefit of Northern Pulp Nova Scotia Corporation. This report may not be relied upon by any other person or entity without the express written consent of Stantec and Northern Pulp Nova Scotia Corporation. Any use of this report by a third party, or any reliance on decisions made based upon this report, are the responsibility of the third party. Stantec accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.

Stantec makes no representation or warranty with respect to this report, other than the work was undertaken by trained professional and technical staff in accordance with generally accepted engineering and scientific practices current at the time the work was performed. Any

SOURCE EMISSIONS TESTING – RECOVERY BOILER AND POWER BOILER, WINTER 2015

information or facts provided by others and referred to or utilized in the preparation of this report was assumed by Stantec to be accurate.


This study was undertaken exclusively for the purpose outlined herein and was limited to those contaminants and sources specifically referenced in this report. It should be noted that the measurements were taken over a relatively short time period on-site, and the emissions results may be considered representative only for the conditions present at the time of testing. This report cannot be used or applied under any circumstances to another location or situation or for any other purpose without further evaluation of the data and related limitations.

This report was developed by Gillian Hatcher, M.A.Sc. and reviewed by Vicki Corning, P.Eng. and Mark Scaplen, P.Eng.

If you have any questions regarding the contents of this report, or require any additional information, please do not hesitate to contact the undersigned.



Gillian Hatcher, M.A.Sc.
Project Manager
Tel: (902) 468-7777



Vicki Corning, P.Eng.
Associate, Environmental Services
Tel: (506) 452-7000

Appendix A

Pre-test Plan



Stantec Consulting Ltd.
102 - 40 Highfield Park Drive
Dartmouth NS B3A 0A3
Tel: (902) 468-7777
Fax: (902) 468-9009

February 20, 2015
File: 121413456

Attention: Mr. Marc Theriault
Nova Scotia Environment
20 Pumphouse Road
Pictou, NS B2H 5C6

Dear Mr. Theriault,

**Reference: Pre-Test Plan for Source Emissions Testing Northern Pulp,
Pictou Mill – 2015 Calendar Year**

Please accept this Pre-test Plan for the completion of source emissions required at the Pictou Mill in New Glasgow, Nova Scotia for the 2015 calendar year.

Introduction

Northern Pulp is required to perform source emissions testing on the Recovery Boiler, Lime Kiln, Smelt Dissolving Tank, Power Boiler and the High Level Roof Vent to fulfil the conditions specified in the current Certificate of Approval (CoA) to Operate 2011-076657-R03. The required annual testing for 2015 consists of:

- Recovery Boiler and Power Boiler particulate matter testing 4 times per year;
- Lime Kiln and Smelt Dissolving Tank particulate matter testing 2 times per year;
- Lime Kiln, High Level Roof Vent and Smelt Dissolving Tank total reduced sulphur (TRS) testing 2 times per year;
- One PM_{2.5} testing event per year on the four stacks noted above for particulate matter; and
- One Chlorine (Cl) and Chlorine Dioxide (ClO₂) event per year on the bleach plant exhaust (High Level Roof Vent being the source of these emissions).

Test Program Organization

The source emissions testing will be performed for:

Company Name:	Northern Pulp
Company Address:	P.O. Box 549, Station Main, New Glasgow, NS, B2H 5E8
Contact Name:	
Position:	Environmental/Technical Leader
Telephone Number:	(902) 752-8461
Email:	info@northernpulp.com



**Reference: Pre-Test Plan for Source Emissions Testing Northern Pulp,
Pictou Mill – 2015 Calendar Year**

Sampling Company: Stantec Consulting Ltd.
Project Manager: Gillian Hatcher
Telephone Number: (902) 468-7777
Fax Number: (902) 468-9009
Email: Stantec.com

Key Sampling Team: (with support from other staff as needed)

Source Emissions Testing Program

The proposed source emissions testing methodology and proposed sampling timeframes are presented in Table 1.

Table 1 Source Emissions Testing Matrix

Source	Number of Visits	Number of Tests per Visit	Parameter	Sampling Method	Proposed Timeframe
Recovery Boiler	4	3	Total Particulate Matter (PM)	EPS 1/RM/8	Winter, Spring, Summer, Fall
	4	3	Combustion Gases	EPS 1/RM/15	Winter, Spring, Summer, Fall
	1	3	Particle Size Analysis	Microscopic technique	Fall
Power Boiler	4	3	Total Particulate Matter (PM)	EPS 1/RM/8	Winter, Spring, Summer, Fall
	4	3	Combustion Gases	EPS 1/RM/15	Winter, Spring, Summer, Fall
	1	3	Particle Size Analysis	Microscopic technique	Fall
Lime Kiln	2	3	Total Particulate Matter (PM)	EPS 1/RM/8	Spring, Fall
	2	3	Combustion Gases	EPS 1/RM/15	Spring, Fall
	1	3	Particle Size Analysis	Microscopic technique	Fall
	2	3	Total Reduced Sulphur (TRS)	US EPA Method 16B/C	Spring, Fall
Smelt Dissolving Tank	2	3	Total Particulate Matter (PM)	EPS 1/RM/8	Spring, Fall
	2	3	Combustion Gases	EPS 1/RM/15	Spring, Fall
	1	3	Particle Size Analysis	Microscopic technique	Fall
	2	3	Total Reduced Sulphur (TRS)	US EPA Method 16B/C	Winter, Summer
High Level Roof Vent	2	3	Total Reduced Sulphur (TRS)	US EPA Method 16B/C	Spring, Fall
	2	3	Combustion Gases	EPS 1/RM/15	Spring, Fall



**Reference: Pre-Test Plan for Source Emissions Testing Northern Pulp,
Pictou Mill – 2015 Calendar Year**

Table 1 Source Emissions Testing Matrix

Source	Number of Visits	Number of Tests per Visit	Parameter	Sampling Method	Proposed Timeframe
	1	3	Chlorine and chlorine dioxide	NCASI Special Report 91-07	Spring
Note: Timeframes are as follows based on the approval deadlines-Winter: January-March 31, 2015, Spring: April – June 30, 2015, Summer: July-September 30, 2015, Fall: October-December 31, 2015					

Details of each of the methods identified in Table 1, in addition to the preliminary testing methodology, are provided in the sections that follow.

Preliminary Testing: Upon arrival at each sampling location, Stantec will set up the source emissions testing equipment and conduct a preliminary survey to measure the average velocity, flue gas composition, and moisture content in the stack gases using EPS 1/RM/8 Methods B, C, and D, respectively. The data from this survey will be used to determine the appropriate nozzle size to conduct isokinetic sampling (where the velocity of the gas entering the nozzle is equal to the gas velocity in the stack) for particulate matter during the official testing part of the work. Verification for cyclonic or reverse flow will also be conducted during the preliminary survey, according to procedures outlined in the Environment Canada reference method EPS 1/RM/8.

Should fluctuations in the velocity pressure at a selected traverse point exceed 20% of the average pressure for that point; the diameter of the testing cross section will be reduced to include only those areas along the traverse which meet this requirement (less than 20% of the average). Although the diameter may be reduced, the number of sampling points along each traverse will remain the same as determined from EPS 1/RM/8, Method A, using the equivalent diameter.

Volumetric flow and exhaust gas emissions will be calculated using the full cross sectional area.

Particulate Matter: The source emissions testing of the Recovery Boiler, Lime Kiln, Smelt Dissolving Tank, and the Power Boiler for total particulate matter will be conducted in accordance with the Environment Canada reference method EPS 1/RM/8, entitled "Measurement of Releases of Particulate from Stationary Sources". In addition the alignment approach, as specified in the US EPA Guidance Document – GD-008, will be applied when source testing the Lime Kiln due to the cyclonic flow this source exhibits.

The particulate sampling train, used specifically for isokinetic sampling, is described in detail in EPS 1/RM/8, and is generally referred to as the "Method 5" sampling train for particulate matter (after the US EPA protocol). The sampling train has several different components which include: a heated sampling probe (a nozzle, stainless steel liner, thermocouple, and pitot tube assembly), a heated sample case containing a filter, an ice box containing impinger glassware, and an



**Reference: Pre-Test Plan for Source Emissions Testing Northern Pulp,
Pictou Mill – 2015 Calendar Year**

umbilical cord leading to the pump, and control console. A schematic of the sampling system is shown in Figure 1.

For all source tests, leak checks of the sampling train will be performed as per accepted US EPA and Environment Canada methods. For each official test, two (2) traverses with up to twelve (12) sampling points per traverse will be used. Sampling will be conducted for five (5) minutes per sampling point, up to a maximum sampling time of 120 minutes per test.

The amount of material caught in the impingers will be determined gravimetrically and reported separately from the calculated total particulate matter emissions. All particulate matter samples will be recovered and analyzed at the Stantec laboratory in Fredericton, NB.

Microscopic Analysis (Fine Particulate, PM_{2.5}): As per the facility's Industrial Approval to Operate, the Environment Canada EPS 1/RM/55 or an alternative method acceptable to the Department is required for PM_{2.5} testing. As the method quoted in the approval is not valid for stacks with potential for entrained water droplets in the exhaust (which applies to boilers and dissolving tank at Northern) or cyclonic flow (which applies to the Lime Kiln), we propose microscopic analysis of filters as the viable option. This method involves analysis of total particulate matter filters (collected as described above) for fine particulate percentage.

The particle size analyses will be performed by MVA Scientific Consultants, based in Duluth, GA, using a JEOL JSM-6500F field emission scanning electron microscope operating in automated mode under the control of a Thermo Scientific Noran System SIX x-ray analysis system, using their automated particle size analysis method.

Total Reduced Sulphur: The source emissions testing of the Lime Kiln, the Smelt Dissolving Tank and the High Level Roof Vent for total reduced sulphur will be conducted in accordance with US EPA Method 16B. In this method, the sample is extracted from the exhaust gas of the stack through a heated Teflon line. The sample is chilled and then passes through an SO₂ analyzer to measure SO₂ from the source. The sample exits the analyzer and is then passed through a furnace where all sulphur compounds in the gas stream are thermally oxidized to SO₂, this SO₂ is measured in a second inline analyzer. The difference in the initial SO₂ and the final SO₂ measurement is the total reduced sulphur concentration (reported as H₂S). The analyzers are both Western Research SO₂ non-dispersive ultra-violet (NDUV) continuous analyzer. Monitoring will be conducted continuously over a 24 hour period as required by the approval condition.

Chlorine, Chlorine Dioxide (Cl₂, ClO₂): Sampling will be conducted in accordance with NCASI's sampling method which consists of the extraction of a sample bubbling through midjet impingers and subsequent analysis by titration. The sampling train for the Cl₂ and ClO₂ consists of series of three mini impingers, connected by Teflon tubing. The first two impingers each contain 20 ml of potassium iodide (KI) solution buffered with potassium di-hydrogen phosphate (KH₂PO₄). The third impinger contains silica gel to remove any remaining moisture from the gas stream. The impingers are cooled by an ice bath, and the dried gas is then drawn through the sampling train with a calibrated pump. Total sampling time for each test is sixty (60) minutes.



**Reference: Pre-Test Plan for Source Emissions Testing Northern Pulp,
Pictou Mill – 2015 Calendar Year**

Following completion of each test for Cl_2 and ClO_2 , the contents of the first two impingers are combined in a pre-cleaned beaker. Subsequent analysis via titration will be performed onsite by Stantec. The combined impinger solutions and de-ionized water rinse of the sample line and empty impingers would be titrated with sodium thiosulphate solution (0.010 N). The volume of titrant required to reach the first colorless endpoint would be recorded on a recovery data form. Five (5) ml of 10% sulphuric acid would be added to the sample and the titration continued. The volume of titrant required to reach the second colorless endpoint would be recorded on a recovery data form. These titrations would be conducted on site shortly following sampling by one of the field staff during the testing due to the instability of the samples, which begin to degrade after 24 hours.

Combustion Gases:

The combustion gases (O_2 , CO_2 , CO, NO_x , and SO_2) will be sampled according to the Environment Canada reference method EPS 1/RM/15, entitled *Reference Method for the Monitoring of Gaseous Emissions from Fossil Fuel-fired Burners*. In this method, samples of flue gas are drawn through a probe, non-isokinetically, from a single point near the centre of the stack. An ENERAC Model 500 Micro-Emission Analyzer, manufactured by ENERAC Inc., will be used to conduct the sampling. The Model 500 is equipped with a flue gas probe that has an integrated filter trap and condensate trap, and a housing unit that contains the pump and the electrochemical cells which are used to measure concentrations of sulphur dioxide, nitrogen oxides, carbon monoxide, carbon dioxide, and oxygen.

In accordance with the regulatory requirements for compliance testing, three replicate tests for each contaminant will be conducted on each stack.

Reporting

As per Approval No. 2011-076657-R03, actual particulate matter emission rates will be reported in units of g/s. The concentration released to the atmosphere will be reported in units of mg/m^3 at reference conditions of 25 °C and 101.3 kPa corrected for 11 % oxygen for the Recovery Boiler and Power Boiler and in units of kg/adubmt for the Lime Kiln and the Dissolving Tank. Fine particulate matter concentrations for the Lime Kiln, Dissolving Tank, Power Boiler and Recovery Boiler will be reported in units of mg/m^3 at reference conditions of 25 °C and 101.3 kPa corrected for 11 % oxygen. Total reduced sulphur will be reported in units of parts per million by dry volume (ppmdv). Emission rates of chlorine and chlorine dioxide from the High Level Roof Vent will be reported in units of g/s and the concentrations released to the atmospheric will be reported in units of mg/m^3 .

Results of each source emissions testing event will be documented in a final report for submission to Nova Scotia Environment (NSE) for review and approval within 60 days of completing the testing.




**Reference: Pre-Test Plan for Source Emissions Testing Northern Pulp,
Pictou Mill – 2015 Calendar Year**

Sampling Locations

The number and location of sample points along each traverse were previously determined according to EPS 1/RM/8, Method A, using the exhaust stack diameter. A diagram of a typical sample location is provided in Figure 2.

Figure 1 Source Emission Testing, Method 5 Sampling Train






February 20, 2015
Mr. Marc Theriault
Page 7 of 12

Reference: Pre-Test Plan for Source Emissions Testing Northern Pulp,
Pictou Mill – 2015 Calendar Year

Figure 2 Source Emissions Testing, Sample Location Details





**Reference: Pre-Test Plan for Source Emissions Testing Northern Pulp,
Pictou Mill – 2015 Calendar Year**

A summary of the sample location details is provided in Table 2.

Table 2 Sample Location Details

Parameter	Recovery Boller	Lime Kiln	Smelt Dissolving Tank	Power Boiler Scrubber Stack	High Level Roof Vent
Stack Height – Above Grade (m)	69	37	51	51	65
Diameter / Equivalent Diameter (m)	3.51	1.22 ³	1.22	1.93	1.83
Stack/Duct Description	Circular	Circular	Circular	Circular	Circular
Stack Orientation	Vertical	Vertical	Vertical	Vertical	Vertical
Location of Source Testing	In Stack	In Stack	In Stack	In Stack	In Stack
Number of Sample Ports	4	2	2	2	1
Sample Port Diameter (m)	0.1	0.15	0.1	0.1	0.1
Location Upstream from any Disturbance,	>2	2	>2	>2	-
Location Downstream from any Disturbance,	1.45	8	6	> 4	-
Ideal or Non Ideal Flow Characteristics at The Sample Location ¹	Not Ideal	Not Ideal ²	Not Ideal	Not Ideal	-
Total Number of Sample Points	24 (for PM)	24 (for PM) 1 (for TRS)	20 (for PM) 1 (for TRS)	24 (for PM)	1 (for TRS and Cl, ClO ₂)
Number of Sample Points per Traverse (PM sampling)	12	12	10	12	NA
Sample Time per Point for PM samples (min)	5	5	5	5	NA
Sample time per Test for PM (min)	120	120	100	120	NA
Sample time per Test for combustion gas (min)	30	30	30	30	30 (for TRS) 60 (for Cl, ClO ₂)
Sample time per Test for TRS (min)	NA	1,440	1,440	NA	1,440

¹ The exhaust gas flow characteristics at the sampling location are referred to as being "Ideal" if the sample ports are located in a straight section of stack at least eight stack diameters downstream and two stack diameters upstream of any flow disturbance.

² The lime kiln sampling location has been changed from ideal to not ideal due to the cyclonic flow.

³ Field measurement – to be confirmed during the Winter/Spring Event

Quality Assurance / Quality Control

Throughout the stack testing program, rigorous quality assurance and quality control procedures will be applied to ensure the collection of reliable, representative, and reproducible emissions data. All equipment will be calibrated according to the protocols as prescribed by Environment Canada, and the US EPA. These calibrations include the following:



**Reference: Pre-Test Plan for Source Emissions Testing Northern Pulp,
Pictou Mill – 2015 Calendar Year**

Pitots:	calibrated in a wind tunnel with probe and nozzles attached;
Gas meters:	calibrated against a critical orifice set;
Thermocouples:	calibrated using a potentiometric technique;
Nozzle:	four diameter measurements made using a micrometer across the sharpened edges; and
Combustion Gas Analyser:	2 point calibrations using span gases of known concentrations.

Calibration data will be provided in the final report.

Quality control checks will be performed at several stages during the testing program to ensure the collection of representative samples and the generation of valid results. These checks are performed by test personnel throughout the program under the guidance of the source testing crew chief. The Quality Control (QC) checks include the following:

- Use of standardized checklists and field notebooks to ensure completeness, traceability, and comparability of the process information and samples collected;
- Field checking of standardized forms by a second person to ensure accuracy and completeness;
- Strict adherence to sample chain-of-custody procedures;
- Use of appropriate field blanks (e.g., filter and solution samples); and
- Leak checks of sample trains.

All internal quality assurance and quality control procedures will be strictly adhered to during all test programs to ensure the production of useful and high quality data throughout the course of the program.

Qualifications of Source Testing Team

The successful completion of this project requires the skills of competent and experienced professionals who have a strong commitment to complete the project quickly and efficiently and to produce high quality results. The source testing team we have assembled to meet the challenges of this assignment consists of highly trained professionals who bring a broad range of expertise and experience to the project. The following paragraphs provide brief descriptions of the qualifications of the source emissions testing team:

Senior Reviewer:



February 20, 2015
Mr. Marc Theriault
Page 10 of 12

**Reference: Pre-Test Plan for Source Emissions Testing Northern Pulp,
Pictou Mill – 2015 Calendar Year**

Project Manager and Report Writer:



February 20, 2015
Mr. Marc Theriault
Page 11 of 12

**Reference: Pre-Test Plan for Source Emissions Testing Northern Pulp,
Pictou Mill – 2015 Calendar Year**

Source Testing Team:

Schedule

Table 3 provides an overview of the proposed schedule to complete the testing, as described in the above sections, for the 2015 calendar year. Stantec will confirm actual test dates, in writing, with NSE within thirty days prior to the testing commencing.

Currently we are proposing to conduct the winter testing event within the week of March 9th.



February 20, 2015
Mr. Marc Theriault
Page 12 of 12

**Reference: Pre-Test Plan for Source Emissions Testing Northern Pulp,
Pictou Mill – 2015 Calendar Year**

Table 3 Proposed Schedule

Event	Proposed Date	Scope
Winter	February-March 31 (March 9 th week)	Recovery and Power Boiler PM, gases, dissolving tank TRS
Spring	April-June 30	Recovery, Power Boiler, kiln, dissolving tank PM, gases, kiln, HLRV TRS, HLRV chlorine
Summer	July-Sept. 30	Recovery and Power Boiler PM, gases, dissolving tank TRS
Fall	October-Dec. 31	Recovery, Power Boiler, kiln, dissolving tank PM, PM _{2.5} , gases, kiln, HLRV TRS

Closing

Your timely written approval of this pre-test plan is greatly appreciated. If you have any questions, please do not hesitate to contact me directly at (902) 468-7777.

Regards,

STANTEC CONSULTING LTD.

Gillian Hatcher
Project Manager – Environmental Services
Phone: (902) 468-7777
Fax: (902) 468-9009
@stantec.com

Vicky Corning
Team Lead
Phone: (506) 457-3200
Fax: (506) 452-7652
@stantec.com

v:\1214\active\121413xxx\121413456_2015_stack_testing_np\reporting\pre-test plan\pre-test plan northern pulp_2015_vc.docx

Appendix B

Calibration Data

VALLEY ENVIRONMENTAL CALIBRATION SERVICES


PITOT TUBE CALIBRATION REPORT

CLIENT - Stantec
PROBE ID - 8-1 FT M5
NOZZLE - #6- 0.1875"
DATE - March 3, 2015

FAN SPEED	STANDARD	PROBE
m/s	PITOT (mm H2O)	PITOT (mm H2O)
0.00	0.00	0.00
12.1	8.70	13.00
13.7	11.20	16.80
15.2	13.90	20.70
16.6	16.50	24.70
18.1	19.70	29.90

PITOT FACTOR C_p = 0.816

PITOT - 8-1 FT M5 NOZZLE - #6- 0.1875"
March 3, 2015



Technician: T. Ryan

Signature

VALLEY ENVIRONMENTAL SERVICES
160 Pony Drive #1
Newmarket, Ontario L3Y 7B6
PH: (905) 830 0136
FAX: (905) 830 0137

Tunnel	VES
Std. Pitot C_p	0.999
Static	-0.25
Barometric	29.1
Temperature	65
Abs Static	29.08

Pre-Test Dry Gas Meter - Control Unit Calibration

Date : 1/4/2015
 Barometric Pressure, Pb : 30.06
 Model Number : 1646
 Calibrated By : JB
 Job #:

Orifice Manometer Setting, deltaH (in. H2O)				Dry Gas Meter Volume, Vm (cu.ft)		Temperatures (F)			Time, theta (min)	
							Dry Gas Meter			
					Outlet, to		Average, tm			
1.0					5.460			58	58	10
1.5					5.377			60	60	8
2.3					5.823			61	62	7

Calculations

Orifice Manometer Setting, deltaH (in. H2O)	Dry Gas Correction Factor, gamma (Tolerance = 0.95 - 1.05, +/-1.5% of avg)	Orifice Pressure Differential (delta H _o) yielding 0.75 cfm of air at 68F and 29.92 in.Hg as in. H2O (Tolerance = +/- 0.15 in.)	Orifice Coefficient Ko
1.0	1.023	1.668	0.742
1.5	1.018	1.762	0.725
2.3	1.021	1.755	0.724
Average	1.021	1.728	0.730

Pre-Test Dry Gas Meter - Control Unit Calibration

Date : 1/4/2015
 Barometric Pressure, Pb : 30.06
 Model Number : 1848
 Calibrated By : JB
 Job #:

Orifice Manometer Setting, deltaH (in. H2O)				Dry Gas Meter Volume, Vm (cu.ft)			Temperatures (F)			Time, theta (min)
						Total	Dry Gas Meter			
								Outlet, to	Average, tm	
0.9						5.293		59	59	10
1.5						5.230		61	62	8
2.3						5.657		63	63	7

Calculations

Orifice Manometer Setting, deltaH (in. H2O)	Dry Gas Correction Factor, gamma (Tolerance = 0.95 - 1.05, +/-1.5% of avg)	Orifice Pressure Differential (delta H _o) yielding 0.75 cfm of air at 68F and 29.92 in.Hg as in. H2O (Tolerance = +/- 0.15 in.)	Orifice Coefficient Ko
0.9	1.057	1.608	0.754
1.5	1.049	1.759	0.727
2.3	1.054	1.751	0.725
Average	1.053	1.706	0.735

METHOD 5 DRY GAS METER CALIBRATION USING CRITICAL ORIFICES



- 1) Select three critical orifices to calibrate the dry gas meter which bracket the expected operating range.
- 2) Record barometric pressure before and after calibration procedure.
- 3) Run at tested vacuum (from Orifice Calibration Report), for a period of time necessary to achieve a minimum total volume of 5 cubic feet.
- 4) Record data and information in the GREEN cells, YELLOW cells are calculated.

DATE: 1/4/2015		METER PART #: 1848		METER SERIAL #: 16605036		CRITICAL ORIFICE SET SERIAL #: 14638		BAROMETRIC PRESSURE (in Hg):		INITIAL: 30.06		FINAL: 30.06		AVG (P _{bar}): 30.06		IF Y VARIATION EXCEEDS 2.00%, ORIFICE SHOULD BE RECALIBRATED			
ORIFICE #	RUN #	K' FACTOR (AVG)	TESTED VACUUM (in Hg)	DGM READINGS (FT ³)		TEMPERATURES °F				ELAPSED TIME (MIN)	DGM ΔH (in H ₂ O)	V _m (STD)	(1)	(2)	(3)	Y VARIATION (%)	ΔH _g		
				INITIAL	FINAL	NET (V _m)	AMBIENT	DGM INLET	DGM OUTLET									DGM AVG	
15	1	0.4164	18	951.10	968.38	5.280	17.3	57	60	57	58	58	10.00	0.95	5.4208	5.7312	1.057	1.67	
	2	0.4164	18	956.38	961.67	5.290	17.4	60	61	58	59	59.5	10.00	0.90	5.4147	5.7306	1.058	1.58	
	3	0.4164	18	961.67	968.98	5.310	17.4	61	61	59	60	60.25	10.00	0.90	5.4273	5.7306	1.058	1.58	
												AVG =		1.057		0.38			
18	1	0.5085	18	968.98	972.19	5.210	17.4	61	62	60	61	61	8.00	1.50	5.3252	5.5985	1.051	1.76	
	2	0.5085	18	972.19	977.43	5.240	17.5	62	63	61	61	61.75	8.00	1.50	5.3482	5.5979	1.047	1.76	
	3	0.5085	18	977.43	982.67	5.240	17.5	63	63	61	62	62.25	8.00	1.50	5.3430	5.5979	1.048	1.76	
												AVG =		1.049		-0.43			
23	1	0.6307	18	982.67	988.30	5.630	17.4	63	64	62	62	62.75	7.00	2.30	5.7484	6.0759	1.057	1.75	
	2	0.6307	18	988.30	993.96	5.660	17.5	64	65	62	63	63.5	7.00	2.30	5.7687	6.0753	1.053	1.75	
	3	0.6307	18	993.96	999.64	5.680	17.5	65	65	63	63	64	7.00	2.30	5.7836	6.0753	1.050	1.75	
												AVG =		1.054		0.05			

USING THE CRITICAL ORIFICES AS CALIBRATION STANDARDS:
The following equations are used to calculate the standard volumes of air passed through the DGM, V_m (std), and the critical orifice, V_c (std), and the DGM calibration factor, Y. These equations are automatically calculated in the spreadsheet above.

AVERAGE DRY GAS METER CALIBRATION FACTOR, Y = 1.053

AVERAGE ΔH_g = 1.71

$$(1) \quad V'_{m_{(std)}} = K' \cdot V'_m \cdot \frac{P_{bar} + (\Delta H / 13.6)}{T_m}$$

= Net volume of gas sample passed through DGM, corrected to standard conditions
K₁ = 17.64 °R/in. Hg (English), 0.3858 °K/mm Hg (Metric)
T_m = Absolute DGM avg. temperature (°R - English, °K - Metric)

$$(2) \quad V'_{cr_{(std)}} = K' \cdot \frac{P_{bar} \cdot \Theta}{\sqrt{T_{amb}}}$$

= Volume of gas sample passed through the critical orifice, corrected to standard conditions
T_{amb} = Absolute ambient temperature (°R - English, °K - Metric)
K' = Average K' factor from Critical Orifice Calibration

$$(3) \quad Y = \frac{V'_{cr_{(std)}}}{V'_{m_{(std)}}}$$

= DGM calibration factor

$$\Delta H_g = \left(\frac{0.75 \theta}{V_{cr}(std)} \right)^2 \Delta H \left(\frac{V_{m}(std)}{V_m} \right)$$

METHOD 5 DRY GAS METER CALIBRATION USING CRITICAL ORIFICES



- 1) Select three critical orifices to calibrate the dry gas meter which bracket the expected operating range.
- 2) Record barometric pressure before and after calibration procedure.
- 3) Run at tested vacuum (from Orifice Calibration Report), for a period of time necessary to achieve a minimum total volume of 5 cubic feet.
- 4) Record data and information in the GREEN cells, YELLOW cells are calculated.

METER PART #: 1646		DATE: 1/4/2015		METER SERIAL #: 17485049		CRITICAL ORIFICE SET SERIAL #: 1463s		BAROMETRIC PRESSURE (in Hg):		INITIAL 30.06		FINAL 30.06		AVG (P _{bar}) 30.06		IF Y VARIATION EXCEEDS 2.00%, ORIFICE SHOULD BE RECALIBRATED	
ORIFICE #	RUN #	K'	TESTED VACUUM (in Hg)	DGM READINGS (Ft ³)		TEMPERATURES °F				ELAPSED TIME (MIN)	DGM ΔH (in H ₂ O)	(1) V _m (STD)	(2) V _c (STD)	(3) Y	Y VARIATION (%)	ΔH _g	
				INITIAL	FINAL	AMBIENT	DGM INLET INITIAL	DGM INLET FINAL	DGM OUTLET								DGM AVG
15	1	0.4164	18	896.93	904.37	5.440	17	58	58	58	58	58	58	58	58	58	1.67
	2	0.4164	18	904.37	909.84	5.470	16.5	58	58	58	57	57	57	57	57	57	1.67
	3	0.4164	18	909.84	915.31	5.470	16.5	58	59	57	58	58	58	58	58	58	1.67
18	1	0.5085	17	915.41	920.77	5.360	16.7	60	61	59	59	59	59	59	59	59	1.76
	2	0.5085	17	920.77	926.15	5.380	17.1	61	62	59	50	60.5	60.5	60.5	60.5	60.5	1.76
	3	0.5085	17	926.15	931.54	5.390	17.3	62	61	60	60	60.75	60.75	60.75	60.75	60.75	1.76
23	1	0.6307	17	931.54	937.37	5.830	17.5	61	63	60	61	61.25	61.25	61.25	61.25	61.25	1.76
	2	0.6307	17	937.37	943.18	5.810	17.6	63	64	61	61	62.25	62.25	62.25	62.25	62.25	1.76
	3	0.6307	17	943.18	949.01	5.830	17.6	64	65	61	62	63	63	63	63	63	1.75

AVG = 1.023

AVG = 1.020

AVG = 1.018

AVG = 1.021

AVG = 1.021

AVG = 1.021

AVG = 1.021

AVG = 1.021

AVERAGE DRY GAS METER CALIBRATION FACTOR, Y = **1.021**

(1) $V'_{m_{(std)}} = K' * V'_m * \frac{P_{bar} + (\Delta H / 13.6)}{T_m}$

(2) $V'_{cr_{(std)}} = K' * \frac{P_{bar} * \Theta}{\sqrt{T_{amb}}}$

(3) $Y = \frac{V'_{cr_{(std)}}}{V'_{m_{(std)}}}$

= Net volume of gas sample passed through DGM, corrected to standard conditions

$K' = 17.64 \text{ }^{\circ}\text{R/in. Hg (English), } 0.3858 \text{ }^{\circ}\text{K/mm Hg (Metric)}$

$T_m = \text{Absolute DGM avg. temperature (}^{\circ}\text{R - English, }^{\circ}\text{K - Metric)}$

= Volume of gas sample passed through the critical orifice, corrected to standard conditions

$T_{amb} = \text{Absolute ambient temperature (}^{\circ}\text{R - English, }^{\circ}\text{K - Metric)}$

$K' = \text{Average K' factor from Critical Orifice Calibration}$

= DGM calibration factor

AVERAGE ΔH_g = **1.73**

$\Delta H_g = \left(\frac{0.75 \theta}{V_c (std)} \right)^2 \Delta H \left(\frac{V_m (std)}{V_m} \right)$

USING THE CRITICAL ORIFICES AS CALIBRATION STANDARDS:

The following equations are used to calculate the standard volumes of air passed through the DGM, V_m (std), and the critical orifice, V_c (std), and the DGM calibration factor, Y. These equations are automatically calculated in the spreadsheet above.

Calibration Data
Enerac 500 Combustion Analyzer

Stantec Consulting Ltd.

Location: Fredericton, NB

Date: March 11, 2015

Parameter	Unit	Span Gas Concentration	Pre-Test Calibration		Post Test Check	
			Date	11-Mar-15	Date	11-Mar-15
			Personnel	NGM	Personnel	NGM
			Ambient Air Reading	Span Gas Reading	Ambient Air Reading	Span Gas Reading
CO	ppm	200 1000	0	193 1012	0	200 1001
SO ₂	ppm	200	0	178	0	200
NOX	ppm	200	0	198	0	200

VALLEY ENVIRONMENTAL CALIBRATION SERVICES


PITOT TUBE CALIBRATION REPORT

CLIENT - Stantec
PROBE ID - 2FT M5
NOZZLE - #8- 0.250"
DATE - February 23, 2015

FAN SPEED	STANDARD	PROBE
m/s	PITOT (mm H2O)	PITOT (mm H2O)
0.00	0.00	0.00
12.2	8.90	14.10
13.6	11.10	17.80
15.1	13.70	21.80
16.7	16.70	26.40
18.1	19.70	31.10

PITOT FACTOR C_p = 0.794

PITOT - 2FT M5 NOZZLE - #8- 0.250"
February 23, 2015



Technician: T. Ryan

Signature: 

VALLEY ENVIRONMENTAL SERVICES
160 Pony Drive #1
Newmarket, Ontario L3Y 7B6
PH: (905) 830 0136
FAX: (905) 830 0137

Tunnel	VES
Std. Pitot C_p	0.999
Static	-0.25
Barometric	29.15
Temperature	65
Abs Static	29.13

Stantec Consulting Ltd.						
Steel Nozzle Calibration Data Sheet						
NozzleID	Nozzle Diameter (inches)					
Set - 1	<1>	<2>	<3>	<4>	Hi-Lo	Avg.
1-4	0.125	0.124	0.125	0.125	0.001	0.125
1-6	0.175	0.173	0.165	0.175	0.010	0.172
1-8	0.236	0.232	0.234	0.232	0.004	0.234
1-10	0.307	0.305	0.308	0.305	0.003	0.306
1-12	0.367	0.372	0.367	0.371	0.005	0.369
1-14	0.434	0.434	0.433	0.434	0.001	0.434
1-16	0.500	0.497	0.503	0.501	0.006	0.500
QA/QC Check						
Each Diameter Measured To Within = 0.001 Inches						
High - Low $\leq$ 0.004						
Prepared By: JJB				Date: Feb 05, 2015		

Appendix C

Field Data Sheets

MOISTURE FIELD DATA SHEET

Project No.: 121413456
 Client: Northern Pulp
 Plant: Pickens NS
 Location: Parker Baler
 Test: PM-1
 Date: Mar 10, 2015
 Analyst: TBH



Moisture Data

Impinger No.	Impinger Contents	Final Weight (g)	Tare Weight (g)	Weight of Moisture (g)
1	100 mL H2O	819.5	726.5	93
2	100 mL H2O	643.1	603.7	39.4
3	Blank	667.7	657.0	10.7
4	200g Silica Gel	994.1	980.8	13.3
Total Weight Gain (g)				156.4
Moisture Volume (mL)				156.4

Volume H₂O Collected: 156.4 ml
 X 0.048 = 7.51 ft³ H₂O (Vwc)

DGM Final 50.82 ft³
 DGM Initial 0.92 ft³

Final - Initial = 49.9 ft³ (Vmc)

Moisture = $\frac{Vwc}{(Vwc + Vmc)}$

Moisture = 0.1308

Moisture = 0.13

1/2

SOURCE TESTING FIELD DATA SHEET

Job No.: 121413456
Client: Northern NJ
Plant: Piscataway
Location: Paver Bldg
Test: PM-1
Date: Nov 10, 2015
Operators: TBH/AMM
Gamma: 1.053
Delta H₀: 1.706
Pilot Coeff.: 0.816
Start: 7:15
Finish:

Static Pressure (in.H₂O): 0.20
Port Length (in.): 6"
Stack Dia. (in.): 76"
Probe Length (ft): 8'
Nozzle ID (in.): 1-16 (0.172)
Console S/N: 1848

Pre-Test Leak Check: ✓
Vacuum Pressure: -18
Post-Test Leak Check: ✓
Vacuum Pressure: -18

K': 0.63

Traverse Point	Time (min)	Stack Gas Temp., T _s (F)	Velocity Head, dP (in.H ₂ O)	Orifice dH (in.H ₂ O)	Gas Meter Volume (cu.ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (in.Hg)
									In	Out	
1	0				0.92						
	2.5	121	1.25	0.69	2.05	264	225	37	52	52	-1
	5	120	1.00	0.55	3.03	258	226	40	52	52	-1
2	7.5	119	1.05	0.59	4.04	272	225	43	52	52	-1
	10	119	1.05	0.58	5.04	274	226	43	52	52	-1
3	12.5	120	1.05	0.61	6.07	274	236	45	53	52	-1
	15	119	1.10	0.61	7.12	273	225	45	53	52	-1
4	17.5	119	1.10	0.61	8.17	252	226	45	54	53	-1
	20	119	1.15	0.64	9.21	247	233	45	55	53	-1
5	22.5	119	1.20	0.67	10.27	248	235	47	56	53	-1
	25	119	1.20	0.67	11.30	250	241	49	56	54	-1
6	27.5	119	1.25	0.70	12.32	263	243	49	56	54	-1
	30	121	1.20	0.67	13.55	267	248	51	57	54	-1
7	32.5	121	1.25	0.70	14.67	270	251	51	57	54	-1
	35	122	1.50	0.84	15.88	266	254	51	57	54	-1
8	37.5	122	1.45	0.81	17.08	261	256	55	57	54	-1
	40	120	1.65	0.93	18.20	259	257	56	57	54	-1
9	42.5	120	1.70	0.95	19.65	280	260	52	57	54	-1
	45	120	1.75	0.96	20.92	282	259	52	57	54	-1
10	47.5	120	1.85	1.03	22.26	287	257	50	58	53	-1
	50	120	1.90	1.06	23.57	297	264	50	58	53	-1
11	52.5	120	1.90	1.06	24.95	300	266	50	58	53	-1
	55	120	2.00	1.12	26.32	300	268	56	60	56	-1
12	57.5	120	2.10	1.17	27.72	300	269	56	60	56	-1
	60	120	2.10	1.17	29.09 *	300	271	57	60	56	-1

2/2

SOURCE TESTING FIELD DATA SHEET

Job No.: 71413456
 Client: Northrop
 Plant: Pittsburgh
 Location: Power Boiler
 Test: PAN-1
 Date: Aug 10, 1965
 Operators: TB & LAM
 Gamma: 1.053
 Delta H₀: 1.306
 Pilot Coeff.: 0.516
 Start: _____
 Finish: _____

Static Pressure (in. H₂O): 0.20
 Port Length (in.): 6"
 Stack Dia. (in.): 36"
 Probe Length (ft): 21
 Nozzle ID (in.): 1-C (0.121)
 Console S/N: 1848

Pre-Test Leak Check: _____
 Vacuum Pressure: _____
 Post-Test Leak Check: _____
 Vacuum Pressure: _____
 K: 0.67

Traverse Point	Time (min)	Stack Gas Temp., T _s (F)	Velocity Head, dP (in. H ₂ O)	Orifice dH (in. H ₂ O)	Gas Meter Volume (cu.ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (in. Hg)
									In	Out	
	0				30.33						
1	2.5	120	0.82	0.46	31.15	297	265	63	57	57	-1
	5	120	0.82	0.46	32.18	297	266	64	57	57	-1
2	7.5	120	0.85	0.48	33.09	298	283	64	57	57	-1
	10	120	0.87	0.49	34.04	297	294	64	57	57	-1
3	12.5	127	0.87	0.49	34.96	297	268	64	58	57	-1
	15	127	0.59	0.32	35.83	288	251	64	58	57	-1
4	15	128	0.53	0.29	36.58	294	254	64	58	57	-1
	17.5	130	0.50	0.28	37.34	291	257	64	57	57	-1
5	20.5	130	0.52	0.29	38.09	296	257	64	57	57	-1
	25	130	0.52	0.29	38.84	297	258	63	58	57	-1
6	27.5	130	0.52	0.29	39.58	282	259	62	59	57	-1
	30	130	0.52	0.36	40.35	283	258	61	59	57	-1
7	31.5	129	0.65	0.36	41.17	281	257	61	59	58	-1
	35	128	0.75	0.42	42.00	278	256	59	59	58	-1
8	37.5	127	0.75	0.42	42.88	292	253	56	60	58	-1
	40	128	0.85	0.47	43.77	295	251	53	60	58	-1
9	42.5	129	0.85	0.47	44.69	297	249	51	60	58	-1
	45	128	0.75	0.41	45.61	296	246	49	59	58	-1
10	47.5	129	0.75	0.47	46.47	293	246	48	60	59	-1
	50	129	0.75	0.47	47.34	286	246	47	59	58	-1
11	52.5	129	0.75	0.42	48.21	284	241	46	58	58	-1
	55	128	0.75	0.42	49.08	281	243	46	59	58	-1
12	57.5	128	0.75	0.40	49.95	280	241	44	59	58	-1
	60	128	0.75	0.42	50.82	281	240	44	60	58	-1

Sampling Methodology: Environment Canada EPS 1/RM/15



Project No.: 121413456
Client: Northern Pulp
Plant: Pictou, NS
Location: Power Boiler

Fuel Type: business

Time Start: 2:45
Time Finish: 3:15

Test No.: Gas #1
Date: Mar 16/15

Personnel: TBH

[illegible]

MOISTURE FIELD DATA SHEET

Project No.: 121413456

Client: Northern Pulp

Plant: Paper Boiler

Location: Pictou, NS

Test: PM-2

Date: Mar 10, 2015

Analyst: JJB/TBH



Moisture Data

Impinger No.	Impinger Contents	Final Weight (g)	Tare Weight (g)	Weight of Moisture (g)
1	100 mL H2O	994.3	731.4	262.9
2	100 mL H2O	651.2	628.0	23.2
3	Blank	659.5	659.5	-0.1
4	200g Silica Gel	998.4	994.0	4.4
Total Weight Gain (g)				290.5
Moisture Volume (mL)				290.5

Volume H₂O Collected: 290.5 ml

X 0.048 = 13.94 ft³ H₂O (Vwc)

DGM Final 74.18 ft³

DGM Initial 52.20 ft³

Final - Initial = 21.98 ft³ (Vmc)

Moisture = $\frac{Vwc}{(Vwc + Vmc)}$

Moisture = 0.144966

Moisture = 0.145

1/2

SOURCE TESTING FIELD DATA SHEET

Job No.: 121413456
Client: Northern Pipe
Plant: Power Boiler
Location: Picher MS
Test: PM-2
Date: M
Operators: JLB/AM
Gamma: 1.053
Delta H: 1.306
Pitot Coeff.: 0.816
Start: 8:47
Finish:

Static Pressure (in.H2O): 0.20
Port Length (in.): 6"
Stack Dia. (in.): 76"
Probe Length (ft): 4'
Nozzle ID (in.): 1-6 Co. 172
Console S/N: 1848

Pre-Test Leak Check:
Vacuum Pressure:
Post-Test Leak Check:
Vacuum Pressure:

K: 0.67

Traverse Point	Time (min)	Stack Gas Temp., Ts (F)	Velocity Head, dp (in.H2O)	Orifice dh (in.H2O)	Gas Meter Volume (cu.ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (in.Hg)
									In	Out	
1	2.5	141	1.6	0.89	52.78	791	263	36	410	410	-1
2	5	144	1.3	0.83	54.73	790	267	37	410	410	-1
3	7.5	145	1.8	1.0	55.98	788	264	38	39	40	-1
4	10	145	1.8	1.0	57.28	785	260	37	40	40	-1
5	12.5	148	1.7	0.94	58.54	781	263	36	40	40	-1
6	15	148	1.6	0.88	59.78	780	262	36	40	40	-1
7	17.5	147	1.5	0.83	60.98	780	274	36	41	40	-1
8	20	142	1.5	0.84	62.17	781	275	36	41	40	-1
9	22.5	146	1.0	0.55	63.26	780	266	36	41	40	-1
10	25	148	1.0	0.55	64.21	786	256	37	42	40	-1
11	27.5	149	0.65	0.36	65.14	796	275	36	42	40	-1
12	30	151	0.6	0.33	65.91	793	251	37	42	40	-1
13	32.5	151	0.5	0.27	66.65	793	255	36	42	40	-1
14	35	151	0.5	0.27	67.33	792	242	36	42	40	-1
15	37.5	150	0.45	0.25	68.02	792	259	36	42	40	-1
16	40	149	0.45	0.25	68.68	791	257	35	42	41	-1
17	42.5	151	0.45	0.25	69.35	791	262	35	42	41	-1
18	45	152	0.45	0.25	70.01	792	256	34	42	41	-1
19	47.5	152	0.45	0.25	70.67	795	264	34	42	41	-1
20	50	151	0.45	0.25	71.32	796	258	34	43	41	-1
21	52.5	150	0.5	0.28	72.01	794	266	34	43	41	-1
22	55	151	0.5	0.28	72.73	792	256	34	43	42	-1
23	57.5	149	0.5	0.28	73.45	788	266	34	43	42	-1
24	60	149	0.5	0.28	74.18	786	257	34	44	42	-1

SOURCE TESTING FIELD DATA SHEET

Job No.: 121413456
 Client: Archetype P&P
 Plant: Process Unit
 Location: Unit 2
 Test: PA-2
 Date: Mar 11, 2015
 Operators: JB/M/A
 Gamma: 1.055
 Delta H@: 1300
 Pilot Coeff.: 0.816
 Start: 8:47
 Finish:

Static Pressure (in.H2O): 0.25
 Port Length (in.): 16"
 Stack Dia. (in.): 76"
 Probe Length (ft): 8'
 Nozzle ID (in.): 1-1/2 (0.172)
 Console SN: 1848

Pre-Test Leak Check:
 Vacuum Pressure:
 Post-Test Leak Check:
 Vacuum Pressure:

K: 0.162

Traverse Point	Time (min)	Stack Gas Temp, Ts (F)	Velocity Head, dp (in.H2O)	Orifice dh (in.H2O)	Gas Meter Volume (cu.ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (in.Hg)
									In	Out	
0	0				74.18						
1	2.5	149	1.50	0.77	75.95 *	301	270	34	43	43	-1
2	5	149	1.45	0.74	77.21	300	268	34	43	43	-1
3	2.5	152	1.30	0.66	78.25	298	273	35	45	43	-1
4	10	153	1.20	0.61	79.76	298	290	35	45	43	-1
5	12.5	150	0.9	0.46	80.21	298	272	38	45	43	-1
6	15	153	0.9	0.46	81.08	283	255	38	45	43	-1
7	17.5	152	0.65	0.33	81.93	296	267	38	46	43	-1
8	20	149	0.65	0.33	82.68	298	260	38	46	43	-1
9	22.5	150	0.50	0.26	83.41	298	268	38	46	43	-1
10	25	153	0.50	0.25	83.97	295	259	38	46	43	-1
11	27.5	154	0.90	0.46	84.74	298	267	38	46	43	-1
12	30	151	0.95	0.49	85.63	294	266	38	46	43	-1
13	31.5	150	1.30	0.67	86.59	296	266	38	47	44	-1
14	35	147	1.40	0.77	87.69	296	245	39	47	44	-1
15	37.5	150	1.80	0.93	88.84	298	255	40	48	45	-1
16	40	147	1.80	0.93	90.09	297	260	39	48	45	-1
17	42.5	148	1.80	0.93	91.33	297	263	39	48	45	-1
18	45	150	1.80	0.93	92.56	296	259	39	49	46	-1
19	47.5	150	1.80	0.93	93.80	295	261	39	49	46	-1
20	50	145	1.80	0.93	95.05	292	272	40	49	46	-1
21	52.5	149	1.80	0.93	96.31	292	260	39	49	46	-1
22	55	142	1.80	0.94	97.55	292	266	40	49	46	-1
23	57.5	142	1.80	0.94	98.80	291	265	40	49	46	-1
24	60	141	1.80	0.94	100.05	289	258	40	49	46	-1

COMBUSTION GAS ANALYSIS CONCENTRATION FIELD SHEET

Sampling Methodology: Environment Canada EPS 1/RM/15



Project No.: 121413456

Client: Northern Pulse

Plant: Pickton, NS

Location: Power Boiler

Fuel Type: biomass

Time Start: 9:45

Time Finish: 10:15

Test No.: Gas # 2, 4

Date: Mar 11, 2015

Personnel: TBH

Time	Concentrations							
	O ₂ (%)	CO ₂ (%)	CO (ppm)	SO ₂ (ppm)	NO _x (ppm)	NO (ppm)	NO ₂ (ppm)	THC (%)
0	10.16	10.0	2552	0	15			
5	10.10	10.0	1498	0	16			
10	11.0	9.5	1360	0	17			
15	11.3	9.2	1445	0	17			
20	11.6	8.9	1901	0	15			
25	10.4	10.3	1870	0	16			
30	9.9	10.6	1511	0	17			
0	10.3	10.1	1249	0	17			
5	10.0	10.7	2928	0	16			
10	10.4	11.4	1370	0	24			
15	9.0	11.7	2904	0	27			
20	9.0	11.1	1749	0	33			
25	9.4	11.0	1627	0	34			
30	9.8	10.5	1646	0	33			

1:00
-
4:30

MOISTURE FIELD DATA SHEET

Project No.: 121413456
 Client: NO.
 Plant: Power Boiler
 Location: Pictou, NS
 Test: PM-3
 Date: Nov. 11, 2015
 Analyst: TBH



Moisture Data

Impinger No.	Impinger Contents	Final Weight (g)	Tare Weight (g)	Weight of Moisture (g)
1	100 mL H ₂ O	945.6	715.5	230.1
2	100 mL H ₂ O	643.0	625.6	17.4
3	Blank	653.0	650.7	2.3
4	200g Silica Gel	1004.4	994.3	10.1
Total Weight Gain (g)				260
Moisture Volume (mL)				

Volume H₂O Collected: 260 ml
 $\times 0.048 = \underline{12.48} \text{ ft}^3 \text{ H}_2\text{O (Vwc)}$

DGM Final 144.18 ft³
 DGM Initial 100.51 ft³
 Final - Initial = 43.67 ft³ (Vmc)

Moisture = $\frac{\text{Vwc}}{(\text{Vwc} + \text{Vmc})}$

Moisture = $\frac{12.48}{12.48 + 43.67}$

Moisture = 22.2%

SOURCE TESTING FIELD DATA SHEET

42

Job No.: 12141345C
 Client: Northern Pulp
 Plant: Auburn, MS
 Location: Power Boiler
 Test: PM-2
 Date: May 11, 2015
 Operators: TGH/MM
 Gamma: 1.053
 Delta H@: 1.306
 Pilot Coeff.: 0.814
 Start: 12.00
 Finish:

Static Pressure (in.H2O): 0.20
 Port Length (in.): 6"
 Stack Dia. (in.): 40"
 Probe Length (ft): 8'
 Nozzle ID (in.): 1-4 (0.132)
 Console SN: 1848

Pre-Test Leak Check:
 Vacuum Pressure:
 Post-Test Leak Check:
 Vacuum Pressure:
 K: 0.62

Traverse Point	Time (min)	Stack Gas Temp, Ts (F)	Velocity Head, dp (in.H2O)	Orifice dh (in.H2O)	Gas Meter Volume (cu.ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (in.Hg)
									In	Out	
1	0	151	0.93	0.48	100.51	300	225	41	48	48	-1
2	2.5	152	0.99	0.51	102.42	298	225	43	50	49	-1
3	3.5	152	0.98	0.50	103.35	300	226	43	50	49	-1
4	4.5	150	0.80	0.41	104.70	300	227	43	50	49	-1
5	12.5	150	0.50	0.25	104.99	300	226	43	52	50	-1
6	15	148	0.52	0.27	105.59	300	235	42	53	50	-1
7	17.5	149	0.47	0.24	106.25	301	257	44	52	51	-1
8	20	150	0.47	0.24	106.81	273	257	44	52	51	-1
9	22.5	150	0.44	0.23	107.55	281	261	44	52	52	-1
10	25	148	0.40	0.21	108.00 *	287	265	44	52	52	-1
11	27.5	151	0.30	0.37	108.97	294	265	44	52	52	-1
12	30	151	0.30	0.37	109.77	300	256	42	51	52	-1
13	32.5	151	0.05	0.54	110.76	299	252	42	52	52	-1
14	35	152	1.10	0.57	111.80	297	253	42	52	52	-1
15	38.5	152	1.80	0.73	112.85	300	248	42	52	52	-1
16	40	148	1.40	0.73	113.98	297	242	41	53	51	-1
17	42.5	149	1.70	0.89	115.14	295	218	42	53	52	-1
18	45	144	1.60	0.84	116.30	295	225	42	53	52	-1
19	47.5	142	1.70	0.90	117.57	296	220	41	53	52	-1
20	50	142	1.30	0.90	118.81	295	213	40	53	52	-1
21	52.5	143	1.30	0.89	120.06	293	214	40	53	53	-1
22	55	147	1.30	0.89	121.31	290	220	39	53	52	-1
23	57.5	147	1.30	0.89	122.55	290	219	39	53	52	-1
24	60	144	1.30	0.89	123.98	290	233	39	54	52	-1

SOURCE TESTING FIELD DATA SHEET

2/2

Job No.: 121413456
 Client: Maxium Oil
 Plant: Altoy AS
 Location: Paroia
 Test: PM-3
 Date: Apr 11, 2015
 Operators: TMT/MM
 Gamma: 1.053
 Delta H₀: 1.30%
 Pilot Coeff.: 0.81%
 Start: _____
 Finish: _____

Static Pressure (in.H₂O): 0.20
 Port Length (in.): 6"
 Stack Dia. (in.): 36"
 Probe Length (ft): 8'
 Nozzle ID (in.): 1-6 (0.173)
 Console S/N: 1848

Pre-Test Leak Check: _____
 Vacuum Pressure: _____
 Post-Test Leak Check: _____
 Vacuum Pressure: _____
 K: 0.62

Traverse Point	Time (min)	Stack Gas Temp., T _s (F)	Velocity Head, dP (in.H ₂ O)	Orifice dH (in.H ₂ O)	Gas Meter Volume (cu.ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (in.Hg)
									In	Out	
1	0	147	1.50	0.79	123.98	293	226	42	53	53	-1
2	2.5	148	1.50	0.78	126.17	290	223	41	53	53	-1
3	5	146	1.40	0.74	127.32	286	222	39	53	53	-1
4	3.5	149	1.40	0.73	128.44	288	231	38	54	53	-1
5	10	152	1.30	0.68	129.56	285	231	39	54	53	-1
6	17.5	149	1.30	0.68	130.67	283	237	38	54	53	-1
7	15	149	1.30	0.68	131.77	280	240	39	54	53	-1
8	13.5	149	1.20	0.63	132.85	282	244	39	54	53	-1
9	20	152	1.20	0.62	133.89	282	243	40	54	53	-1
10	22.5	149	1.20	0.63	134.91	289	240	41	53	53	-1
11	25	149	0.90	0.47	135.85	294	239	41	53	53	-1
12	30	147	0.90	0.47	136.80	296	234	42	54	53	-1
13	32.5	149	0.65	0.34	137.68	297	224	43	54	53	-1
14	35	151	0.65	0.34	138.53	291	206	44	53	53	-1
15	37.5	151	0.45	0.24	139.28	289	214	44	53	53	-1
16	40	152	0.45	0.23	139.93	288	213	44	53	53	-1
17	42.5	152	0.30	0.16	140.56	284	210	44	53	53	-1
18	45	151	0.30	0.16	141.16	285	207	44	53	53	-1
19	47.5	151	0.20	0.10	141.30	284	193	44	53	53	-1
20	50	150	0.20	0.10	142.20	285	176	45	53	53	-1
21	52.5	150	0.20	0.10	142.70	284	175	45	53	53	-1
22	55	150	0.20	0.10	143.19	284	191	44	53	53	-1
23	57.5	150	0.20	0.10	143.68	284	207	43	53	53	-1
24	60	148	0.20	0.10	144.18	288	186	43	53	53	-1

Sampling Methodology: Environment Canada EPS 1/RM/15



Project No.: 121413456
Client: Northern Pulp
Plant: Pictou, NS
Location: Power Boiler

Fuel Type: biomass

Time Start: 12:15

Time Finish: 12:45

Test No.: Gas # 3

Date: Mar 11, 2015

Personnel: TBF

[illegible]

MOISTURE FIELD DATA SHEET

Project No.: 121413456
 Client: Northern Pulp
 Plant: Power Boiler
 Location: Pictou NS
 Test: PM-4
 Date: March 11, 2015
 Analyst: TBH



Moisture Data

Impinger No.	Impinger Contents	Final Weight (g)	Tare Weight (g)	Weight of Moisture (g)
1	100 mL H ₂ O	964.7	715.5	
2	100 mL H ₂ O	757.9	735.2	
3	Blank	573.0	570.6	
4	200g Silica Gel	941.7	931.3	
Total Weight Gain (g)				
Moisture Volume (mL)				

Volume H₂O Collected: _____ ml
 X 0.048 = _____ ft³ H₂O (V_{wc})

DGM Final _____ ft³
 DGM Initial _____ ft³
 Final - Initial = _____ ft³ (V_{mc})

Moisture = $\frac{V_{wc}}{(V_{wc} + V_{mc})}$

Moisture = _____

Moisture = _____

SOURCE TESTING FIELD DATA SHEET

Job No.: 121413456
 Client: Northern Dap
 Plant: Power Boiler
 Location: Bldg. N5
 Test: PM-4
 Date: Mar 11, 2015
 Operators: JJB/TEH/JH
 Gamma: 1.053
 Delta H: 1.706
 Pilot Coeff.: 0.816
 Start: _____
 Finish: _____

Static Pressure (In.H2O): 0.20
 Port Length (In.): 6"
 Stack Dia. (In.): 76"
 Probe Length (ft): 41
 Nozzle ID (In.): 1-6 (0.175)
 Console SN: 1848

Pre-Test Leak Check: _____
 Vacuum Pressure: _____
 Post-Test Leak Check: _____
 Vacuum Pressure: _____

K': 0.62

Traverse Point	Time (min)	Stack Gas Temp., Ts (F)	Velocity Head, dP (In.H2O)	Orifice dH (In.H2O)	Gas Meter Volume (cu.ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (In.Hg)
									In	Out	
1	0				168.21						
	2.5	134	1.00	0.54	169.20	295	190	45	58	57	-1
	5	151	1.00	0.52	170.18	296	197	44	59	58	-1
2	7.5	155	1.00	0.52	171.18	298	202	43	59	57	-1
	10	153	1.00	0.52	172.17	297	208	43	59	58	-1
3	12.5	154	0.60	0.31	173.14	295	216	43	60	58	-1
	15	151	0.60	0.31	173.98	292	218	42	60	58	-1
4	17.5	150	0.45	0.24	174.71	296	217	43	60	58	-1
	20	147	0.45	0.24	175.38	299	220	43	60	59	-1
5	22.5	144	0.40	0.21	176.04	298	219	43	60	59	-1
	25	144	0.35	0.19	176.68	295	238	43	60	59	-1
6	27.5	145	0.95	0.51	177.33	296	264	44	60	59	-1
	30	142	1.00	0.53	178.27	293	260	43	60	59	-1
7	32.5	145	1.50	0.80	179.31	298	268	42	60	59	-1
	35	147	1.50	0.80	180.52	295	260	42	60	59	-1
8	37.5	145	1.80	0.96	181.70	297	265	43	60	59	-1
	40	142	1.60	0.96	182.96	297	266	42	60	59	-1
9	42.5	139	1.90	1.07	184.27	297	259	42	60	59	-1
	45	140	1.90	1.02	185.62	297	261	42	59	59	-1
10	47.5	143	1.90	1.02	186.93	297	270	42	59	59	-1
	50	137	1.90	1.02	188.27	295	263	42	59	58	-1
11	52.5	137	1.80	0.97	189.58	298	271	43	59	58	-1
	55	140	1.80	0.97	190.98	297	260	44	60	58	-1
12	57.5	138	1.80	0.97	192.18	291	267	44	60	58	-1
	60	135	1.80	0.97	193.49	294	267	44	60	58	-1

MOISTURE FIELD DATA SHEET

Project No.: 121413456
 Client: Northern Pulp
 Plant: Recovery Boiler
 Location: Pictou, NS
 Test: PM-1
 Date: Mar 10
 Analyst: JJB/TBH/JH



Moisture Data

Impinger No.	Impinger Contents	Final Weight (g)	Tare Weight (g)	Weight of Moisture (g)
1	100 mL H2O	973.5	726.0	247.5
2	100 mL H2O	974.0	729.6	244.4
3	Blank	596.6	570.9	25.7
4	200g Silica Gel	1013.1	990.6	22.5
Total Weight Gain (g)				540.1
Moisture Volume (mL)				540.1

Volume H₂O Collected: 540.1 ml
 X 0.048 = 25.92 ft³ H₂O (Vwc)

DGM Final 269.25 ft³

DGM Initial 2034 ft³

Final - Initial = 58.91 ft³ (Vmc)

Moisture = $\frac{Vwc}{(Vwc + Vmc)}$ 84.83

Moisture = 0.306

Moisture = 0.31

SOURCE TESTING FIELD DATA SHEET

Job No.: 17413456
 Client: Northern Pip
 Plant: Parkway NS
 Location: Parkway 30.00
 Test: PM-1
 Date: Mar 10/15
 Operators: TH/JS
 Gamma: 1.021
 Delta H: 1.728
 Pitot Coeff.: 0.974
 Start: 9:00
 Finish:

Static Pressure (in.H2O): 1.10
 Port Length (in.): 6"
 Stack Dia. (in.): 138"
 Probe Length (ft): 2'
 Nozzle ID (in.): 1-8 (0.234)
 Console S/N: 1646

Pre-Test Leak Check: -18
 Vacuum Pressure:
 Post-Test Leak Check:
 Vacuum Pressure: -13
 K': 1.70

Traverse Point	Time (min)	Stack Gas Temp., Ts (F)	Velocity Head, dP (in.H2O)	Orifice dH (in.H2O)	Gas Meter Volume (cu.ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (in.Hg)
									In	Out	
	0				210.34						
1	2.5	152	0.58	0.82	211.53	262	300	39	50	50	-1
	5	152	0.59	0.83	211.70	270	300	42	47	47	-1
2	7.5	152	0.59	0.83	213.89	270	304	41	47	47	-1
	10	154	0.59	0.83	215.07	270	304	40	48	47	-1
3	12.5	154	0.58	0.81	216.27	270	307	40	48	47	-2
	15	154	0.57	0.80	217.47	270	312	40	49	47	-2
4	17.5	154	0.58	0.82	218.65	270	312	40	49	47	-2
	20	154	0.58	0.82	219.84	270	313	40	49	47	-3
5	22.5	154	0.58	0.82	221.01	270	313	40	49	47	-3
	25	154	0.58	0.82	222.21	271	311	40	49	47	-3
6	27.5	154	0.58	0.82	223.39	270	307	40	50	47	-3
	30	154	0.58	0.82	224.58	271	312	41	50	47	-4
1	32.5	152	0.58	0.82	225.75	270	307	41	50	47	-4
	35	154	0.58	0.82	226.93	270	311	41	50	47	-4
2	37.5	154	0.58	0.82	228.12	270	311	42	50	47	-5
	40	154	0.59	0.83	229.32	270	311	42	51	47	-5
3	42.5	154	0.59	0.83	230.51	271	310	44	51	48	-5
	45	154	0.58	0.82	231.71	270	307	44	52	48	-5
4	47.5	154	0.58	0.82	232.87	270	312	45	52	48	-6
	50	151	0.59	0.84	234.10	270	309	46	52	48	-6
5	52.5	153	0.59	0.84	235.29	270	311	46	53	49	-6
	55	153	0.59	0.84	236.51	271	311	46	53	49	-6
6	57.5	153	0.59	0.84	237.73	270	306	47	54	49	-7
	60	153	0.59	0.84	238.93	270	310	47	54	50	-7

2/2

SOURCE TESTING FIELD DATA SHEET

Job No.: 121413456
 Client: Northern Pump
 Plant: Richmond, MS
 Location: Recovery Boiler
 Test: PM-1
 Date: Nov 10/15
 Operators: JLB/JSB
 Gamma: 1.024
 Delta H: 1.778
 Pitot Coeff.: 0.994
 Start: 9:00
 Finish: 11:00

Static Pressure (in.H2O): 1.10
 Port Length (in.): 6.4
 Stack Dia. (in.): 13.8
 Probe Length (ft): 2.1
 Nozzle ID (in.): 1-8 (0.234)
 Console S/N: 1646

Pre-Test Leak Check:
 Vacuum Pressure: -18
 Post-Test Leak Check:
 Vacuum Pressure: -18

K: 1.70

Traverse Point	Time (min)	Stack Gas Temp., Ts (F)	Velocity Head, dp (in.H2O)	Orifice dH (in.H2O)	Gas Meter Volume (cu.ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (in.Hg)
									In	Out	
1	0				238.93						
	25	153	0.58	0.82	240.52	269	314	44	51	50	-8
	5	154	0.61	0.86	241.79	269	308	44	53	50	-8
2	75	155	0.60	0.85	243.07	270	310	44	53	50	-8
	10	154	0.59	0.84	244.35	270	311	44	54	50	-8
3	125	154	0.60	0.85	245.65	270	308	44	54	51	-9
	15	154	0.59	0.83	246.79	270	312	44	54	51	-9
4	175	154	0.59	0.83	248.02	270	309	44	55	51	-9
	20	154	0.58	0.82	249.26	270	310	44	55	51	-9
5	225	155	0.61	0.86	250.51	270	308	45	55	51	-9
	25	154	0.59	0.84	251.76	270	309	45	55	51	-9
6	275	155	0.59	0.84	253.00	270	311	45	55	51	-10
	30	154	0.58	0.84	254.24	270	308	45	55	51	-10
1	325	154	0.58	0.82	255.47	269	310	45	55	51	-10
	35	153	0.61	0.86	256.74	270	306	45	55	51	-10
2	375	154	0.60	0.85	258.02	270	311	50	55	52	-10
	40	152	0.61	0.87	259.26	270	309	50	55	52	-10
3	425	154	0.59	0.84	260.55	270	310	50	55	52	-10
	45	155	0.58	0.83	261.75	270	311	50	55	52	-10
4	475	155	0.60	0.85	263.00	270	306	54	55	52	-10
	50	155	0.60	0.85	264.25	270	311	54	55	52	-10
5	525	154	0.59	0.84	265.50	270	309	56	55	52	-10
	55	153	0.59	0.84	266.75	270	311	56	55	52	-10
6	575	154	0.60	0.85	268.99	270	310	58	54	52	-10
	60	153	0.60	0.85	269.25	270	310	58	54	52	-12

Sampling Methodology: Environment Canada EPS 1/RM/15



Project No.: 121413456
Client: Northern Pulp
Plant: Pictou NS
Location: Recovery Daler

Fuel Type: Gas

Time Start: 10:00

Time Finish: 10:36

Test No.: PM-1

Date: Mar 10, 2015

Personnel: 7614

[illegible]

MOISTURE FIELD DATA SHEET

Project No.: 121413456
 Client: Northern Pulp
 Plant: Recovery Boiler
 Location: Pictou, NS
 Test: PM-2
 Date: March 10, 2015
 Analyst: JJB/TRH/JAH



Moisture Data

Impinger No.	Impinger Contents	Final Weight (g)	Tare Weight (g)	Weight of Moisture (g)
1	100 mL H2O	987.2	725.7	261.5
2	100 mL H2O	974.2	723.1	251.1
3	Blank	581.2	571.6	9.6
4	200g Silica Gel	1032.6	1013.2	19.4
Total Weight Gain (g)				541.6
Moisture Volume (mL)				541.6

Volume H₂O Collected: 541.6 ml
 X 0.048 = 25.99 ft³ H₂O (Vwc)

DGM Final 331.08 ft³
 DGM Initial 269.42 ft³
 Final - Initial = 61.66 ft³ (Vmc)

Moisture = $\frac{Vwc}{(Vwc + Vmc)}$

Moisture = 0.296

Moisture = 0.30

1/2

SOURCE TESTING FIELD DATA SHEET

Job No.: 121413456
Client: Parthenon Pulp
Plant: Pictou, NS
Location: Recrey Boil
Test: PM-7
Date: APR 12 1915
Operators: 18H/513
Gamma: 1.014
Delta H@: 1.779
Pilot Coeff.: 0.744
Start: 12:15
Finish: _____

Static Pressure (in.H2O): 1.10
Port Length (in): 6"
Stack Dia. (in.): 13.8"
Probe Length (ft): 2.1
Nozzle ID (in.): 1-8 (0.234)
Console S/N: 1646
Pre-Test Leak Check: -18
Vacuum Pressure: _____
Post-Test Leak Check: _____
Vacuum Pressure: _____
K: 1.70

Traverse Point	Time (min)	Stack Gas Temp., Ts (F)	Velocity Head, dP (in.H2O)	Orifice dH (in.H2O)	Gas Meter Volume (cu.ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (in.Hg)
									In	Out	
1	0	151	0.64	0.91	269.42	268	292	48	53	53	-1
	2.5	152	0.64	0.91	270.68	269	293	49	55	53	-1
2	5	154	0.64	0.91	271.96	271	301	45	55	53	-1
	2.5	154	0.66	0.94	273.24	270	300	42	56	53	-1
3	10	154	0.66	0.94	274.51	271	302	41	57	54	-1
	2.5	155	0.65	0.93	275.80	269	302	40	58	54	-1
4	15	155	0.65	0.93	277.10	270	307	39	58	54	-2
	2.5	155	0.65	0.93	278.34	270	311	39	59	55	-2
5	20	155	0.65	0.93	279.63	271	311	38	59	55	-1
	2.5	156	0.65	0.93	280.88	270	316	38	60	55	-3
6	25	157	0.66	0.94	282.15	270	305	38	60	56	-3
	2.5	157	0.66	0.94	283.44	270	311	38	61	56	-3
1	30	155	0.66	0.95	284.70	270	314	38	60	57	-3
	2.5	154	0.66	0.95	285.98	270	310	39	60	57	-4
2	35	155	0.66	0.95	287.25	270	308	39	61	57	-4
	2.5	155	0.66	0.95	288.53	270	314	39	61	57	-4
3	40	156	0.66	0.95	289.82	271	309	39	61	57	-5
	2.5	155	0.67	0.96	291.12	269	314	39	62	58	-5
4	45	155	0.67	0.96	292.40	270	306	39	62	58	-5
	2.5	155	0.67	0.96	293.69	270	309	40	61	58	-5
5	50	155	0.67	0.96	295.00	270	304	40	61	58	-6
	2.5	156	0.65	0.93	296.29	271	309	40	62	58	-6
6	55	157	0.66	0.95	297.60	269	305	41	62	58	-6
	2.5	155	0.66	0.95	298.87	269	309	42	61	58	-7
	60				300.16						

2/2

SOURCE TESTING FIELD DATA SHEET

Job No.: 12413456
Client: Northern Pipe
Plant: Picking MS
Location: Picking Base
Test: PM-2
Date: 10/19/2015
Operators: 134 / J13
Gamma: 1.021
Delta H₀: 1.728
Pilot Coeff.: 0.744
Start:
Finish:
K': 1.70

Static Pressure (in. H₂O): 1.10
Port Length (in.): 6"
Stack Dia. (in.): 2.38"
Probe Length (ft): 2.1
Nozzle ID (in.): 1-B (0.134)
Console S/N: 1646

Pre-Test Leak Check:
Vacuum Pressure:
Post-Test Leak Check:
Vacuum Pressure:
K': 1.70

Traverse Point	Time (min)	Stack Gas Temp., T _s (F)	Velocity Head, dP (in. H ₂ O)	Orifice dH (in. H ₂ O)	Gas Meter Volume (cu. ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (in. Hg)
									In	Out	
	0				300.16						
1	2.5	156	0.66	0.95	301.47	271	312	41	61	58	-7
2	5	155	0.66	0.95	302.75	269	309	42	61	59	-7
3	7.5	153	0.65	0.94	304.04	270	310	43	61	58	-7
4	10	155	0.66	0.95	305.32	270	311	44	60	59	-8
5	12.5	155	0.66	0.95	306.62	271	313	44	59	58	-8
6	15	155	0.66	0.95	307.89	269	302	45	59	58	-8
7	17.5	154	0.66	0.95	309.18	270	312	45	58	58	-8
8	20	154	0.66	0.95	310.48	270	311	45	58	57	-9
9	22.5	151	0.66	0.95	311.76	270	306	45	58	57	-9
10	25	152	0.66	0.95	313.04	270	309	46	57	57	-9
11	27.5	153	0.66	0.95	314.33	270	311	47	56	56	-10
12	30	153	0.67	0.96	315.63	270	310	47	56	56	-10
13	32.5	152	0.66	0.95	316.92	271	303	47	56	56	-11
14	35	152	0.66	0.95	318.22	269	308	48	55	55	-11
15	37.5	152	0.66	0.95	319.50	270	306	48	55	55	-11
16	40	151	0.66	0.94	320.77	270	307	49	54	54	-11
17	42.5	153	0.66	0.94	322.05	270	310	50	54	54	-12
18	45	152	0.65	0.93	323.34	271	312	50	54	54	-12
19	47.5	153	0.66	0.94	324.61	269	303	51	53	53	-12
20	50	153	0.66	0.94	325.90	270	311	52	54	53	-13
21	52.5	153	0.66	0.94	327.22	270	307	52	54	53	-13
22	55	153	0.66	0.94	328.51	270	312	53	54	53	-13
23	57.5	154	0.66	0.94	329.80	270	310	53	54	53	-14
24	60	151	0.66	0.94	331.08	270	305	54	54	53	-14

Sampling Methodology: Environment Canada EPS 1/RM/15



Project No.: 121413456
Client: Northern Pulp
Plant: Pictou, NS
Location: Recovery Boiler

Fuel Type: *biomass*

Time Start: 1:00
Time Finish: 1:30

Test No.: Gas # 2
Date: Mar 10/15

Personnel: *TBH*

[illegible]

MOISTURE FIELD DATA SHEET

Project No.: 121413456

Client: Northern Pulp

Plant: Recovery Boiler

Location: Pictou NS

Test: PM-3

Date: March 11, 2015

Analyst: JTB/TBH/JAH



Moisture Data

Impinger No.	Impinger Contents	Final Weight (g)	Tare Weight (g)	Weight of Moisture (g)
1	100 mL H ₂ O	995.8	730.8	265.1
2	100 mL H ₂ O	957.9	718.3	239.6
3	Blank	582.6	570.7	11.9
4	200g Silica Gel	973.8	949.7	24.1
Total Weight Gain (g)				540.6
Moisture Volume (mL)				540.6

Volume H₂O Collected: 540.6 ml
 X 0.048 = 25.95 ft³ H₂O (Vwc)

DGM Final 392.317 ft³

DGM Initial 334.37 ft³

Final - Initial = 57.94 ft³ (Vmc)

Moisture = $\frac{Vwc}{(Vwc + Vmc)}$

Moisture = 0.309

Moisture = 0.31

1/2

SOURCE TESTING FIELD DATA SHEET

Job No.: 121413456
 Client: Northern Pulp
 Plant: Recovery Boiler
 Location: Pictou NS
 Test: PM-5
 Date: Apr 11, 2015
 Operators: JJB/JH
 Gamma: 1.021
 Delta H₂O: 1.728
 Pilot Coeff.: 0.794
 Start: 9:20
 Finish:

Static Pressure (in.H₂O): 1.10
 Port Length (in): 6
 Stack Dia. (in.): 13.8
 Probe Length (ft): 21
 Nozzle ID (in.): 1-8 (0.234)
 Console S/N: 1646

Pre-Test Leak Check: ☒
 Vacuum Pressure: -13
 Post-Test Leak Check: ☒
 Vacuum Pressure: -13
 K': 1.70

Traverse Point	Time (min)	Stack Gas Temp., T _s (F)	Velocity Head, dP (in.H ₂ O)	Orifice dH (in.H ₂ O)	Gas Meter Volume (cu.ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (in.Hg)
									In	Out	
1	0	150	0.56	0.79	334.37	2108	310	48	43	43	-1
	2.5	149	0.57	0.80	336.81	2106	311	48	44	43	-1
2	7.5	150	0.59	0.83	337.99	270	304	48	44	43	-1
	10	150	0.59	0.83	339.25	270	309	46	44	43	-1
3	12.5	151	0.58	0.81	340.40	270	313	46	44	43	-1
	15	152	0.58	0.81	341.62	270	309	45	45	43	-2
4	17.5	151	0.58	0.81	342.84	270	310	45	46	44	-2
	20	150	0.57	0.80	344.01	270	311	45	46	44	-2
5	22.5	150	0.58	0.82	345.24	270	303	45	47	44	-3
	25	151	0.58	0.82	346.47	270	310	45	47	44	-3
6	27.5	151	0.57	0.82	347.65	270	313	45	47	44	-3
	30	151	0.57	0.80	348.86	270	308	45	47	44	-3
1	32.5	151	0.58	0.82	350.07	2106	307	45	47	44	-3
	35	150	0.59	0.83	351.21	270	309	48	46	45	-3
2	37.5	150	0.56	0.79	352.40	270	310	48	47	45	-1
	40	151	0.58	0.82	353.65	270	312	49	47	45	-4
3	42.5	151	0.58	0.82	354.93	270	310	49	47	45	-4
	45	151	0.58	0.82	356.07	270	309	49	47	45	-4
4	47.5	148	0.57	0.84	357.27	270	308	51	48	45	-4
	50	151	0.57	0.80	358.49	270	310	51	48	45	-4
5	52.5	149	0.58	0.82	359.69	270	307	52	48	46	-4
	55	151	0.57	0.80	360.86	270	313	52	48	46	-4
6	57.5	149	0.58	0.82	362.04	270	312	52	50	46	-5
	60	149	0.57	0.81	363.17	270	308	52	50	46	-5

2/12

SOURCE TESTING FIELD DATA SHEET

Job No.: 121413456
 Client: Northern Pulp
 Plant: Pevensey
 Location: Fulton, NJ
 Test: PM-3
 Date: MSC 11/2015
 Operators: SSB/JH
 Gamma: 1021
 Delta H₀: 1.728
 Pilot Coeff.: 0.797
 Start: 4:20
 Finish: _____

Static Pressure (in.H₂O): _____
 Port Length (in.): _____
 Stack Dia. (in.): _____
 Probe Length (ft): _____
 Nozzle ID (in.): _____
 Console S/N: _____

Pre-Test Leak Check: _____
 Vacuum Pressure: _____
 Post-Test Leak Check: _____
 Vacuum Pressure: _____

K': 1.70

Traverse Point	Time (min)	Stack Gas Temp., T _s (F)	Velocity Head, dP (in.H ₂ O)	Orifice dH (in.H ₂ O)	Gas Meter Volume (cu.ft)	Probe Temp. (F)	Oven Temp. (F)	Impinger Outlet Temp. (F)	Gas Meter Temp. (F)		Pump Vacuum (in.Hg)
									In	Out	
1	0				363.17						
	2.5	150	0.58	0.82	364.38	270	311	55	50	46	-5
	5	150	0.57	0.81	365.57	270	309	55	50	46	-5
2	7.5	150	0.58	0.82	366.76	270	311	57	51	47	-6
	10	150	0.58	0.82	367.98	270	312	59	51	47	-6
3	12.5	150	0.58	0.82	369.16	270	307	60	51	47	-6
	15	148	0.58	0.83	370.26	270	311	60	51	47	-6
4	17.5	150	0.57	0.81	371.50	270	309	61	51	47	-7
	20	150	0.57	0.84	372.77	270	309	67	51	47	-7
5	22.5	150	0.59	0.84	374.00	270	315	62	51	47	-8
	25	150	0.58	0.82	375.21	270	309	62	51	47	-8
6	27.5	151	0.58	0.82	376.39	270	308	68	51	48	-8
	30	150	0.57	0.81	377.62	270	307	70	51	48	-9
1	32.5	149	0.58	0.82	378.82	269	308	70	51	48	-9
	35	150	0.58	0.82	380.02	270	312	72	52	48	-9
2	37.5	150	0.59	0.84	381.23	271	306	67	52	48	-9
	40	149	0.59	0.84	382.44	270	312	63	53	49	-10
3	42.5	149	0.59	0.84	383.67	270	308	60	53	49	-10
	45	148	0.60	0.86	384.90	270	305	58	53	49	-10
4	47.5	148	0.60	0.86	386.14	270	307	55	53	49	-11
	50	149	0.60	0.86	387.38	270	310	54	54	50	-11
5	52.5	148	0.60	0.86	388.63	270	308	53	54	50	-11
	55	149	0.59	0.84	389.86	270	311	53	54	50	-12
6	57.5	150	0.60	0.86	391.08	270	310	53	54	51	-13
	60	149	0.60	0.86	392.31	270	309	54	54	52	-13

Sampling Methodology: Environment Canada EPS 1/RM/15



Project No.: 121413456
Client: Northern Pulp
Plant: Pictou, NS
Location: Recovery Boiler

Fuel Type: bio diesel

Time Start: 10:20
Time Finish: 10:50

Test No.: Gas # 3
Date: Mar. 11, 2015

Personnel: TB/H

[illegible]

Appendix D

Calculations

Raw Data for: Test #1

Client: Northern Pup
Job Number: 121413456

Plant: Power Boiler
Location: Pictou, NS
Test: PM-2
Date: 10-Mar-11

Personnel: TBH / JBS/AH

Test Start: 8:47 AM

Test Finish: 10:47 AM

Parameters

Barometric Pressure, Pbar (in. Hg)
Stack Static Pressure, Pstatic (in. H2O)
Ambient Temp, (°F)
H2O Volume Collected, Vw (mL)
Total # Sampling Points,
Sampling Time per Point, (min)
Readings Taken Every ___ mins
Regulatory Agency

Impinger No.	Impinger	Final Weight (g)	Tare Weight (g)	Weight of Moisture (g)
1	Condensate	994.3	731.4	262.9
2	100 mL H2O	881.2	828.0	53.2
3	100 mL H2O	859.5	859.5	0.0
4	Blank	998.4	994.0	4.4
	200g Silica Gel			290.5
				290.5

76	31.50
8	0.172
0.816	1.013
6	

Stack Diameter, (in.)
Stack Area, (sq. ft.)
Probe Length, (ft.)
Nozzle Diameter, (in.)
Pilot Coefficient, (Cp)
Gamma, meter constant
Port Height, (in.)

Particulate Collected from Filter (mg): 198.6
Particulate Collected from Probe Wash (mg): 20.9
Particulate Collected from Impinger Wash (mg): 4.8
Total Particulate Collected (mg): 219.5

O2, (%)
CO2, (%)
N2, (%)
CO (ppm)
NOx (ppm)
SO2 (ppm)

29.55
0.20
28
290.5
24
5
2.5
NSENW

Time (min)	Stack Gas Temp, Tg (°F)	S-type Pilot delta P (in. H2O)	Orifice delta H (in. H2O)	Gas Meter Volume (cu. ft.)	Gas Meter Inlet (°F)	Gas Meter Outlet (°F)
2.5	141	1.40	0.89	52.180	40	40
5	144	1.50	0.83	53.520	40	40
7.5	145	1.00	0.83	54.730	39	40
10	145	1.80	1.00	55.980	40	40
12.5	148	1.80	1.00	57.280	40	40
15	148	1.70	0.94	58.540	40	40
17.5	147	1.60	0.88	59.780	40	40
20	147	1.50	0.83	60.980	41	40
22.5	146	1.50	0.84	62.170	41	40
25	148	1.00	0.55	63.260	42	40
27.5	149	1.00	0.55	64.210	42	40
30	151	0.60	0.33	65.140	42	40
32.5	151	0.50	0.27	66.650	42	40
35	151	0.50	0.27	67.330	42	40
37.5	150	0.45	0.25	68.020	42	41
40	149	0.45	0.25	68.680	42	41
42.5	151	0.45	0.25	69.350	42	41
45	152	0.45	0.25	70.010	42	41
47.5	152	0.45	0.25	70.670	42	41
50	151	0.45	0.25	71.320	43	41
52.5	150	0.50	0.28	72.010	43	42
55	151	0.50	0.28	72.730	43	42
57.5	149	0.50	0.28	73.450	43	42
60	149	0.50	0.28	74.180	44	42
62.5	149	1.50	0.77	74.180	43	43
65	149	1.45	0.74	75.590	43	43
67.5	152	1.30	0.66	77.210	43	43
70	153	1.20	0.61	78.250	45	43
72.5	150	0.90	0.46	79.260	45	43
75	153	0.90	0.46	80.210	45	43
77.5	152	0.65	0.33	81.080	46	43
80	149	0.65	0.33	81.930	46	43
82.5	150	0.50	0.26	82.680	46	43
85	153	0.50	0.25	83.310	46	43
87.5	154	0.50	0.25	83.940	46	43
90	151	0.95	0.46	84.740	46	44
92.5	150	1.30	0.67	85.630	47	44
95	147	1.40	0.72	86.590	47	44
97.5	150	1.80	0.93	87.690	48	45
100	147	1.80	0.93	88.840	48	45
102.5	148	1.80	0.93	90.080	49	46
105	150	1.80	0.93	91.330	49	46
107.5	145	1.80	0.93	92.560	49	46
110	145	1.80	0.93	93.800	49	46
112.5	142	1.80	0.94	95.110	49	46
115	142	1.80	0.94	96.310	49	46
117.5	142	1.80	0.94	97.550	49	46
120	141	1.80	0.94	98.800	49	46
				100.050	49	46

Traverse 2

Traverse Point	Time (min)	Stack Gas Temp, Tg (°F)	S-type Pilot delta P (in. H2O)	Orifice delta H (in. H2O)	Gas Meter Volume (cu. ft.)	Gas Meter Inlet (°F)	Gas Meter Outlet (°F)
1	62.5	149	1.50	0.77	74.180	43	43
2	65	149	1.45	0.74	75.590	43	43
3	67.5	152	1.30	0.66	77.210	43	43
4	70	153	1.20	0.61	78.250	45	43
5	72.5	150	0.90	0.46	79.260	45	43
6	75	153	0.90	0.46	80.210	45	43
7	77.5	152	0.65	0.33	81.080	46	43
8	80	149	0.65	0.33	81.930	46	43
9	82.5	150	0.50	0.26	82.680	46	43
10	85	153	0.50	0.25	83.310	46	43
11	87.5	154	0.50	0.25	83.940	46	43
12	90	151	0.95	0.46	84.740	46	44
	92.5	150	1.30	0.67	85.630	47	44
	95	147	1.40	0.72	86.590	47	44
	97.5	150	1.80	0.93	87.690	48	45
	100	147	1.80	0.93	88.840	48	45
	102.5	148	1.80	0.93	90.080	49	46
	105	150	1.80	0.93	91.330	49	46
	107.5	145	1.80	0.93	92.560	49	46
	110	145	1.80	0.93	93.800	49	46
	112.5	142	1.80	0.94	95.110	49	46
	115	142	1.80	0.94	96.310	49	46
	117.5	142	1.80	0.94	97.550	49	46
	120	141	1.80	0.94	98.800	49	46

Calculations for: 0
Test #1

Client: Northern Pulp
Job Number: 121413455

Plant: Power Boiler
Location: Ptdou, NS
Test: PM-2
Date: 10-Mar-15
Personnel: TBH / JEB/JAH

Calculated Parameters

Stack Gas Pressure, Ps (in.Hg)
Stack Gas Molecular Weight, Dry Basis, M_d (lb/lb-mole)
Volume of Water Vapour Collected, V_{wc} (cu.ft)
Stack Gas Moisture Content (% as decimal)
Stack Gas Molecular Weight, Wet Basis, M_s (lb/lb-mole)

29.59
30.00
13.944
0.208
27.50

Isokineticity Checks

Check range
Check average

Outside of Criteria
Within Criteria

Traverse Point	Time (min)	Stack Gas Temp, T _s (R)	S-type Pitot, delta P (in. H ₂ O)	Orifice delta H (in. H ₂ O)	Stack Gas Velocity, U _s (ft/s)	Meter Press., P _m (in. Hg)	Avg. Temp, T _m (R)	Gas Meter		Vol. @ Ref., V _{mc} (cu. ft.)	Isokinetics I (%)
								Volume, V _m (cu. ft.)			
Traverse 1	1	601	1.50	0.89	75.72	29.82	500	1240	1388	108.33	
	2	604	1.50	0.83	73.50	29.81	500	1210	1354	109.43	
	3	605	1.80	1.00	80.58	29.82	500	1250	1401	103.43	
	4	608	1.70	0.94	78.51	29.82	500	1280	1458	107.46	
	5	607	1.50	0.88	76.16	29.81	500	1240	1388	108.86	
	6	602	1.80	0.83	73.68	29.81	501	1200	1342	108.69	
	7	608	1.50	0.84	73.38	29.81	501	1190	1331	107.34	
	8	608	1.00	0.55	60.11	29.59	501	1090	1218	120.73	
	9	608	1.00	0.55	60.21	29.59	501	0.950	1.060	105.29	
	10	609	1.00	0.55	60.26	29.59	501	0.930	1.038	103.16	
	11	611	0.60	0.33	46.76	29.57	501	0.770	0.859	110.39	
	12	611	0.50	0.27	42.68	29.57	501	0.740	0.825	118.20	
Traverse 2	1	609	1.50	0.77	73.81	29.81	503	1770	1969	159.78	
	2	609	1.45	0.74	72.56	29.80	503	1260	1402	115.66	
	3	612	1.30	0.66	68.68	29.80	504	1040	1154	100.85	
	4	610	0.90	0.48	66.23	29.59	504	1010	1121	102.01	
	5	613	0.80	0.46	57.22	29.58	504	0.950	1.054	110.48	
	6	612	0.90	0.48	57.36	29.58	504	0.870	0.985	101.43	
	7	609	0.85	0.33	48.70	29.57	505	0.850	0.942	118.36	
	8	610	0.85	0.33	48.58	29.57	505	0.750	0.831	102.42	
	9	613	0.50	0.26	42.85	29.57	505	0.630	0.698	98.15	
	10	614	0.50	0.25	42.75	29.57	505	0.630	0.698	98.39	
	11	611	0.90	0.46	57.40	29.58	505	0.830	0.896	103.16	
	12	611	0.95	0.49	58.83	29.59	505	0.890	0.985	100.84	
Traverse 3	1	607	1.30	0.67	68.77	29.59	506	0.960	1.062	92.87	
	2	610	1.40	0.72	71.19	29.60	508	1.100	1.217	102.08	
	3	607	1.80	0.83	80.92	29.62	507	1.150	1.271	94.21	
	4	608	1.80	0.83	80.78	29.62	507	1.250	1.381	102.18	
	5	610	1.80	0.83	80.78	29.62	507	1.240	1.370	101.42	
	6	610	1.80	0.83	80.92	29.62	508	1.230	1.357	100.57	
	7	610	1.80	0.83	80.92	29.62	508	1.240	1.368	101.39	
	8	605	1.80	0.93	80.58	29.62	508	1.250	1.379	101.78	
	9	602	1.80	0.93	80.38	29.62	508	1.260	1.390	102.35	
	10	602	1.80	0.94	80.36	29.62	508	1.240	1.368	100.72	
	11	602	1.80	0.94	80.36	29.62	508	1.250	1.379	101.54	
	12	601	1.80	0.94	80.32	29.62	508	1.250	1.379	101.45	
Total	120	Average 609	Average 1.13	Average 0.60	Average 62.07	Average 29.59	Average 503	Total 47.770	Total 53.081	Average 106.92	

Combustion Gas Data for: Northern Pulp

Client: Northern Pulp
Job Number: 121413456

Plant: Power Boiler
Location: Pictou, NS
Test: PM-2
Date: 10-Mar-15
Personnel: TBH / JJB/JAH

Test Start:
Test Finish:

Time (min)	O2 (%)	CO2 (%)	CO (ppm)	SO2 (ppm)	NOx (ppm)
0	10.6	10.0	2552	0	15
5	10.6	10.0	1498	0	16
10	11.0	9.5	1360	0	17
15	11.3	9.2	1445	0	17
20	11.6	8.9	1901	0	15
25	10.4	10.3	1870	0	16
30	9.9	10.6	1511	0	17
Average:	10.8	9.8	1734	0	16

Raw Data for: Test #2

Client: Northern Pup
Job Number: 121413458
Plant: Power Boiler
Location: Picou, NS
Test: PM10
Date: 11-Mar-15
Personnel: TBM / JJB/AH
Test Start: 12:00 PM
Test Finish: 2:00 PM

Parameters

Barometric Pressure, Pbar (in. Hg)
Stack Static Pressure, Pstatic (in. H2O)
Ambient Temp. (°F)
H2O Volume Collected, Vw (mL)
Total # Sampling Points,
Sampling Time per Point, (min)
Readings Taken Every ___ mins
Regulatory Agency

29.38
0.20
33
259.9
24
3
1.5
NSENIV

O2 (%)
CO2 (%)
N2 (%)
CO (ppm)
NOx (ppm)
SO2 (ppm)

11.4
9.3
79.4
2079.0
21.0
0.0

Particulate Collected from Filter (mg):
Particulate Collected from Probe Wash (mg):
Total Particulate Collected (mg):

211.4
27.8
239.2

Impinger No.
Impinger Contents
Final Weight (g)
Tare Weight (g)
Weight of Moisture (g)

1
100 mL H2O
945.6
715.5
230.1

2
100 mL H2O
843.0
625.6
21.4

3
Blank
653.0
650.7
2.3

4
200g Silica Gel
1004.4
994.3
10.1

Total Weight Gan (g)
Moisture Volume (mL)

256.9
259.9

76
31.50
8
0.172
0.816
1.053
6

Stack Diameter, (in.)
Stack Area, (sq. ft.)
Probe Length, (in.)
Nozzle Diameter, (in.)
Pilot Coefficient, (Cp)
Gamma, meter constant
Port Length (in.)

Gas Meter Temp
Inlet (°F)
Outlet (°F)

Gas Meter
Volume (cu. ft.)

Office
delta P
(in. H2O)

S-type Pilot
delta P
(in. H2O)

Stack Gas
Temp, Tg
(°F)

Time
(min)

Traverse
Point

Traverse 1	1	2.5	151	0.93	0.48	100.510	48	48
	5	7.5	152	0.99	0.51	101.450	50	49
	10	12.5	150	0.80	0.50	102.420	50	49
	15	17.5	148	0.50	0.41	103.350	50	49
	20	22.5	149	0.32	0.25	104.200	52	50
	25	27.5	148	0.47	0.27	104.910	53	50
	30	32.5	151	0.70	0.24	105.590	52	51
	35	37.5	151	1.05	0.21	106.250	52	52
	40	42.5	148	0.40	0.23	106.910	52	52
	45	47.5	144	0.70	0.21	107.170	52	52
	50	52.5	147	1.70	0.37	108.170	51	52
	55	57.5	147	1.70	0.54	109.770	52	52
	60		144	1.70	0.70	110.760	52	52
					0.71	112.850	52	52
					0.89	115.980	53	51
					0.84	118.140	53	52
					0.90	120.360	53	52
					0.89	122.060	53	52
					0.89	123.310	53	52
					0.89	124.590	53	52
					0.89	125.880	54	52

Traverse 2	1	62.5	147	1.50	0.79	125.880	53	53
	65	67.5	148	1.50	0.78	126.020	53	53
	70	72.5	149	1.40	0.74	127.320	53	53
	75	77.5	152	1.30	0.73	128.440	54	53
	80	82.5	149	1.30	0.68	129.560	54	53
	85	87.5	149	1.20	0.68	130.670	54	53
	90	92.5	149	1.20	0.63	131.770	54	53
	95	97.5	149	1.20	0.62	132.830	54	53
	100	102.5	149	1.20	0.63	133.890	54	53
	105	107.5	149	1.20	0.63	134.910	53	53
	110	112.5	147	0.90	0.47	135.850	53	53
	115	117.5	147	0.90	0.47	136.800	54	53
	120		149	0.65	0.34	137.680	54	53
			151	0.45	0.24	138.530	53	53
			152	0.45	0.24	139.280	53	53
			151	0.30	0.16	140.560	53	53
			151	0.20	0.10	141.160	53	53
			150	0.20	0.10	141.700	53	53
			150	0.20	0.10	142.300	53	53
			150	0.20	0.10	142.700	53	53
			150	0.20	0.10	143.190	53	53
			148	0.20	0.10	143.680	53	53
					0.10	144.180	53	53

Calculations for: 0
Test #2

Client: Northern Pulp
Job Number: 121413458

Plant: Power Boiler
Location: Pictou NS
Test: PAL3
Date: 11-Mar-15
Personnel: TBH / JJB/JAH

Calculated Parameters

Stack Gas Pressure, P_s (in-Hg)
Stack Gas Molecular Weight, Dry Basis, M_d (lb/lb-mole)
Volume of Water Vapour Collected, V_{wc} (cu.ft)
Stack Gas Moisture Content (% as decimal)
Stack Gas Molecular Weight, Wet Basis, M_w (lb/lb-mole)

26.39
12.475
0.208
27.45

Isokineticity Checks

Check range
Check average

Outside of Criteria
Within Criteria

Transverse Point	Time (min)	Stack Gas Temp, T _s (F)	S-type Pitot, delta P (in. H ₂ O)	Orifice delta H (in. H ₂ O)	Stack Gas Velocity, U _s (ft/s)	Meter Press., P _m (in. Hg)	Avg. Temp, T _m (F)	Gas Meter Volume, V _m (cu. ft.)	Vol. @ Ref., V _{ref} (cu. ft.)	Isokinetics I (%)
Transverse 1	2.5	611	0.83	0.48	58.43	29.42	508	0.940	1.029	108.43
	5	612	0.99	0.51	60.34	29.42	510	0.970	1.058	108.23
	7.5	612	0.88	0.50	60.03	29.42	510	0.930	1.015	102.36
	10	610	0.80	0.41	54.15	29.41	510	0.850	0.927	103.35
	12.5	610	0.50	0.25	42.81	29.40	511	0.710	0.772	108.84
	15	608	0.52	0.27	43.58	29.40	512	0.680	0.739	101.85
	17.5	609	0.47	0.24	41.47	29.40	512	0.660	0.717	104.18
	20	610	0.47	0.24	41.51	29.40	512	0.660	0.717	104.25
	22.5	610	0.44	0.23	40.16	29.40	512	0.640	0.694	104.37
	25	608	0.40	0.21	38.23	29.40	512	0.620	0.673	105.87
	27.5	611	0.70	0.37	50.70	29.41	512	0.800	0.868	103.56
	30	611	0.70	0.37	50.70	29.41	512	0.800	0.868	103.56
Transverse 2	32.5	611	1.05	0.54	62.09	29.42	512	0.980	1.075	104.88
	35	612	1.10	0.57	63.60	29.42	512	1.040	1.129	107.54
	37.5	612	1.40	0.73	71.75	29.43	512	1.330	1.441	108.27
	40	608	1.40	0.73	71.52	29.43	513	1.228	1.228	103.27
	42.5	609	1.70	0.89	78.87	29.45	513	1.160	1.260	103.88
	45	604	1.50	0.84	74.20	29.44	513	1.220	1.325	103.88
	47.5	602	1.80	0.90	78.42	29.45	513	1.314	1.314	102.27
	50	602	1.70	0.80	78.42	29.45	513	1.240	1.348	103.42
	52.5	607	1.70	0.88	78.74	29.45	513	1.250	1.356	103.52
	55	607	1.70	0.89	78.74	29.45	513	1.250	1.357	103.52
	57.5	607	1.70	0.89	78.74	29.45	513	1.240	1.348	102.70
	60	604	1.70	0.89	78.55	29.45	513	1.240	1.348	102.70
Transverse 2	62.5	607	1.50	0.79	73.97	29.44	513	1.140	1.236	100.39
	65	608	1.50	0.78	74.03	29.44	513	1.150	1.247	101.35
	67.5	608	1.40	0.74	71.40	29.43	513	1.150	1.247	104.72
	70	609	1.40	0.73	71.58	29.43	514	1.120	1.213	102.14
	72.5	612	1.30	0.68	69.14	29.43	514	1.120	1.213	108.25
	75	609	1.30	0.68	68.97	29.43	514	1.110	1.202	105.04
	77.5	609	1.30	0.68	68.97	29.43	514	1.100	1.191	104.09
	80	608	1.20	0.63	66.27	29.43	514	1.080	1.170	100.38
	82.5	612	1.20	0.62	66.43	29.43	514	1.040	1.128	102.67
	85	609	1.20	0.63	66.27	29.43	513	1.020	1.106	100.55
	87.5	609	0.90	0.47	57.39	29.41	513	0.940	1.019	108.95
	90	607	0.90	0.47	57.29	29.41	514	0.950	1.028	107.81
Transverse 2	92.5	609	0.85	0.34	48.77	29.41	514	0.860	0.952	117.87
	95	611	0.85	0.34	48.85	29.41	513	0.850	0.921	113.95
	97.5	611	0.45	0.24	40.65	29.40	513	0.750	0.812	120.81
	100	612	0.45	0.23	40.68	29.40	513	0.650	0.704	104.78
	102.5	612	0.30	0.16	33.22	29.39	513	0.630	0.682	124.37
	105	611	0.30	0.16	33.19	29.39	513	0.600	0.650	118.35
	107.5	611	0.20	0.10	27.10	29.39	513	0.540	0.585	130.43
	110	610	0.20	0.10	27.08	29.39	513	0.500	0.541	120.67
	112.5	610	0.20	0.10	27.08	29.39	513	0.541	0.541	120.67
	115	610	0.20	0.10	27.08	29.39	513	0.480	0.530	118.26
	117.5	610	0.20	0.10	27.08	29.39	513	0.480	0.530	118.26
	120	608	0.20	0.10	27.03	29.39	513	0.500	0.541	120.47
Total	120	Average 608	Average 0.95	Average 0.49	Average 56.19	Average 29.42	Average 512	Total 43.670	Total 47.369	Average 107.81

Combustion Gas Data for: Northern Pulp

Client: Northern Pulp
Job Number: 121413456

Plant: Power Boiler
Location: Pictou, NS
Test: PM-3
Date: 11-Mar-15
Personnel: TBH / JJB/JAH

Test Start: 12:15 PM
Test Finish: 12:45 PM

Time (min)	O2 (%)	CO2 (%)	CO (ppm)	SO2 (ppm)	NOx (ppm)
0	12.1	8.6	3163	0	16
5	11.5	9.1	2865	0	21
10	11.1	9.5	2296	0	22
15	11.6	9.1	1540	0	24
20	12.1	8.5	1760	0	23
25	10.9	9.6	1129	0	16
30	10.2	10.4	1800	0	25
Average:	11.4	9.3	2079	0	21

Raw Data for: Test #3

Client: Northern Pulp
Job Number: 121413455
Plant: Power Boiler
Location: Piddou, NS
Test: PM-1
Date: 11-Nov-15
Personnel: TBJ/HJ/AJH
Test Start: 2:32 PM
Test Finish: 4:52 PM

Parameters
Barometric Pressure, Pbar (in. Hg)
Stack Static Pressure, Pstatic (in. H2O)
Ambient Temp. (°F)
H2O Volume Collected, Vw (mL)
Total # Sampling Points,
Sampling Time per Point, (min)
Readings Taken Every ___ mins
Regulatory Agency

Impinger No.	Impinger Contents	Final Weight (g)	Tare Weight (g)	Weight of Moisture (g)
1	100 mL H2O	864.7	718.5	249.2
2	100 mL H2O	757.9	735.2	22.7
3	Blank	573.0	570.6	2.4
4	200g Silica Gel	941.7	931.3	10.4
Total Weight Gain (g)				284.7
Moisture Volume (mL)				284.7

Stack Diameter, (in.)
76
Stack Area, (sq. ft.)
31.50
Probe Length, (ft.)
8
Nozzle Diameter, (in.)
0.172
Pilot Coefficient, (Cp)
0.816
Gamma, meter constant
1.053
Port length (in.)
6

Particulate Collected from Filter (mg): 184.3
Particulate Collected from Probe Wash (mg): 45.0
Particulate Collected from Impinger Wash (mg): 4.2
Total Particulate Collected (mg): 229.3

O2 (%)
9.7
CO2 (%)
11.0
N2 (%)
79.3
CO (ppm)
1896.1
NOx (ppm)
26.3
SO2 (ppm)
0.0

29.35
0.20
36
284.70
24
5
2.5
NSEW

Traverse	Traverse Point	Time (min)	Stack Gas Temp, Ts (°F)	S-type Pilot delta P (in. H2O)	Orifice delta H (in. H2O)	Gas Meter Volume (cc. ft.)	Gas Meter Inlet (°F)	Gas Meter Outlet (°F)
Traverse 1	1	2.5	142	1.50	0.79	144.830	50	50
	5	5	142	1.50	0.79	146.850	51	51
	7.5	7.5	145	1.60	0.84	147.230	51	51
	10	10	145	1.60	0.84	148.450	52	51
	12.5	12.5	145	1.60	0.84	149.680	53	51
	15	15	150	1.50	0.78	150.870	54	51
	17.5	17.5	147	1.50	0.79	152.040	55	52
	20	20	146	1.50	0.79	152.220	56	52
	22.5	22.5	151	1.40	0.73	154.390	57	53
	25	25	149	1.40	0.73	155.530	58	53
	27.5	27.5	149	0.90	0.47	156.720	59	54
	30	30	151	0.90	0.47	157.670	59	55
Traverse 2	1	62.5	134	1.00	0.54	168.200	58	57
	2	65	131	1.00	0.52	169.300	59	58
	3	67.5	133	1.00	0.52	170.160	59	57
	4	70	135	1.00	0.52	171.180	59	57
	5	72.5	135	1.00	0.52	172.170	60	58
	6	75	131	0.60	0.31	173.180	60	58
	7	77.5	150	0.55	0.29	173.960	60	58
	8	80	147	0.45	0.24	174.710	60	59
	9	82.5	144	0.40	0.21	175.380	60	59
	10	85	144	0.35	0.19	176.560	60	59
	11	87.5	145	0.95	0.51	177.390	60	59
	12	90	142	1.00	0.53	177.970	60	59
Traverse 3	1	92.5	145	1.50	0.80	179.310	60	59
	2	95	147	1.50	0.80	180.320	60	59
	3	97.5	145	1.80	0.96	181.700	60	59
	4	100	142	1.80	0.96	182.960	60	59
	5	102.5	139	1.90	1.02	184.270	60	59
	6	105	140	1.90	1.02	185.620	60	59
	7	107.5	143	1.90	1.02	186.930	59	59
	8	110	137	1.90	1.02	188.320	59	58
	9	112.5	137	1.80	0.97	189.580	59	58
	10	115	140	1.80	0.97	190.880	60	58
	11	117.5	138	1.80	0.97	192.160	60	58
	12	120	135	1.80	0.97	193.490	60	58

Calculations for: 0
Test #3

Client: Northern Pulp
Job Number: 121413456

Plant: Power Boiler
Location: Picou, NS
Test: PMA-4
Date: 11-Mar-15
Personnel: TBHJLB/UAH

Calculated Parameters

Stack Gas Pressure, P_s (in.Hg)
Stack Gas Molecular Weight, Dry Basis, M_d (lb/lb-mole)
Volume of Water Vapour Collected, V_{wc} (cu.ft)
Stack Gas Moisture Content (% as decimal)
Stack Gas Molecular Weight, Wet Basis, M_w (lb/lb-mole)

29.36
30.15
13.666
0.207
27.63

Isokineticity Checks

Check range
Check average

Within Criteria
Within Criteria

Traverse	Point	Time (min)	Stack Gas Temp, T _s (R)	S-type Pitot, delta P (in. H ₂ O)	Orifice delta H (in. H ₂ O)	Stack Gas Velocity, U _s (ft/s)	Meter Press., P _m (in. Hg)	Avg. Temp., T _m (R)	Gas Meter Volume, V _m (cu. ft.)	Vol. @ Ref., V _{mrc} (cu. ft.)	Isokinetics I (%)
Traverse 1	1	2.5	602	1.50	0.79	71.46	29.41	510	1.220	1.330	107.76
	2	5	605	1.50	0.79	71.46	29.41	511	1.180	1.283	104.03
	3	10	605	1.60	0.84	76.05	29.41	512	1.220	1.328	104.31
	4	12.5	607	1.50	0.78	71.94	29.41	513	1.230	1.335	105.06
	5	15	607	1.50	0.79	71.76	29.41	514	1.190	1.290	105.29
	6	17.5	608	1.50	0.79	71.62	29.41	514	1.160	1.277	103.95
	7	20	611	1.40	0.73	71.49	29.40	515	1.170	1.285	103.05
	8	22.5	612	1.40	0.73	71.55	29.40	516	1.140	1.262	106.71
	9	25	609	1.40	0.73	71.38	29.40	517	1.229	1.329	103.96
	10	27.5	609	0.90	0.47	57.23	29.38	517	1.190	1.280	103.04
	11	30	611	0.90	0.47	57.32	29.38	517	0.950	1.020	107.40
	12	32.5	611	0.90	0.31	46.60	29.37	518	0.970	1.041	109.74
Traverse 2	1	62.5	594	1.00	0.54	59.58	29.35	518	1.000	1.072	105.70
	2	65	611	1.00	0.52	60.42	29.38	519	0.980	1.050	104.99
	3	67.5	615	1.00	0.52	60.62	29.38	519	1.000	1.072	107.59
	4	70	613	1.00	0.52	60.52	29.38	519	0.990	1.060	106.23
	5	72.5	614	1.00	0.52	60.57	29.38	519	1.010	1.081	108.38
	6	75	611	0.60	0.31	46.80	29.39	519	0.830	0.835	107.77
	7	77.5	610	0.55	0.29	44.77	29.37	519	0.750	0.862	108.09
	8	80	607	0.45	0.24	40.40	29.37	520	0.670	0.716	106.38
	9	82.5	604	0.40	0.21	38.09	29.37	520	0.620	0.662	104.14
	10	85	605	0.35	0.19	35.54	29.37	520	0.560	0.596	100.55
	11	87.5	605	0.35	0.51	58.60	29.38	520	0.830	0.887	90.53
	12	90	602	1.00	0.53	59.86	29.38	520	0.860	0.941	93.40
Traverse 3	1	92.5	605	1.50	0.80	71.76	29.41	520	1.040	1.112	90.35
	2	95	607	1.50	0.80	71.64	29.39	520	1.210	1.285	105.36
	3	97.5	605	1.60	0.96	80.67	29.41	520	1.160	1.262	93.64
	4	100	602	1.60	0.96	80.47	29.42	520	1.260	1.349	96.79
	5	102.5	599	1.90	1.02	82.47	29.42	520	1.310	1.402	100.73
	6	105	600	1.90	1.02	82.53	29.43	519	1.350	1.447	104.00
	7	107.5	603	1.90	1.02	82.74	29.43	519	1.310	1.447	101.17
	8	110	597	1.90	1.02	82.33	29.43	519	1.340	1.437	103.07
	9	112.5	597	1.60	0.97	80.13	29.43	519	1.310	1.405	103.53
	10	115	600	1.60	0.97	80.33	29.42	519	1.300	1.393	102.66
	11	117.5	598	1.90	0.97	80.20	29.42	519	1.300	1.393	102.71
	12	120	595	1.90	0.97	80.00	29.42	519	1.310	1.403	103.24
Total		120	Average 607	Average 1.15	Average 0.61	Average 62.72	Average 29.39	Average 517	Total 48.660	Total 52.274	Average 104.52

Combustion Gas Data for: Northern Pulp

Client: Northern Pulp
Job Number: 121413456

Plant: Power Boiler
Location: Pictou, NS
Test: PM-4
Date: 11-Mar-15
Personnel: TBH/JJB/JAH

Test Start: 4:00 PM
Test Finish: 4:30 PM

Time (min)	O2 (%)	CO2 (%)	CO (ppm)	SO2 (ppm)	NOx (ppm)
0	10.3	10.1	1249	0	17
5	10.0	10.7	2928	0	16
10	10.4	11.4	1370	0	24
15	9.0	11.7	2984	0	27
20	9.0	11.6	1749	0	33
25	9.4	11.0	1627	0	34
30	9.8	10.5	1646	0	33
Average:	9.7	11.0	1936	0	26

DATA ENTRY

Northern Pulp

Pictou, NS

Fuel: Fuel oil

Operating Conditions:

Emission Control Equipment:

Stack Height from Grade: m

Stack Diameter: m

Reference Temperature, Tref (F): 77
(K): 298
Reference Pressure, Pref (in.Hg): 29.92
(Bar): 1.0

Parameter	Symbol	Units	Test 1	Test 2	Test 3	Average
Test ID	-	-	PM-2	PM-3	PM-4	-
Date	-	-	10-Mar-15	11-Mar-15	11-Mar-15	n/a
Start Time	-	-	8:47 AM	12:00 PM	2:52 PM	n/a
End Time	-	-	10:47 AM	2:00 PM	4:52 PM	n/a
Total Sampling Time	-	min	120	120	120	120
Stack Diameter	D	in.	76	76	76	76
Average Stack Gas Temperature	Ts	F	149	149	147	148
Average Dry Gas Meter Temperature	Tm	F	43	52	57	51
Barometric Pressure	Pbar	in.Hg	29.55	29.38	29.35	29.43
Stack Static Pressure	Pstatic	in.H2O	0.20	0.20	0.20	0.20
Average Pressure Drop (Head)	dP	in.H2O	1.13	0.95	1.15	1.08
Average delta H Orifice	dH	in.H2O	0.60	0.49	0.61	0.57
Average Meter Temperature	Tm	F	43	52	57	51
Gas Sample Volume	Vm	cu.ft	47.77	43.67	48.66	46.70
Average Isokinetics	I	%	107	108	105	108
Nozzle Diameter	Dn	in.	0.172	0.172	0.172	0.172
Pitot Coefficient	Cp	-	0.816	0.816	0.816	0.816
Gamma, meter constant	y	-	1.053	1.053	1.053	1.053
Reference Temperature	Tref	R	537	537	537	537
Reference Pressure	Pref	in.Hg	29.92	29.92	29.92	29.92
Stack Gas Oxygen Content	Co2	%	10.8	11.4	9.7	10.6
Stack Gas Carbon Dioxide Content	Cco2	%	9.8	9.3	11.0	10.0
Stack Gas Nitrogen Content	Cn2	%	79.4	79.4	79.3	79.4
Stack Gas Sulphur Dioxide Content	Cso2	ppm	0.0	0.0	0.0	0.0
Stack Gas Nitrogen Oxides Content	Cnox	ppm	16.1	21.0	26.3	21.1
Stack Gas Carbon Monoxide Content	Cco	ppm	1733.9	2079.0	1936.1	1916.3
Volume of Water Collected	Vw	mL	291	260	285	278
Particulate Collected from Filter	-	mg	198.6	211.4	184.3	198.1
Particulate Collected from Probe Wash	-	mg	20.9	27.8	45.0	31.3
Particulate Collected from Impinger Wash	-	mg	4.8	3.0	4.2	4.0
Total Particulate Collected (excluding impingers)	Mp	mg	220	239	229	229

Legend: F - degrees Fahrenheit
K - degrees Kelvin
Bar - bars
in.Hg - inches of mercury
in. - inches

in.H2O - inches of water
cu.ft - cubic feet
R - degrees Rankin
NOx - as NO2

CALCULATIONS

Northern Pulp

Pictou, NS

Fuel: Fuel oil

Operating Conditions:

Emission Control Equipment:

Stack Height from Grade: m

Stack Diameter: m

Variable	Symbol	Units	Calculation	Test 1	Test 2	Test 3	Average
Stack Area	As	sq.ft sq.m	$As = \pi \times (D/2)^2 \times 1/4$ $As (sq.m) = As (sq.ft) \times 0.0929$	31.50 2.93	31.50 2.93	31.50 2.93	31.50 2.93
Barometric Pressure	Pbar	kPa	$Pbar (kPa) = Pbar (in.Hg) \times 3.386$	100.1	99.5	99.4	99.6
Stack Static Pressure	Pstatic	kPa	$Pstatic (kPa) = Pstatic (in.H2O) \times 0.249$	0.05	0.05	0.05	0.05
Avg. Stack Temperature	Ts	R	$Ts (R) = Ts (F) + 460$	609	609	607	608
Avg. Meter Temperature	Tm	R	$Tm (R) = Tm (F) + 460$	503	512	517	511.0
Nozzle Diameter	Dn	mm	$Dn (mm) = Dn (in.) \times 25.4$	4	4	4	4.4
Gas Meter Pressure	Pm	in.Hg	$Pm = Pbar + (dh / 13.6)$	29.59	29.42	29.39	29.47
Sample Volume at Ref Cond	Vmc	cu.ft cu.m	$Vmc = TrefPref \times (Vm \times Pm \times y) / Tm$ $Vmc (cu.m) = 0.02832 \times Vmc (cu.ft)$	53.09 1.50	47.38 1.34	52.25 1.48	50.9 1.44
Volume of Water Vapour	Vwc	cu.ft	$Vwc = 0.0406 \times Vm$	13.94	12.48	13.87	13.38
Water Fraction	Bwa	-	$Bwa = Vwc / (Vmc + Vwc)$	0.208	0.208	0.207	0.2
Molecular Weight, Dry	Md	lb/lb-mol	$Md = 0.44 (Cco2) + 0.32 (Co2) + 0.28 (Co2)$	30.00	29.94	30.15	30.0
Molecular Weight, Wet	Mw	lb/lb-mol	$Mw = Md (1 - Bwa) + (18 \times Bwa)$	27.50	27.45	27.63	27.5
Stack Pressure	Ps	in.Hg	$Ps = Pbar + (Pstatic / 13.6)$	29.58	29.39	29.36	29.44
Stack Gas Velocity	Us	ft/s m/s	$Us = 85.33 \times Cp \times ((dP \times Ts) / (Ps \times Mw))^{0.5}$ $Us (m/s) = 0.3048 \times Us (ft/s)$	62.07 18.92	56.19 17.13	62.72 19.12	60.3 18.4
Actual Stack Gas Flow Rate	Q	acfm	$Q = 60 \times Us \times As$	117,330	108,218	118,558	114,035
Dry Stack Gas Flow Rate	Qd	Rcfm	$Qd = Q \times (1 - Bwa) \times (TrefTs) \times (Ps/Pref)$ $Qd (Rcfm) = 0.000472 \times Qd (Rcfm)$	81,028 38.25	72,822 34.37	81,607 38.52	78,486 37.0
Sulphur Dioxide - SO2	Cso2	ppm	Measurement from Flow Gas Analyser	0.00	0.00	0.00	0.00
SO2 Measured Concentration	Cso2	mg/Rcm	$Cso2 (mg/Rcm) = Cso2 (ppm) \times 2.62$	0.00	0.00	0.00	0.00
Uncorrected @ Ref Cond	ERso2	g/s	$ERso2 = Cso2/1000 \times Qd$	0.00	0.00	0.00	0.00
SO2 Emission Rate	ERso2	kg/hr	$ERso2 (kg/hr) = 3.6 \times ERso2 (g/s)$	0.00	0.00	0.00	0.00
SO2 Concentration	Cso2	mg/Rcm	$Cso2 (11\% O2) = Cso2 (mg/Rcm) \times (20.9-11) / (20.9-Cso2)$	0.00	0.00	0.00	0.00
Corrected to 11% O2	Cso2	mg/Rcm	$Cso2 (3\% O2) = Cso2 (mg/Rcm) \times (20.9-3) / (20.9-Cso2)$	0.00	0.00	0.00	0.00
Corrected to 3% O2	Cso2	mg/Rcm	$Cso2 (12\% CO2) = Cso2 (mg/Rcm) \times (12/Cso2)$	0.00	0.00	0.00	0.00
Corrected to 12% CO2	Cso2	mg/Rcm					
Nitrogen Oxides - NOx	Cnox	ppm	Measurement from Flow Gas Analyser	16.14	21.00	26.29	21.14
NOx Measured Concentration	Cnox	mg/Rcm	$Cnox (mg/Rcm) = Cnox (ppm) \times 1.882$	30.38	39.52	49.47	39.79
Uncorrected @ Ref Cond	ERnox	g/s	$ERnox = Cnox/1000 \times Qd$	1.16	1.36	1.91	1.48
NOx Emission Rate	ERnox	kg/hr	$ERnox (kg/hr) = 3.6 \times ERnox (g/s)$	4.18	4.89	6.86	5.31
NOx Concentration	Cnox	mg/Rcm	$Cnox (11\% O2) = Cnox (mg/Rcm) \times (20.9-11) / (20.9-Cso2)$	29.70	41.00	43.73	38.14
Corrected to 11% O2	Cnox	mg/Rcm	$Cnox (3\% O2) = Cnox (mg/Rcm) \times (20.9-3) / (20.9-Cso2)$	53.89	74.13	79.06	68.96
Corrected to 3% O2	Cnox	mg/Rcm	$Cnox (12\% CO2) = Cnox (mg/Rcm) \times (12/Cso2)$	37.26	51.23	53.97	47.48
Corrected to 12% CO2	Cnox	mg/Rcm					
Carbon Monoxide - CO	Cco	ppm	Measurement from Flow Gas Analyser	1733.86	2079.00	1936.14	1916.33
CO Measured Concentration	Cco	mg/Rcm	$Cco (mg/Rcm) = Cco (ppm) \times 1.145$	1985.27	2380.46	2216.88	2194.20
Uncorrected @ Ref Cond	ERco	g/s	$ERco = Cco/1000 \times Qd$	75.93	81.82	85.39	81.05
CO Emission Rate	ERco	kg/hr	$ERco (kg/hr) = 3.6 \times ERco (g/s)$	273.34	294.56	307.41	291.77
CO Concentration	Cco	mg/Rcm	$Cco (11\% O2) = Cco (mg/Rcm) \times (20.9-11) / (20.9-Cso2)$	1940.46	2409.54	1959.57	2123.19
Corrected to 11% O2	Cco	mg/Rcm	$Cco (3\% O2) = Cco (mg/Rcm) \times (20.9-3) / (20.9-Cso2)$	3508.52	4485.13	3543.05	3838.90
Corrected to 3% O2	Cco	mg/Rcm	$Cco (12\% CO2) = Cco (mg/Rcm) \times (12/Cso2)$	2434.48	3085.78	2418.42	2646.23
Corrected to 12% CO2	Cco	mg/Rcm					
Particulate Concentration	Cs	mg/Rcm	$Cs = Mp / Vmc$	146.01	178.29	154.92	159.74
Particulate Emission Rate	ERp	g/s kg/hr	$ERp = Cs/1000 \times Qd$ $ERp (kg/hr) = 3.6 \times ERp (g/s)$	5.58 20.10	6.13 22.06	5.97 21.48	5.89 21.22
Particulate Concentration	Cs	mg/Rcm	$Cs (11\% O2) = Cs \times (20.9-11) / (20.9-Cso2)$	142.72	184.96	136.94	154.87
Corrected to 11% O2	Cs	mg/Rcm	$Cs (3\% O2) = Cs \times (20.9-3) / (20.9-Cso2)$	258.04	334.42	247.59	280.02
Corrected to 3% O2	Cs	mg/Rcm	$Cs (12\% CO2) = Cs \times (12/Cso2)$	179.05	231.11	169.00	193.05
Corrected to 12% CO2	Cs	mg/Rcm					

Legend: sq ft - square feet
sq m - square metres
P - 3.142
R - degrees Rankin
ppm - parts per million

in.Hg - inches of mercury
cu.ft - cubic feet
cu.m - cubic metres
Ref Cond - reference temperature and pressure (25 °C and 101.3 kPa)
Rcfm - dry reference cubic metres per second
Rcfm - dry reference cubic feet per minute

mg/Rcm - milligrams per dry reference cubic metre
g/s - grams per second
NOx - as NO2
acfm - actual cubic feet per minute

OFFICIAL STACK TESTING RESULTS

Northern Pulp

Pictou, NS

Fuel: Fuel oil

Operating Conditions:

Emission Control Equipment:

Stack Height from Grade: m

Stack Diameter: m

Parameter	Test 1	Test 2	Test 3	Average	NSENV Limits
Test ID	PM-2	PM-3	PM-4	-	-
Test Date	10-Mar-15	11-Mar-15	11-Mar-15	-	-
Stack Gas Temperature (C)	64.7	65.1	63.9	64.6	-
Moisture Content (%)	20.8	20.8	20.7	20.8	-
Velocity (m/s)	18.9	17.1	19.1	18.4	-
Volumetric Flow (Rcms)	38.2	34.4	38.5	37.0	-
Oxygen - O2 (%)	10.8	11.4	9.7	10.6	-
Carbon Dioxide - CO2 (%)	9.79	9.26	11.0	10.0	-
Sulphur Dioxide - SO2					
SO2 Measured Concentration (ppm)	0.0	0.0	0.0	0.0	-
SO2 Concentration at 11% O2 (mg/Rcm)	0.0	0.0	0.0	0.0	-
Emission Rate (kg/hr)	0.00	0.00	0.00	0.00	-
Nitrogen Oxides - NOx					
NOx Measured Concentration (ppm)	16.1	21.0	26.3	21.1	-
NOx Concentration at 11% O2 (mg/Rcm)	29.7	41.0	43.7	38.1	-
Emission Rate (kg/hr)	4.18	4.89	6.86	5.31	-
Carbon Monoxide - CO					
CO Measured Concentration (ppm)	1734	2079	1936	1916	-
CO Concentration at 11% O2 (mg/Rcm)	1940	2470	1960	2123	-
Emission Rate (kg/hr)	273.3	294.6	307.4	291.8	-
Particulate Matter - PM					
Particulate Concentration at 11% O2 (mg/Rcm)	143	185	137	155	-
Particulate Emission Rate (kg/hr)	20.1	22.1	21.5	21.2	-

Legend: C - degrees Celsius
m/s - metres per second
Rcms - dry reference cubic metres per second
ppm - parts per million

Ref Cond - reference temperature and pressure (25 C and 101.3 kPa)
mg/Rcm - milligrams per dry reference cubic metre
NOx - as NO2
ND - non-detectable

Particulate Recoveries: Impinger Catch, Probe Wash, Filter Catch

Client: Northern Pulp
 Facility: Power Boiler
 Location: Poplar, NS
 Job Number: 121413456

IMPINGER CATCH

Container ID	Beaker Pre Weights [g]				Sample ID	Recoveries				Beaker Post Weights [g]				Unconnected Particulate Weight [g]	Corrected Particulate Weight [g]
	Date					Jar + Sample + Rinse [g]	Jar Tare [g]	Sample Collected [g]	Rinse Water [g]	Total Rinse Water [g]	Date				
	Analyzed by										Analyzed by				
	Trial 1	Trial 2	Trial 3	Average							Total 1	Total 2	Total 3	Average	
M	107 9280	107 9278		107 9279	PM-2	880.0	455.9	290.5	11.0	153.6	107 8334	107 8350		107 8332	0.0048
P5	112 4398	112 4397		112 4398	PM-3	834.3	455.7	259.9	8.9	127.6	112 4432	112 4432		112 4432	0.0030
C2	107 7205	107 7203		107 7204	PM-4	831.2	456.0	284.7	6.3	98.8	107 7251	107 7248		107 7250	0.0042
															Conc. [g/mL]
L23	109 2005	109 2006		109 2006	WB	608.6	455.1	153.5		153.5	109 2010	109 2011		109 2011	0.00003

PROBE WASH

Container ID	Beaker Pre Weights (g)				Sample ID	Recoveries				Beaker Post Weights (g)				Unconnected Particulates Weight (g)	Corrected Particulates Weight (g)
	Date					Jar + Acetone (g)	Jar Tare (g)	Recovered Acetone (g)	Rinse Acetone	Total Acetone (g)	Date				
	Trial 1	Trial 2	Trial 3	Average							Trial 1	Trial 2	Trial 3	Average	
M	112 1840	112 1840		112 1840	PM-2	439.9	324.5	115.4	7.2	122.6	112 2063	112 2064		112 2064	0.0209
AB	110 6382	110 6378		110 6380	PM-3	422.1	324.0	98.1	0.6	107.7	110 6671	110 6671		110 6671	0.0278
N1	112 7048	112 7051		112 7050	PM-4	395.9	324.5	71.4	22.5	93.9	112 7511	112 7510		112 7511	0.0450
															Conc. (g/mL)
N2	112 2684	112 2682		112 2684	AB	383.2	324.9	68.3		68.3	112 2804	112 28		112 2802	0.00009

Density of Acetone: 0.7850 g/ml

FILTER CATCH

Filter ID	Pre Weights [g]				Sample ID	Post Weights [g]				Particulate Weight from Filter [g]
	Analyzed by									
	Trial 1	Trial 2	Trial 3	Average						
0226-21	0.3509	0.3505		0.3507	PM-2	0.5495	0.5491		0.5493	0.1898
0226-20	0.3477	0.3474		0.3476	PM-3	0.5589	0.5590		0.5590	0.2114
0226-15	0.3472	0.3471		0.3472	PM-4	0.5268	0.5262		0.5264	0.1843

Raw Data for: Test #1

Client: Northern Pulp
Job Number: 121413458
Plant: Recovery Boiler
Location: Pictou, NS
Test: PM-1
Date: 10-Mar-15
Personnel: TBN/JJB/AH
Test Start: 9:00 AM
Test Finish: 11:00 AM

Parameters

Barometric Pressure, Pbar (in. Hg)
Stack Static Pressure, Pstatic (in. H2O)
Ambient Temp. (°F)
H2O Volume Collected, Vw (mL)
Total # Sampling Points,
Sampling Time per Point, (min)
Readings Taken Every ___ mins
Regulatory Agency

30.13
1.10
10
540.1
24
5
2.5

O2, (%)
CO2, (%)
N2, (%)
CO(ppm)
NOx (ppm)
SO2 (ppm)

4.8
15.6
79.6
1772.3
23.7
8.1

Particulate Collected from Filter (mg):
Particulate Collected from Probe Wash (mg):
Total Particulate Collected (mg):

1743.4
730.6
2474.2

Impinger No.
Impinger Contents
Final Weight (g)
Tare Weight (g)
Weight of Moisture (g)

1
100 mL H2O
973.5
728.0
247.5
2
100 mL H2O
974.0
728.6
244.4
3
Blank
586.6
570.9
23.7
4
200g Silica Gel
1013.1
980.6
22.5

Total Weight Gain (g)
Moisture Volume (mL)

540.1
540.1

Stack Diameter, (in.)
Stack Area, (sq. ft.)
Probe Length, (in.)
Nozzle Diameter, (in.)
Pitot Coefficient, (Cp)
Gamma, meter constant
Port length (in.)

138
103.87
2
0.234
0.794
1.021
6

Time (min)	Stack Gas Temp, Ts (°F)	S-type Pitot delta P (in. H2O)	Orifice delta P (in. H2O)	Gas Meter Volume (cu. ft.)	Gas Meter Inlet (°F)	Gas Meter Outlet (°F)
2.5	152	0.58	0.82	210.340	50	50
5	152	0.59	0.83	211.530	47	47
7.5	152	0.59	0.83	212.700	47	47
10	154	0.59	0.83	213.890	48	47
12.5	154	0.58	0.81	215.070	48	47
15	154	0.57	0.80	216.270	49	47
17.5	154	0.58	0.82	217.470	49	47
20	154	0.58	0.82	218.650	49	47
22.5	154	0.58	0.82	219.840	49	47
25	154	0.58	0.82	221.080	49	47
27.5	154	0.58	0.82	222.210	49	47
30	154	0.58	0.82	223.390	50	47
32.5	152	0.58	0.81	224.580	50	47
35	154	0.58	0.82	225.750	50	47
37.5	154	0.58	0.82	226.900	50	47
40	154	0.59	0.83	228.120	50	47
42.5	154	0.59	0.83	229.310	51	47
45	154	0.58	0.82	230.510	51	48
47.5	154	0.58	0.82	231.720	52	48
50	151	0.59	0.84	232.890	52	48
52.5	153	0.59	0.84	234.100	52	48
55	153	0.59	0.84	235.250	53	49
57.5	153	0.59	0.84	236.510	53	49
60	153	0.59	0.84	237.720	54	49
				239.020	54	50

62.5	153	0.58	0.82	239.020	51	50
65	154	0.61	0.86	240.450	53	50
67.5	155	0.60	0.85	241.790	53	50
70	154	0.59	0.84	243.070	54	50
72.5	154	0.60	0.85	244.350	54	51
75	154	0.59	0.83	245.550	54	51
77.5	154	0.59	0.83	246.790	55	51
80	154	0.58	0.82	248.020	55	51
82.5	155	0.61	0.86	249.260	55	51
85	154	0.59	0.84	250.510	55	51
87.5	155	0.59	0.84	251.760	55	51
90	154	0.59	0.84	253.000	55	51
92.5	154	0.58	0.84	254.240	55	51
95	153	0.61	0.86	255.470	55	51
97.5	154	0.60	0.85	256.740	55	52
100	152	0.61	0.87	258.060	55	52
102.5	154	0.59	0.84	259.260	55	52
105	155	0.58	0.83	260.550	55	52
107.5	155	0.60	0.85	261.750	55	52
110	155	0.60	0.85	263.000	55	52
112.5	154	0.59	0.84	264.250	55	52
115	153	0.59	0.84	265.500	54	52
117.5	154	0.60	0.85	266.750	54	52
120	153	0.60	0.85	267.990	54	52
				269.250	54	52

Traverse 2

Calculations for: 0
Test #1

Client: Northern Pulp
Job Number: 121413450

Plant: Recovery Boiler
Location: Pictou, NS
Test: PM-1
Date: 10-Mar-15
Personnel: TBH / JBJ/AH

Calculated Parameters

Stack Gas Pressure, Ps (in.Hg)
Stack Gas Molecular Weight, Dry Basis, Md (lb/lb-mole)
Volume of Water Vapour Collected, Vwc (cu.ft)
Stack Gas Moisture Content (% as decimal)
Stack Gas Molecular Weight, Wet Basis, Mw (lb/lb-mole)

Isokineticity Checks

Check range
Check average

30.21
30.59
25.925
0.289
27.03

Within Criteria
Within Criteria

Traverse Point	Time (min)	Stack Gas Temp, Ts (R)	S-type Pitot, delta P (in. H2O)	Orifice delta H (in. H2O)	Stack Gas Velocity, Us (ft/s)	Meter Press., Pm (in. Hg)	Avg. Temp, Tm (F)	Gas Meter Volume, Vm (cu. ft.)	Vol. @ Ref., Vmc (cu. ft.)	Isokinetics I (%)
Traverse 1	2.5	612	0.58	0.82	44.67	30.19	510	1.160	1.291	102.41
	5	612	0.59	0.83	45.06	30.19	507	1.170	1.277	100.43
	7.5	612	0.59	0.83	45.06	30.19	507	1.190	1.269	102.14
	10	614	0.59	0.83	45.13	30.19	500	1.180	1.266	101.35
	12.5	614	0.59	0.81	44.75	30.19	500	1.200	1.308	103.95
	15	614	0.57	0.80	44.36	30.19	500	1.200	1.307	104.75
	17.5	614	0.58	0.82	44.75	30.19	500	1.160	1.285	102.12
	20	614	0.58	0.82	44.75	30.19	508	1.190	1.296	102.98
	22.5	614	0.58	0.82	44.75	30.19	508	1.170	1.274	101.25
	25	614	0.58	0.82	44.75	30.19	508	1.200	1.307	103.85
	27.5	614	0.58	0.82	44.75	30.19	509	1.160	1.284	102.02
	30	614	0.58	0.82	44.75	30.19	509	1.190	1.295	102.88
Traverse 2	32.5	612	0.58	0.82	44.67	30.19	509	1.170	1.273	100.99
	35	614	0.58	0.82	44.75	30.19	509	1.160	1.264	102.02
	37.5	614	0.58	0.82	44.75	30.19	509	1.190	1.295	102.88
	40	614	0.59	0.83	45.13	30.19	510	1.200	1.304	102.77
	42.5	614	0.58	0.83	45.13	30.19	510	1.210	1.313	101.81
	45	614	0.58	0.82	44.75	30.19	510	1.170	1.269	100.66
	47.5	614	0.58	0.82	44.75	30.19	510	1.210	1.313	103.17
	50	611	0.58	0.84	45.02	30.19	511	1.190	1.288	101.43
	52.5	613	0.59	0.84	45.09	30.19	511	1.220	1.321	103.99
	55	613	0.59	0.84	45.09	30.19	512	1.220	1.320	103.89
	57.5	613	0.59	0.84	45.09	30.19	512	1.290	1.394	109.74
	60	613	0.59	0.84	45.09	30.19	512	1.290	1.394	109.74
Traverse 3	62.5	613	0.58	0.82	44.71	30.19	511	1.430	1.550	123.05
	65	614	0.81	0.86	45.89	30.19	512	1.340	1.449	112.31
	67.5	615	0.80	0.85	45.55	30.19	512	1.260	1.365	108.26
	70	614	0.59	0.84	45.13	30.19	512	1.260	1.363	108.96
	72.5	614	0.80	0.85	45.51	30.19	513	1.295	1.395	101.21
	75	614	0.59	0.83	45.13	30.19	513	1.240	1.339	105.47
	77.5	614	0.59	0.83	45.13	30.19	513	1.230	1.328	104.51
	80	614	0.58	0.82	44.75	30.19	513	1.240	1.337	106.26
	82.5	615	0.81	0.86	45.93	30.19	513	1.250	1.348	104.55
	85	614	0.59	0.84	45.13	30.19	513	1.250	1.348	106.22
	87.5	615	0.59	0.84	45.17	30.19	513	1.240	1.337	105.45
	90	614	0.59	0.84	45.13	30.19	513	1.240	1.337	105.37
Traverse 4	92.5	614	0.58	0.82	44.75	30.19	513	1.230	1.326	105.41
	95	613	0.81	0.86	45.85	30.19	513	1.270	1.370	106.05
	97.5	614	0.85	0.85	45.51	30.19	514	1.260	1.358	106.07
	100	612	0.81	0.87	45.81	30.19	514	1.260	1.358	105.03
	102.5	614	0.59	0.84	45.13	30.19	514	1.290	1.390	109.51
	105	615	0.58	0.83	44.78	30.19	514	1.200	1.293	102.82
	107.5	615	0.60	0.85	45.55	30.19	514	1.250	1.347	105.31
	110	615	0.60	0.85	45.55	30.19	514	1.250	1.347	105.31
	112.5	614	0.59	0.84	45.13	30.19	514	1.250	1.347	106.11
	115	613	0.59	0.84	45.09	30.19	513	1.250	1.348	106.13
	117.5	614	0.50	0.85	45.51	30.19	513	1.240	1.337	104.49
	120	613	0.50	0.85	45.47	30.19	513	1.280	1.359	106.08
Total	120	Average 614	Average 0.59	Average 0.83	Average 45.08	Average 30.19	Average 511	Total 50.910	Total 63.767	Average 104.75

Combustion Gas Data for: Northern Pulp

Client: Northern Pulp
Job Number: 121413456

Plant: Recovery Boiler
Location: Pictou, NS
Test: PM-1
Date: 10-Mar-15
Personnel: TBH / JJB/JAH

Test Start: 10:00 AM
Test Finish: 10:30 AM

Time (min)	O2 (%)	CO2 (%)	CO (ppm)	SO2 (ppm)	NOx (ppm)
0	4.9	15.5	2581	8	17
5	4.9	15.5	2943	9	19
10	5.1	15.4	1346	8	21
15	4.9	15.6	1281	9	23
20	4.8	15.7	1263	8	25
25	4.5	15.9	1453	7	32
30	4.5	15.9	1539	8	29
Average:	4.8	15.6	1772	8	24

Raw Data for: Test #2

0

Client: Northern Pup
Job Number: 121413456

Plant: Recovery Boiler
Location: Picou, NS
Test: PM-2
Date: 10-Mar-13
Personnel: TBH / JBB/AH

Test Start: 12:13 PM
Test Finish: 2:13 PM

Parameters

Barometric Pressure, Pbar (in. Hg)
Stack Static Pressure, Pstatic (in. H2O)
Ambient Temp. (°F)
H2O Volume Collected, Vw (mL)
Total # Sampling Points,
Sampling Time per Point, (min)
Readings Taken Every ____ mins
Regulatory Agency

Impinger No.	Impinger Contents	Final Weight (g)	Tare Weight (g)	Weight of Moisture (g)
1	100 mL H2O	987.2	725.7	261.5
2	100 mL H2O	874.2	723.1	251.1
3	Blank	581.2	571.6	9.6
4	200g Silica Gel	1032.6	1013.2	19.4
		Total Weight Gain (g)		541.6
		Moisture Volume (mL)		541.6

Stack Diameter, (in.)
Stack Area, (sq. ft.)
Probe Length, (ft.)
Nozzle Diameter, (in.)
Pilot Coefficient, (Cp)
Gasflow, meter constant
Port length (in.)

O2, (%)
CO2, (%)
H2, (%)
CO (ppm)
NOx (ppm)
SO2 (ppm)

Particulate Collected from Filter (mg):
Particulate Collected from Probe Wash (mg):
Particulate Collected from Impinger Wash (mg):
Total Particulate Collected (mg):

Time (min)

Traverse Point

Stack Gas Temp, Ts (°F)

S-type Pilot delta P (in. H2O)

Orifice delta H (in. H2O)

Gas Meter Volume (cu. ft.)

Gas Meter Temp Inlet (°F)

Gas Meter Temp Outlet (°F)

Traverse 1	1	2.5	151	0.64	0.91	269.420	53	53
	2	5	152	0.64	0.91	270.680	55	53
	3	7.5	154	0.64	0.91	271.960	55	53
	4	10	154	0.66	0.94	272.248	56	53
	5	12.5	154	0.66	0.94	274.510	57	54
	6	15	155	0.65	0.93	275.500	58	54
	7	17.5	155	0.65	0.93	277.100	58	54
	8	20	155	0.65	0.93	278.340	59	55
	9	22.5	155	0.65	0.93	279.630	59	55
	10	25	156	0.65	0.93	282.150	60	56
	11	27.5	157	0.66	0.94	283.448	61	56
	12	30	157	0.66	0.94	284.700	61	57
	13	32.5	155	0.66	0.93	285.980	60	57
	14	35	154	0.66	0.93	287.250	60	57
	15	37.5	155	0.66	0.93	288.310	61	57
	16	40	156	0.66	0.96	289.820	61	57
	17	42.5	155	0.67	0.96	291.120	61	57
	18	45	155	0.66	0.95	292.400	62	58
	19	47.5	155	0.67	0.96	293.690	62	58
	20	50	155	0.67	0.96	295.000	61	58
	21	52.5	155	0.67	0.96	296.290	61	58
	22	55	156	0.65	0.93	297.600	62	58
	23	57.5	157	0.66	0.95	298.870	62	58
	24	60	155	0.66	0.95	300.160	61	58

Traverse 2	1	62.5	156	0.66	0.95	300.160	61	58
	2	65	155	0.66	0.95	301.470	61	59
	3	67.5	153	0.65	0.94	302.750	61	58
	4	70	155	0.66	0.95	304.040	60	59
	5	72.5	155	0.66	0.95	305.320	59	58
	6	75	155	0.66	0.95	306.620	59	58
	7	77.5	154	0.66	0.95	307.890	59	58
	8	80	154	0.66	0.95	309.180	58	58
	9	82.5	151	0.66	0.95	310.480	58	57
	10	85	152	0.66	0.95	311.760	57	57
	11	87.5	153	0.66	0.95	313.040	56	56
	12	90	153	0.67	0.96	314.330	56	56
	13	92.5	152	0.66	0.95	315.630	56	56
	14	95	152	0.66	0.95	316.920	55	55
	15	97.5	152	0.66	0.95	318.220	55	55
	16	100	151	0.66	0.94	319.500	54	54
	17	102.5	153	0.66	0.94	320.770	54	54
	18	105	152	0.65	0.93	322.050	54	54
	19	107.5	153	0.66	0.94	323.340	53	53
	20	110	153	0.66	0.94	324.610	54	53
	21	112.5	153	0.66	0.94	325.900	54	53
	22	115	153	0.66	0.94	327.220	54	53
	23	117.5	154	0.66	0.94	328.510	54	53
	24	120	154	0.66	0.94	329.800	54	53

Calculations for: 0
Test #2

Client: Northern Pulp
Job Number: 121413456
Plant: Recovery Boiler
Location: Pictou, NS
Test: PM4-2
Date: 10-Mar-15
Personnel: TBH / JJB/UAH

Calculated Parameters

Stack Gas Pressure, Ps (in.Hg)
Stack Gas Molecular Weight, Dry Basis, Md (lb/lb-mole)
Volume of Water Vapour Collected, Vwc (cu.ft)
Stack Gas Moisture Content (% as decimal)
Stack Gas Molecular Weight, Wet Basis, Mw (lb/lb-mole)

30.20
30.73
25.997
0.283
27.13

Isokineticity Checks

Check range
Check average
Within Criteria
Within Criteria

Traverse Point	Time (min)	Stack Gas Temp, T _s (°F)	S-type Pilot, delta P (in. H2O)	Orifice delta H (in. H2O)	Stack Gas Velocity, V _s (ft/s)	Meter Press., P _m (in. Hg)	Avg. Temp., T _m (°F)	Gas Meter Volume, V _m (cu. ft.)	Vol. @ Ref., V _m @ Ref. (cu. ft.)	Isokinetics I (%)
Traverse 1	2.5	611	0.64	0.91	46.81	30.19	513	1.260	1.359	101.83
	5	612	0.64	0.91	46.84	30.19	514	1.280	1.378	101.33
	7.5	614	0.64	0.91	46.92	30.19	514	1.280	1.378	101.50
	10	614	0.66	0.94	47.85	30.19	515	1.270	1.369	101.03
	12.5	614	0.66	0.94	47.85	30.19	516	1.290	1.384	102.42
	15	615	0.65	0.93	47.32	30.19	516	1.300	1.394	103.99
	17.5	615	0.65	0.93	47.32	30.19	516	1.240	1.329	98.19
	20	615	0.65	0.93	47.32	30.19	517	1.290	1.380	102.99
	22.5	615	0.65	0.93	47.32	30.19	517	1.250	1.338	99.79
	25	616	0.65	0.93	47.36	30.19	518	1.270	1.358	101.38
	27.5	617	0.66	0.94	47.76	30.19	518	1.260	1.378	102.18
	30	617	0.66	0.94	47.76	30.19	518	1.260	1.344	96.70
Traverse 2	32.5	615	0.66	0.95	47.68	30.19	518	1.260	1.368	101.12
	35	614	0.66	0.95	47.65	30.19	519	1.270	1.355	100.25
	37.5	615	0.66	0.95	47.69	30.19	519	1.280	1.384	101.03
	40	616	0.66	0.96	47.73	30.19	519	1.290	1.375	101.90
	42.5	615	0.67	0.96	48.05	30.19	519	1.300	1.388	101.84
	45	615	0.66	0.95	47.89	30.19	520	1.260	1.362	100.83
	47.5	615	0.67	0.96	48.05	30.19	520	1.290	1.372	100.66
	50	615	0.67	0.96	48.05	30.19	520	1.310	1.395	102.52
	52.5	615	0.67	0.96	48.05	30.19	520	1.290	1.374	100.96
	55	618	0.65	0.93	47.36	30.19	520	1.310	1.394	104.07
	57.5	617	0.66	0.95	47.76	30.19	520	1.270	1.351	100.21
	60	615	0.66	0.95	47.69	30.19	520	1.290	1.374	101.72
Traverse 2	62.5	618	0.66	0.95	47.73	30.19	520	1.310	1.395	102.38
	65	615	0.66	0.95	47.69	30.19	520	1.290	1.362	100.83
	67.5	613	0.65	0.94	47.25	30.19	520	1.290	1.374	102.33
	70	615	0.66	0.95	47.69	30.19	520	1.280	1.363	100.93
	72.5	615	0.66	0.95	47.69	30.19	519	1.300	1.387	102.70
	75	615	0.66	0.95	47.69	30.19	519	1.270	1.355	100.33
	77.5	614	0.66	0.95	47.85	30.19	518	1.270	1.378	101.93
	80	614	0.66	0.95	47.85	30.19	518	1.300	1.390	102.82
	82.5	611	0.66	0.95	47.53	30.19	518	1.368	1.388	100.96
	85	612	0.66	0.95	47.57	30.19	517	1.280	1.370	101.17
	87.5	613	0.67	0.96	47.87	30.19	516	1.333	1.383	102.24
	90	612	0.66	0.95	47.57	30.19	516	1.300	1.384	102.26
Traverse 2	92.5	612	0.66	0.95	47.57	30.19	515	1.300	1.396	102.16
	95	612	0.66	0.95	47.57	30.19	515	1.280	1.375	101.15
	97.5	611	0.66	0.94	47.53	30.19	514	1.270	1.367	100.86
	100	611	0.66	0.94	47.61	30.19	514	1.290	1.378	100.86
	102.5	613	0.65	0.93	47.21	30.19	514	1.290	1.388	101.34
	105	612	0.65	0.94	47.61	30.19	513	1.270	1.370	101.24
	107.5	613	0.66	0.94	47.61	30.19	514	1.290	1.390	102.74
	110	613	0.66	0.94	47.61	30.19	514	1.320	1.422	105.13
	112.5	613	0.66	0.94	47.61	30.19	514	1.320	1.422	105.13
	115	613	0.66	0.94	47.61	30.19	514	1.390	1.390	102.74
	117.5	614	0.66	0.94	47.65	30.19	514	1.290	1.390	102.62
	120	614	0.66	0.94	47.65	30.19	514	1.280	1.379	102.02
Total	120	Average 614	Average 0.66	Average 0.94	Average 47.58	Average 30.19	Average 517	Total 61.660	Total 65.997	Average 101.88

Combustion Gas Data for: Northern Pulp

Client: Northern Pulp
Job Number: 121413456

Plant: Recovery Boiler
Location: Pictou, NS
Test: PM-2
Date: 10-Mar-15
Personnel: TBH / JJB/JAH

Test Start: 12:00 PM
Test Finish: 12:30 PM

Time (min)	O2 (%)	CO2 (%)	CO (ppm)	SO2 (ppm)	NOx (ppm)
0	4.5	15.9	2465	8	42
5	4.5	15.8	2647	7	34
10	4.4	16.0	2660	7	36
15	4.4	16.0	3058	6	49
20	4.5	16.0	2893	6	42
25	4.6	15.9	2973	5	59
30	4.6	15.8	3025	4	61
Average:	4.5	15.9	2817	6	46

Raw Data for: Test #3

0

Client: Northern Pup
Job Number: 121413456

Plant: Recovery Boiler
Location: Pictou, NS
Test: PM-3
Date: 11-Mar-15
Personnel: TBH/TB/JAH

Test Start: 9:20 AM
Test Finish: 11:20 AM

Parameters

Barometric Pressure, Pbar (in. Hg)
Stack Static Pressure, Pstatic (in. H2O)
Ambient Temp, (°F)
H2O Volume Collected, Vw (mL)
Total # Sampling Points,
Sampling Time per Point, (min)
Readings Taken Every ___ mins
Regulatory Agency

29.55
1.10
28
540.60
24
5
2.5
0

CO2 (%)
CO2 (%)
N2 (%)
CO (ppm)
NOx (ppm)
SO2 (ppm)

4.4
16.1
79.5
3083.0
52.1
27.9

Stack Diameter, (in.)
Stack Area, (sq. ft.)
Probe Length, (ft.)
Nozzle Diameter, (in.)
Pilot Coefficient, (Cp)
Gasflow, meter constant
Port length, (in.)

136
103.87
2
0.234
0.794
1.021
6

Impinger No. Impinger Contents Final Weight (g) Tare Weight (g) Weight of Moisture (g)

1 100 mL H2O 995.8 730.8 265.0
2 100 mL H2O 957.9 718.3 239.6
3 Blank 562.6 570.7 11.9
4 200g Silica Gel 873.8 849.7 24.1

Total Weight Gain (g)
Moisture Volume (mL)

540.6
540.6

Particulate Collected from Filter (mg): 1506.2
Particulate Collected from Probe Wash (mg): 714.8
Total Particulate Collected (mg): 2219.8

Traverse Point	Time (min)	Stack Gas Temp, Ts (°F)	S-type Pilot Delta P (in. H2O)	Orifice Delta H (in. H2O)	Gas Meter Volume (cu. ft.)	Gas Meter Inlet Temp (°F)	Gas Meter Outlet Temp (°F)
Traverse 1	1	150	0.56	0.79	334.370	43	43
	2.5	149	0.57	0.80	335.610	44	43
	5	150	0.59	0.83	337.990	44	43
	7.5	150	0.59	0.83	339.250	44	43
	10	151	0.58	0.81	340.400	44	43
	12.5	151	0.58	0.81	341.620	45	43
	15	152	0.58	0.81	342.840	46	44
	17.5	151	0.57	0.80	344.010	46	44
	20	150	0.57	0.82	345.240	47	44
	22.5	150	0.58	0.82	346.470	47	44
	25	151	0.57	0.80	347.650	47	44
	27.5	151	0.57	0.80	348.860	47	44
	30	151	0.58	0.82	350.070	47	44
	32.5	15	0.58	0.85	351.210	46	45
	35	150	0.59	0.79	352.400	47	45
	37.5	151	0.56	0.82	353.650	47	45
	40	151	0.58	0.82	354.950	47	45
	42.5	151	0.58	0.82	356.070	47	45
	45	151	0.59	0.84	357.270	48	45
	47.5	148	0.57	0.80	358.490	48	45
	50	151	0.57	0.82	359.690	48	46
	52.5	149	0.58	0.80	360.860	48	46
	55	151	0.57	0.82	362.040	50	46
	57.5	149	0.58	0.82	363.170	50	46
	60	149	0.57	0.81			
Traverse 2	1	150	0.58	0.82	363.170	50	46
	2.5	150	0.57	0.81	364.380	50	46
	5	150	0.58	0.82	365.570	51	47
	7.5	150	0.58	0.82	366.760	51	47
	10	150	0.58	0.82	367.980	51	47
	12.5	150	0.58	0.82	369.160	51	47
	15	148	0.58	0.83	370.260	51	47
	17.5	150	0.57	0.81	371.560	51	47
	20	150	0.59	0.84	372.770	51	47
	22.5	150	0.59	0.84	374.000	51	47
	25	150	0.58	0.82	375.210	51	47
	27.5	151	0.58	0.82	376.390	51	48
	30	150	0.57	0.81	377.620	51	48
	32.5	149	0.58	0.82	378.820	51	48
	35	150	0.58	0.82	380.020	52	48
	37.5	150	0.59	0.84	381.230	52	48
	40	149	0.59	0.84	382.440	53	49
	42.5	149	0.59	0.84	383.670	53	49
	45	148	0.60	0.86	384.900	53	49
	47.5	148	0.60	0.86	386.140	54	50
	50	149	0.60	0.86	387.380	54	50
	52.5	148	0.59	0.85	388.630	54	50
	55	149	0.59	0.84	389.860	54	50
	57.5	150	0.60	0.86	391.080	54	51
	60	149	0.60	0.86	392.310	54	52

Calculations for: 0
Test #3

Client: Northern Pulp
Job Number: 121413456

Plant: Recovery Boiler
Location: Pictou, NS

Test: PMA3

Date: 11-Mar-15
Personnel: TBHJLBJAH

Calculated Parameters

Stack Gas Pressure, P_s (in.Hg)
Stack Gas Molecular Weight, Dry Basis, M_d (lb/lb-mole)
Volume of Water Vapour Collected, V_{wc} (cu.ft)
Stack Gas Moisture Content (% as decimal)
Stack Gas Molecular Weight, Wet Basis, M_w (lb/lb-mole)

29.83
30.75
25.949
0.285
26.96

Isokineticity Checks

Check range
Check average

Within Criteria
Within Criteria

Time (min)	Traverse Point	Stack Gas Temp, T _s (°F)	S-type Pitot, delta P (in. H ₂ O)	Orifice delta H (in. H ₂ O)	Stack Gas Velocity, U _s (ft/s)	Meter Press., P _m (in. Hg)	Avg. Temp, T _m (°F)	Gas Meter Volume, V _m (cu. ft.)	Vol. @ Ref., V _{mc} (cu. ft.)	Isokinetics I (%)
2.5	1	610	0.56	0.79	44.29	29.81	503	1.240	1.338	109.76
5	2	609	0.57	0.80	44.84	29.81	504	1.200	1.283	105.06
7.5	3	610	0.59	0.83	45.46	29.81	504	1.180	1.272	101.67
10	4	610	0.58	0.81	45.11	29.81	504	1.290	1.358	108.56
12.5	5	611	0.56	0.81	45.14	29.81	504	1.150	1.239	100.01
15	6	612	0.58	0.81	45.14	29.81	504	1.220	1.313	108.00
17.5	7	611	0.59	0.81	45.11	29.81	505	1.220	1.311	105.78
20	8	610	0.57	0.80	44.86	29.81	505	1.170	1.257	102.25
22.5	9	610	0.58	0.82	45.07	29.81	506	1.230	1.320	106.46
25	10	611	0.58	0.82	45.11	29.81	506	1.230	1.320	106.55
27.5	11	611	0.57	0.80	44.72	29.81	508	1.180	1.267	103.10
30	12	611	0.57	0.80	44.72	29.81	508	1.210	1.299	105.72
32.5	1	610	0.58	0.82	45.46	29.81	508	1.210	1.299	105.72
35	2	610	0.59	0.85	45.46	29.81	508	1.140	1.224	97.84
37.5	3	610	0.56	0.79	44.29	29.81	508	1.190	1.278	104.71
40	4	611	0.58	0.82	45.11	29.81	508	1.250	1.340	108.17
42.5	5	611	0.58	0.82	45.11	29.81	508	1.290	1.373	110.77
45	6	611	0.58	0.82	45.11	29.81	508	1.140	1.222	98.65
47.5	7	608	0.59	0.84	45.36	29.81	507	1.200	1.266	102.61
50	8	611	0.57	0.80	44.72	29.81	507	1.200	1.307	106.39
52.5	9	609	0.56	0.82	45.03	29.81	507	1.290	1.394	103.47
55	10	611	0.57	0.80	44.72	29.81	507	1.170	1.252	101.93
57.5	11	609	0.56	0.82	45.03	29.81	508	1.180	1.260	101.55
60	12	609	0.57	0.81	44.54	29.81	508	1.130	1.207	98.09
62.5	1	610	0.58	0.82	45.07	29.85	508	1.210	1.290	104.00
65	2	610	0.57	0.81	44.80	29.81	508	1.190	1.271	103.39
67.5	3	610	0.58	0.82	45.07	29.81	508	1.190	1.269	102.29
70	4	610	0.58	0.82	45.07	29.81	508	1.220	1.301	104.87
72.5	5	610	0.58	0.83	45.07	29.81	508	1.180	1.258	101.43
75	6	608	0.56	0.83	45.00	29.81	508	1.100	1.173	94.40
77.5	7	610	0.57	0.81	44.68	29.81	508	1.300	1.388	112.72
80	8	610	0.59	0.84	45.46	29.81	509	1.210	1.290	103.12
82.5	9	610	0.59	0.84	45.46	29.81	509	1.230	1.311	104.83
85	10	610	0.58	0.82	45.07	29.81	509	1.210	1.290	104.01
87.5	11	611	0.58	0.82	45.11	29.81	510	1.180	1.257	101.41
90	12	610	0.57	0.81	44.86	29.81	510	1.230	1.290	106.55
92.5	1	609	0.58	0.82	45.03	29.81	510	1.200	1.278	102.98
95	2	610	0.58	0.82	45.07	29.81	510	1.200	1.277	102.95
97.5	3	610	0.58	0.84	45.46	29.81	510	1.210	1.287	102.82
100	4	609	0.59	0.84	45.42	29.81	511	1.210	1.285	102.64
102.5	5	609	0.59	0.84	45.42	29.81	511	1.230	1.308	104.34
105	6	608	0.60	0.86	45.77	29.81	511	1.230	1.308	103.39
107.5	7	608	0.60	0.86	45.77	29.81	511	1.240	1.317	104.22
110	8	609	0.60	0.86	45.80	29.81	512	1.240	1.314	104.11
112.5	9	608	0.60	0.86	45.77	29.81	512	1.250	1.325	104.86
115	10	608	0.59	0.84	45.42	29.81	512	1.230	1.304	104.14
117.5	11	610	0.60	0.86	45.84	29.81	513	1.220	1.292	102.41
120	12	609	0.60	0.86	45.80	29.81	513	1.230	1.301	103.07
Total 120		Average 607	Average 0.58	Average 0.82	Average 45.02	Average 29.81	Average 508	Total 57.940	Total 61.912	Average 103.60

Combustion Gas Data for: Northern Pulp

Client: Northern Pulp
Job Number: 121413456

Plant: Recovery Boiler
Location: Pictou, NS
Test: PM-3
Date: 11-Mar-15
Personnel: TBH/JJB/JAH

Test Start: 11:00 AM
Test Finish: 11:30 AM

Time (min)	O2 (%)	CO2 (%)	CO (ppm)	SO2 (ppm)	NOx (ppm)
0	4.5	15.9	3018	25	47
5	4.7	15.9	3129	36	49
10	4.0	16.4	3099	44	51
15	4.2	16.1	2938	30	52
20	4.6	15.9	3214	20	54
25	4.5	16.0	3009	17	56
30	4.2	16.3	3174	23	56
Average:	4.4	16.1	3083	28	52

DATA ENTRY

Northern Pulp

Pictou, NS

Fuel: Fuel oil

Operating Conditions: Normal

Emission Control Equipment: wet scrubber

Stack Height from Grade: 69 m

Stack Diameter: 3.51 m

Reference Temperature, Tref (F): 77
(K): 298
Reference Pressure, Pref (in.Hg): 29.92
(Bar): 1.0

Parameter	Symbol	Units	Test 1	Test 2	Test 3	Average
Test ID	-	-	PM-1	PM-2	PM-3	-
Date	-	-	10-Mar-15	10-Mar-15	11-Mar-15	n/a
Start Time	-	-	9:00 AM	12:15 PM	9:20 AM	n/a
End Time	-	-	11:00 AM	2:15 PM	11:20 AM	n/a
Total Sampling Time	-	min	120	120	120	120
Stack Diameter	D	in.	138	138	138	138
Average Stack Gas Temperature	Ts	F	154	154	147	152
Average Dry Gas Meter Temperature	Tm	F	51	57	48	52
Barometric Pressure	Pbar	in.Hg	30.13	30.12	29.55	29.93
Stack Static Pressure	Pstatic	in.H2O	1.10	1.10	1.10	1.10
Average Pressure Drop (Head)	dP	in.H2O	0.59	0.66	0.58	0.61
Average deltaH Orifice	dH	in.H2O	0.83	0.94	0.82	0.87
Average Meter Temperature	Tm	F	51	57	48	52
Gas Sample Volume	Vm	cu.ft	58.91	61.66	57.94	59.50
Average Isokinetics	I	%	105	102	104	103
Nozzle Diameter	Dn	in.	0.234	0.234	0.234	0.234
Pitot Coefficient	Cp	-	0.794	0.794	0.794	0.794
Gamma, meter constant	y	-	1.021	1.021	1.021	1.021
Reference Temperature	Tref	R	537	537	537	537
Reference Pressure	Pref	in.Hg	29.92	29.92	29.92	29.92
Stack Gas Oxygen Content	Co2	%	4.8	4.5	4.4	4.6
Stack Gas Carbon Dioxide Content	Cco2	%	15.6	15.9	16.1	15.9
Stack Gas Nitrogen Content	Cn2	%	79.6	79.6	79.5	79.6
Stack Gas Sulphur Dioxide Content	Cso2	ppm	8.1	6.1	27.9	14.0
Stack Gas Nitrogen Oxides Content	Cnox	ppm	23.7	46.1	52.1	40.7
Stack Gas Carbon Monoxide Content	Cco	ppm	1772.3	2817.3	3083.0	2557.5
Volume of Water Collected	Vw	mL	540	542	541	541
Particulate Collected from Filter	-	mg	1743.4	1626.3	1505.2	1625.0
Particulate Collected from Probe Wash	-	mg	730.6	1152.8	714.6	866.1
Particulate Collected from Impinger Wash	-	mg	1.94	4.54	3.27	3.25
Total Particulate Collected (excluding impingers)	Mp	mg	2,474	2,779	2,220	2,491

Legend: F - degrees Fahrenheit
K - degrees Kelvin
Bar - bars
in.Hg - inches of mercury
in. - inches

in.H2O - inches of water
cu.ft - cubic feet
R - degrees Rankin
NOx - as NO2

CALCULATIONS
 Northern Pulp
 Pictou, NS
 Fuel: Fuel oil
 Operating Conditions: Normal
 Emission Control Equipment: wet scrubber
 Stack Height from Grade: 69 m
 Stack Diameter: 3.51 m

Variable	Symbol	Units	Calculation	Test 1	Test 2	Test 3	Average
Stack Area	A_s	sq. ft sq. m	$A_s = \pi \times ((D/12)^2 \times \pi / 4)$ $A_s \text{ (sq.m)} = A_s \text{ (sq.ft)} \times 0.0929$	103.87 9.65	103.87 9.65	103.87 9.65	103.87 9.65
Barometric Pressure	P_{bar}	kPa	$P_{bar} \text{ (kPa)} = P_{bar} \text{ (in.Hg)} \times 3.386$	102.0	102.0	100.1	101.4
Stack Static Pressure	P_{static}	kPa	$P_{static} \text{ (kPa)} = P_{static} \text{ (in.Hg)} \times 3.386$	0.27	0.27	0.27	0.27
Avg. Stack Temperature	T_s	R	$T_s \text{ (R)} = T_s \text{ (F)} + 460$	614	614	607	612
Avg. Meter Temperature	T_m	R	$T_m \text{ (R)} = T_m \text{ (F)} + 460$	511	517	508	511.8
Nozzle Diameter	D_n	mm	$D_n \text{ (mm)} = D_n \text{ (in.)} \times 25.4$	6	6	6	5.9
Gas Meter Pressure	P_m	in.Hg	$P_m = P_{bar} + (dH / 13.6)$	30.19	30.19	29.61	30.00
Sample Volume at Ref Cond	V_{mc}	cu.ft cu.m	$V_{mc} = T_{ref} \times P_{ref} \times (V_m \times P_m \times \gamma) / T_m$ $V_{mc} \text{ (cu.m)} = 0.02832 \times V_{mc} \text{ (cu.ft)}$	63.79 1.81	66.00 1.87	61.92 1.75	63.9 1.81
Volume of Water Vapour	V_{wc}	cu.ft	$V_{wc} = 0.0488 \times V_w$	25.92	26.00	25.95	25.96
Water Fraction	B_{wo}	-	$B_{wo} = V_{wc} / (V_{wc} + V_{mc})$	0.289	0.283	0.295	0.3
Molecular Weight, Dry	M_d	lb/lb-mol	$M_d = 0.44 \times (C_{co2}) + 0.32 \times (C_{co}) + 0.28 \times (C_{co2})$	30.69	30.73	30.75	30.7
Molecular Weight, Wet	M_s	lb/lb-mol	$M_s = M_d \times (1 - B_{wo}) + (18 \times B_{wo})$	27.03	27.13	26.98	27.0
Stack Pressure	P_s	in.Hg	$P_s = P_{bar} + (P_{static} / 13.6)$	30.21	30.20	29.63	30.01
Stack Gas Velocity	U_s	ft/s m/s	$U_s = 85.33 \times C_p \times ((dP \times T_s) / (P_s \times M_s))^{0.5}$ $U_s \text{ (m/s)} = 0.3048 \times U_s \text{ (ft/s)}$	45.08 13.74	47.58 14.50	45.02 13.72	45.9 14.0
Actual Stack Gas Flow Rate	Q	scfm	$Q = 60 \times U_s \times A_s$	280,972	296,542	280,554	286,023
Dry Stack Gas Flow Rate	Q_d	Rcfm Rcms	$Q_d = Q \times (1 - B_{wo}) \times (T_{ref} / T_s) \times (P_s / P_{ref})$ $Q_d \text{ (Rcms)} = 0.000472 \times Q_d \text{ (Rcfm)}$	176,516 83.32	187,783 86.63	173,197 81.75	179,165 84.6
Sulphur Dioxide - SO ₂							
SO ₂ Measured Concentration	C_{so2}	ppm	Measurement from Flow Gas Analyser	8.14	6.14	27.86	14.05
Uncorrected @ Ref Cond	C_{so2}	mg/Rcm	$C_{so2} \text{ (mg/Rcm)} = C_{so2} \text{ (ppm)} \times 2.62$	21.33	16.09	72.99	36.80
SO ₂ Emission Rate	ER_{so2}	g/s kg/hr	$ER_{so2} = C_{so2} / 1000 \times Q_d$ $ER_{so2} \text{ (kg/hr)} = 3.6 \times ER_{so2} \text{ (g/s)}$	1.78 6.40	1.43 5.14	5.97 21.48	3.08 11.00
SO ₂ Concentration							
Corrected to 11% O ₂	C_{so2}	mg/Rcm	$C_{so2} \text{ (11% O}_2\text{)} = C_{so2} \text{ (mg/Rcm)} \times (20.9 - 11) / (20.9 - C_{o2})$	13.12	9.72	43.75	22.20
Corrected to 3% O ₂	C_{so2}	mg/Rcm	$C_{so2} \text{ (3% O}_2\text{)} = C_{so2} \text{ (mg/Rcm)} \times (20.9 - 3) / (20.9 - C_{o2})$	23.72	17.57	79.11	40.13
Corrected to 12% CO ₂	C_{so2}	mg/Rcm	$C_{so2} \text{ (12% CO}_2\text{)} = C_{so2} \text{ (mg/Rcm)} \times (12 / C_{co2})$	16.37	12.14	54.50	27.67
Nitrogen Oxides - NO _x							
NO _x Measured Concentration	C_{nox}	ppm	Measurement from Flow Gas Analyser	23.71	46.14	52.14	40.67
Uncorrected @ Ref Cond	C_{nox}	mg/Rcm	$C_{nox} \text{ (mg/Rcm)} = C_{nox} \text{ (ppm)} \times 1.382$	44.83	66.84	98.13	76.53
NO _x Emission Rate	ER_{nox}	g/s kg/hr	$ER_{nox} = C_{nox} / 1000 \times Q_d$ $ER_{nox} \text{ (kg/hr)} = 3.6 \times ER_{nox} \text{ (g/s)}$	3.72 13.39	7.70 27.71	8.02 28.88	6.48 23.33
NO _x Concentration							
Corrected to 11% O ₂	C_{nox}	mg/Rcm	$C_{nox} \text{ (11% O}_2\text{)} = C_{nox} \text{ (mg/Rcm)} \times (20.9 - 11) / (20.9 - C_{o2})$	27.44	52.42	58.83	48.23
Corrected to 3% O ₂	C_{nox}	mg/Rcm	$C_{nox} \text{ (3% O}_2\text{)} = C_{nox} \text{ (mg/Rcm)} \times (20.9 - 3) / (20.9 - C_{o2})$	49.82	94.78	106.37	83.59
Corrected to 12% CO ₂	C_{nox}	mg/Rcm	$C_{nox} \text{ (12% CO}_2\text{)} = C_{nox} \text{ (mg/Rcm)} \times (12 / C_{co2})$	34.24	65.48	73.27	57.66
Carbon Monoxide - CO							
CO Measured Concentration	C_{co}	ppm	Measurement from Flow Gas Analyser	1772.29	2817.29	3083.00	2557.52
Uncorrected @ Ref Cond	C_{co}	mg/Rcm	$C_{co} \text{ (mg/Rcm)} = C_{co} \text{ (ppm)} \times 1.145$	2029.27	3225.79	3530.04	2928.36
CO Emission Rate	ER_{co}	g/s kg/hr	$ER_{co} = C_{co} / 1000 \times Q_d$ $ER_{co} \text{ (kg/hr)} = 3.6 \times ER_{co} \text{ (g/s)}$	169.07 608.85	285.91 1029.29	288.58 1038.88	247.85 892.27
CO Concentration							
Corrected to 11% O ₂	C_{co}	mg/Rcm	$C_{co} \text{ (11% O}_2\text{)} = C_{co} \text{ (mg/Rcm)} \times (20.9 - 11) / (20.9 - C_{o2})$	1247.81	1947.28	2116.19	1770.43
Corrected to 3% O ₂	C_{co}	mg/Rcm	$C_{co} \text{ (3% O}_2\text{)} = C_{co} \text{ (mg/Rcm)} \times (20.9 - 3) / (20.9 - C_{o2})$	2256.14	3520.83	3826.24	3201.07
Corrected to 12% CO ₂	C_{co}	mg/Rcm	$C_{co} \text{ (12% CO}_2\text{)} = C_{co} \text{ (mg/Rcm)} \times (12 / C_{co2})$	1556.70	2432.37	2635.78	2208.26
Particulate Concentration	C_p	mg/Rcm	$C_p = M_p / V_{mc}$	1389.56	1486.91	1265.99	1374.15
Particulate Emission Rate	ER_p	g/s kg/hr	$ER_p = C_p / 1000 \times Q_d$ $ER_p \text{ (kg/hr)} = 3.6 \times ER_p \text{ (g/s)}$	114.11 410.78	131.79 474.44	103.49 372.58	116.46 419.27
Particulate Concentration							
Corrected to 11% O ₂	C_p	mg/Rcm	$C_p \text{ (11% O}_2\text{)} = C_p \times (20.9 - 11) / (20.9 - C_{o2})$	842.15	897.58	758.94	832.89
Corrected to 3% O ₂	C_p	mg/Rcm	$C_p \text{ (3% O}_2\text{)} = C_p \times (20.9 - 3) / (20.9 - C_{o2})$	1522.68	1822.90	1372.22	1505.93
Corrected to 12% CO ₂	C_p	mg/Rcm	$C_p \text{ (12% CO}_2\text{)} = C_p \times (12 / C_{co2})$	1050.62	1121.19	945.27	1038.03

Legend: sq ft - square feet
 sq m - square metres
 Pi - 3.142
 R - degrees Rankin
 ppm - parts per million

in Hg - inches of mercury
 cu ft - cubic feet
 cu m - cubic metres
 Ref Cond - reference temperature and pressure (25 C and 101.3 kPa)
 Rcms - dry reference cubic metres per second
 Rcfm - dry reference cubic feet per minute

mg/Rcm - milligrams per dry reference cubic metre
 g/s - grams per second
 NO_x - as NO₂
 scfm - actual cubic feet per minute

OFFICIAL STACK TESTING RESULTS

Northern Pulp

Pictou, NS

Fuel: Fuel oil

Operating Conditions: Normal

Emission Control Equipment: wet scrubber

Stack Height from Grade: 69 m

Stack Diameter: 3.51 m

Parameter	Test 1	Test 2	Test 3	Average	0 Limits
Test ID	PM-1	PM-2	PM-3	-	-
Test Date	10-Mar-15	10-Mar-15	11-Mar-15	-	-
Stack Gas Temperature (C)	67.6	67.8	63.9	66.4	-
Moisture Content (%)	28.9	28.3	29.5	28.9	-
Velocity (m/s)	13.7	14.5	13.7	14.0	-
Volumetric Flow (Rcms)	83.3	88.6	81.7	84.6	-
Oxygen - O ₂ (%)	4.80	4.50	4.39	4.56	-
Carbon Dioxide - CO ₂ (%)	15.6	15.9	16.1	15.9	-
Sulphur Dioxide - SO ₂					
SO ₂ Measured Concentration (ppm)	8.14	6.14	27.9	14.0	-
SO ₂ Concentration at 11% O ₂ (mg/Rcm)	13.1	9.72	43.8	22.2	-
Emission Rate (kg/hr)	6.40	5.14	21.48	11.00	-
Nitrogen Oxides - NO _x					
NO _x Measured Concentration (ppm)	23.7	46.1	52.1	40.7	-
NO _x Concentration at 11% O ₂ (mg/Rcm)	27.4	52.4	58.8	46.2	-
Emission Rate (kg/hr)	13.4	27.7	28.9	23.3	-
Carbon Monoxide - CO					
CO Measured Concentration (ppm)	1772	2817	3083	2558	-
CO Concentration at 11% O ₂ (mg/Rcm)	1248	1947	2116	1770	-
Emission Rate (kg/hr)	609	1029	1039	892	-
Particulate Matter - PM					
Particulate Concentration at 11% O ₂ (mg/Rcm)	842	898	759	833	375
Particulate Emission Rate (kg/hr)	411	474	373	419	-

Legend: C - degrees Celsius
m/s - metres per second
Rcms - dry reference cubic metres per second
ppm - parts per million

Ref Cond - reference temperature and pressure (25 C and 101.3 kPa)
mg/Rcm - milligrams per dry reference cubic metre
NO_x - as NO₂
ND - non-detectable

Particulate Recoveries: Impinger Catch, Probe Wash, Filter Catch

Client: Hopton Pulp
 Facility: Recovery Boiler
 Location: Plant 165
 Job Number: 121413456

IMPINGER CATCH

Container ID	Beaker Pre Weights (g)				Sample ID	Recoveries				Beaker Post Weights (g)				Uncorrected Particulate Weight (g)	Corrected Particulate Weight (g)
	Date Analyzed by					Jar + Sample + Rinse (g)	Jar Time (s)	Sample Collected (g)	Rinse Water (g)	Total Rinse Water (g)	Date Analyzed by				
	Trial 1	Trial 2	Trial 3	Average							Trial 1	Trial 2	Trial 3	Average	
E1	110 0890	110 0895			PM-1	1018.6	308.1	540.1	4.1	94.5	110 0715	110 0715		0.0022	0.0019
W5	112 8650	112 8655			PM-2	1019.7	308.5	541.6	5.1	94.7	112 8702	112 8700		0.0049	0.0045
C5	111 9711	111 9712			PM-3	1019.2	458.9	540.6	4.0	65.7	111 9749	111 9745		0.0036	0.0033
															Conc. (g/m ³)
H3	109 2005	109 2006			WB	608.6	455.1	151.5		153.5	109 2010	109 2011		0.0005	0.000033

PROBE WASH

Container ID	Beaker Pre Weights (g)				Sample ID	Recoveries				Beaker Post Weights (g)				Uncorrected Particulate Weight (g)	Corrected Particulate Weight (g)
	Date					Jar + Acetone (g)	Jar Time (s)	Recovered Acetone (g)	Rinse Acetone (g)	Total Acetone (g)	Date				
	Trial 1	Trial 2	Trial 3	Average							Total 1	Total 2	Total 3	Average	
S1	109.1753	109.1754			PM-1	418.8	324.8	95.1	42.2	137.3	109.8076	109.8076	0.7323	0.7308	
O3	111.5652	111.5650			PM-2	416.3	324.6	91.7	35.7	127.4	112.7480	112.7484	1.1541	1.1526	
V1	111.8278	111.8279			PM-3	408.8	301.1	105.7	32.6	138.3	112.6438	112.6440	0.7160	0.7146	
															Conc. (g/mL)
X4	112.2864	112.2865			AB	383.2	324.9	68.3		68.3	112.2864	112.28	0.0007	0.000038	

Density of Acetone: 0.7850 g/ml

FILTER CATCH

Filter ID	Pre Weights (g)				Sample ID	Post Weights (g)				Particulate Weight from Filter (g)
	Analyzed by Date:					Analyzed by Date:				
	Trial 1	Trial 2	Trial 3	Average		Trial 1	Trial 2	Trial 3	Average	
2001-16	0.4134	0.4130		0.4132	PM-1	2.1566	2.1568		2.1567	1.7434
0226-17	0.3524	0.3521		0.3523	PM-2	1.9745	1.9785		1.9745	1.6283
0226-18	0.3510	0.3514		0.3512	PM-3	1.8564	1.8564		1.8564	1.5652

Stack Gas Velocity Profiles
Pictou, NS

