



1




2

Excavate diversion channel leaving earth plugs at both ends. Line diversion channel with plastic or Type A or B gravel depending on stream velocity.




3

Open downstream plug and allow water pressure to equalize in stream diversion. Some sedimentation will occur.





4

Open upstream plug and allow water to flow through both existing stream channel and new stream diversion. Some sedimentation will occur.




5

Immediately place a non-erodible dam in the upstream end of the existing channel.




6

Immediately install a non-erodible dam downstream to prevent backflow into the construction site. Rescue all fish from the dammed portion of the watercourse. Pumped water must be filtered through vegetation or a filter bag prior to re-entering a live stream. Alternatively, construct a de-watering basin (16 X gal/min. = cu. ft. of storage) to pump out the existing creek.




7

Construct drainage structure. Complete all channel work.




8

Remove de-watering basin. Remove downstream dam.




9

Remove upstream dam. Fill in downstream and upstream ends of temporary stream diversion with non-erodible material.



10

Fill in remainder of stream diversion. Stabilize. Construct Roadway



REV	DATE	DESCRIPTION	DATE	BY	CHECKED BY	DATE
AS NOTED	MARCH 2001	NOVA SCOTIA DEPARTMENT OF TRANSPORTATION AND PUBLIC WORKS ENVIRONMENTAL PROTECTION PLAN				
VARIOUS	VARIOUS	VARIOUS				
VARIOUS	VARIOUS	VARIOUS				
PROJECT NUMBER	TV20007	Task 0003	DATE	REV		
CHECKED BY	TV20007	Task 0003	DATE	REV		
APPROVED (PROJECT)			DATE	REV		
APPROVED (DESIGN)			DATE	REV		
AMEC Earth & Environmental Ltd.						